

GEORGIA DEPARTMENT OF TRANSPORTATION

GDOT Project No: NH000-0073-03(242)

PI No: 714130

JBT Project No. 255717

Bridge No. 31
I-75 REVERSIBLE OVER NOONDAY CREEK

November, 2009

COBB COUNTY

DESIGN CALCULATIONS

Note 1: Georgia Department of Transportation (GDOT) terminated Contract Number TOURDPPI60072 for its convenience prior to the completion of all work under that contract and directed that the work with respect to these calculations be discontinued.

(a) These calculations were not completed at the time of GDOT's direction and the information contained herein is not complete and/or has not been fully verified or checked. These calculations are a work-in-progress and are presented only as such.

(b) Any user is cautioned that the use of these calculations and any related information or calculations, without access to pertinent factors and without proper regard for their purpose, could lead to erroneous conclusions.

(c) If any such calculations or any information contained herein is used in future work efforts or any follow on design work activity, a complete confirmation of the information contained herein should be performed prior to any such use.

(d) GTP has no responsibility for the use of this information not under its direct control.

Prepared for Georgia Transportation Partners
Atlanta, Georgia



Purpose of Calculation

Bridge design calculations for Bridge #31 were made for costing purposes.

1. Specifications and References

AASHTO 17th Edition, 2002

GDOT Bridge Design Manual, 2008

2. Computer

Computer Type Used: PC

Operating System: Windows XP, Pentium 4, 2GB RAM (min.)

3. Computer Programs (Standard Computer Program)

Excel, Microsoft Office 2003 – JBT Calculation Spreadsheets

BRLLCA, 2008 – Live Load Case Program, by GDOT

BRPIER, 2008 – Pier Design and Analysis, by GDOT

BRSPAN, 2008 – Simple Beam Design and Analysis, by GDOT

CALCULATION COVER SHEET

PROJECT	JOB NO.	CALC NO.	SHEET
I-75 / I-575 NORTHWEST CORRIDOR	NH000-0073-03(242)	BR#31	1
SUBJECT	DISCIPLINE		
Slab Design	STRUCTURAL		

CALCULATION STATUS DESIGNATION	PRELIMINARY	CONFIRMED	SUPSEDED	VOIDED	INCOMPLETE
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

COMPUTER PROGRAM/TYPE	SCP	MAINFRAME	PC	PROGRAM	VERSION/RELEASE NO.
	<input checked="" type="radio"/> YES <input type="radio"/> NO	<input type="radio"/>	<input checked="" type="radio"/>	Excel	2003

Note 1: Georgia Department of Transportation (GDOT) terminated Contract Number TOURDPP160072 for its convenience prior to the completion of all work under that contract and directed that the work with respect to these calculations be discontinued.

(a) These calculations were not completed at the time of GDOT's direction and the information contained herein is not complete and/or has not been fully verified or checked. These calculations are a work-in-progress and are presented only as such.

(b) Any user is cautioned that the use of these calculations and any related information or calculations, without access to factors and without proper regard for their purpose, could lead to erroneous conclusions.

(c) If any such calculations or any information contained herein is used in future work efforts or any follow on design work activity, a complete confirmation of the information contained herein should be performed prior to any such use.

(d) GTP has no responsibility for the use of this information not under its direct control.

Slab Design calculations are included for spans 1, 2 and 3.

A	As per GDOT's termination for convenience direction	12	12	JCR			11/30/09
NO.	REASON FOR REVISION	TOTAL NO. OF SHEETS	LAST SHEET NO.	BY	CHECKED	APPROVED/ ACCEPTED	DATE
RECORD OF REVISIONS							

CALCULATION SHEET

PROJECT: I-75 / I-575 NORTHWEST CORRIDOR
JOB NUMBER NH000-0073-03(242)
CALC NO. BR#31

SUBJECT: Slab Design
BY: JCR DATE: 11/30/2009

SHEET NO.
SHEET REV.

Sufficient sample calculations representative of the scope and conditions in the design calculation were performed and the results compared to demonstrate the computer program adequacy.

BRIDGE: I-75 over Noonday Creek
COUNTY: COBB
P.I. NO: 713640
PROJECT: NH000-0575-01(028)

J.B. TRIMBLE, INC.



SPAN 1

JOB NO: 31-6036
DESIGNED BY: SHG
DATE: 10/14/2009

PSG
10/21/09

PRELIMINARY INFORMATION

INTERMEDIATE SLAB THICKNESS = 8.125 IN
OVERHANG SLAB THICKNESS = 8.125 IN
GIRDER SPACING = 7.500 FT
NUMBER OF GIRDERS = 5
OVERHANG WIDTH = 3.000 FT
TOP FLANGE WIDTH = 12.000 IN
CONCRETE STRENGTH, f_c = 3500 PSI
STEEL STRENGTH, f_y = 60000 PSI
PARAPET HEIGHT = 2.667 FT
PARAPET WIDTH = 1.625 FT
PARAPET AREA = 2.700 SF
C.G. FROM OUTSIDE = 0.667 FT
TOP BAR CLEARANCE = 2.750 IN
BOTTOM BAR CLEARANCE = 1.000 IN
GROOVED DEPTH = 0.250 IN
DESIGN SPEED = 50.00 MPH (IF CENTRIFUGAL CONSIDERED)
RADIUS = 0.00 FT (IF CENTRIFUGAL CONSIDERED)
WHEEL LOAD = 16.00 KIPS
IMPACT FACTOR = 1.30
ADDITIONAL LOAD = 30.00 PSF
RAILING LOAD = 10.00 KIP
HS20
AT TOP OF PARAPET

BAR DETAILS		
SIZE	AREA	WEIGHT
Not Needed	0	0
No. 3	0.11	0.376
No. 4	0.20	0.668
No. 5	0.31	1.043
No. 6	0.44	1.502
No. 7	0.60	2.044
No. 8	0.79	2.670
No. 9	1.00	3.400
No. 10	1.27	4.300
No. 11	1.56	5.310
No. 14	2.25	7.650
No. 18	4.00	13.600

INTERMEDIATE SLAB DESIGN

BEAM TYPE: STEEL (TB, STEEL, PSC, BULB-T)

EFFECTIVE SPAN LENGTH = 7.000 FT

AASHTO 3.24.1.2

DEAD LOAD

SLAB D.L. = 0.102 KIP/FT/LF
ADDITIONAL D.L. = 0.030 KIP/FT/LF
TOTAL D.L. = 0.132 KIP / FT / LF

$$\text{DEAD LOAD MOMENT} = 1.3 * (\text{WT DL}) * (\text{SPAN})^2 / 10 = 0.838 \text{ KIP-FT / LF}$$

LIVE LOAD

WHEEL LOAD = 16.00 KIPS
CONT. FACTOR = 0.80
IMPACT = 1.30

$$\text{LIVE LOAD MOMENT} = 2.17 * ((S + 2)/32) * P(LL + I) * 0.8 = 10.156 \text{ KIP-FT / LF}$$

AASHTO 3.24.3.1

CENTRIFUGAL LOAD

$$C = 6.68 * S^2 / R = 0.000 \text{ FRACTION OF LIVE LOAD}$$

AASHTO 3.10.1

$$\text{CENTRIFUGAL FORCE MOMENT} = 1.3 * ((S + 2)/32) * P(LL + I) * 0.8 * C = 0.000 \text{ KIP-FT / LF}$$

AASHTO TABLE 3.22.1A

$$\text{TOTAL DESIGN MOMENT } (\phi M_u) = 10.994 \text{ KIP-FT / LF} = 131.92 \text{ K-IN / LF}$$

FLEXURE STRENGTH

AASHTO 8.16.3.2

$$\phi M_n > M_u \quad \phi = 0.90$$

$$\phi M_n = \phi * [A_s * f_y * (d - a/2)] \quad \text{where } a = A_s * f_y / [0.85 * f_c * b]$$

$a = 1.681$ As
 $d_{top} = 5.063$ IN USE 5 BAR As = 0.31 IN²/LF
 $d_{bot} = 6.563$ IN USE 5 BAR As = 0.31 IN²/LF

TOP STEEL

$$273.375 \text{ As} - 45.38 \text{ As}^2 = 131.92 \text{ K-IN / LF}$$

TOP BAR = NO. 5 SPACED AT 6.250 IN As = 0.60 IN²/LF

$$\phi M_n = 146.64 \text{ K-IN / LF} \geq \phi M_u = 131.92 \text{ K-IN / LF} \quad \text{OK}$$

BOTTOM STEEL

$$354.375 \text{ As} - 45.38 \text{ As}^2 = 131.92 \text{ K-IN / LF}$$

BOT BAR = NO. 5 SPACED AT 6.250 IN As = 0.60 IN²/LF

$$\phi M_n = 194.85 \text{ K-IN / LF} \geq \phi M_u = 131.92 \text{ K-IN / LF} \quad \text{OK}$$

BRIDGE: I-75 over Noonday Creek
COUNTY: COBB
P.I. NO: 713640
PROJECT: NH000-0575-01(028)

J.B. TRIMBLE, INC.



SPAN 1

JOB NO: 31-6036
DESIGNED BY: SHG
DATE: 10/14/2009

OVERHANG SLAB DESIGN

EFFECTIVE SPAN LENGTH = 2.500 FT

AASHTO 3.24.5.1

DEAD LOAD

SLAB D.L. = 0.102 KIP/FT/LF
ADDITIONAL D.L. = 0.030 KIP/FT/LF
PARAPET D.L. = 0.405 KIP/FT/LF

DL MOMENT @ FLANGE:

SLAB MOM = 0.317 KIP-FT/LF
ADD'L MOM = 0.011 KIP-FT/LF
PARAPET MOM = 0.743 KIP-FT/LF

TOTAL MOM = 1.071 KIP-FT/LF

DL MOMENT @ EDGE OF BARRIER:

SLAB MOM = 0.134 KIP-FT/LF
ADD'L MOM = 0.000 KIP-FT/LF
PARAPET MOM = 0.388 KIP-FT/LF

TOTAL MOM = 0.522 KIP-FT/LF

DEAD LOAD MOMENT @ FLANGE = 1.3 * TOTAL MOMENT = 1.393 KIP-FT / LF

D.L. MOMENT @ EDGE OF BARRIER = 1.3 * TOTAL MOMENT = 0.679 KIP-FT / LF

LIVE LOAD

WHEEL LOAD 16.00 KIPS

IMPACT = 1.30
MOM ARM (X) = 0.38 FT
E = 0.8 * X + 3.75 = 4.05 FT

LIVE LOAD MOMENT = 2.17 * (P(LL + I) / E) * X = 4.179 KIP-FT / LF

AASHTO 3.24.5.1.1

CENTRIFUGAL LOAD

C = 6.68 * S² / R = 0.000 FRACTION OF LIVE LOAD

CENTRIFUGAL FORCE MOMENT = 1.3 * (P(LL + I) / E) * X * C = 0.000 KIP-FT / LF

RAILING LOAD

RAILING LOAD = 10.00 KIPS

AASHTO 3.24.5.2

RAILING LOAD @ FLANGE:

MOM ARM (H) = 3.118 FT
DISTANCE (X) = 1.83 FT
E = 0.8 * X + 5.00 = 6.47 FT

RAILING LOAD @ EDGE OF BARRIER:

MOM ARM (H) = 3.12 FT
DISTANCE (X) = 0.96 FT
E = 0.8 * X + 5.00 = 5.77 FT

RAIL MOM @ FLANGE = 2.17 * (P_{rail} / E) * H = 10.463 KIP-FT / LF

RAIL MOM @ EDGE OF BARRIER = 2.17 * (P_{rail} / E) * H = 11.733 KIP-FT / LF

SUMMARY OF MOMENTS:

DL + LL @ FLANGE = 5.572 KIP-FT / LF

DL + RAIL @ FLANGE = 11.856 KIP-FT / LF

DL + RAIL @ BARRIER = 12.412 KIP-FT / LF

TOTAL DESIGN MOMENT (φ Mu) = 12.412 KIP-FT / LF = 148.95 K-IN / LF

FLEXURE STRENGTH

AASHTO 8.16.3.2

φ Mn > Mu

φ = 0.90

φ Mn = φ * [As * fy * (d - a/2)] where a = As * fy / [0.85 * f'c * b]

a = 1.681 As

d_{top} = 5.063 IN

USE 5 BAR

As = 0.31 IN² / LF

PROVIDE ADDITIONAL OVERHANG STEEL = 4 BAR

As = 0.20 IN² / LF

TOP STEEL

273.375 As - 45.38 As² = 148.95 K-IN / LF

TOP BAR = NO. 5 SPACED AT 6.250 IN As = 0.60 IN² / LF

φ Mn = 146.64 K-IN / LF < φ Mu = 148.95 K-IN / LF ADD. REINF. NEEDED!!

ADD'L BAR = NO. 4 SPACED AT 12.50 IN As = 0.19 IN² / LF

Mn = 187.08 K-IN / LF ≥ Mu = 148.95 K-IN / LF OK

BRIDGE: I-75 over Noonday Creek
COUNTY: COBB
P.I. NO: 713640
PROJECT: NH000-0575-01(028)

J.B. TRIMBLE, INC.



SPAN 2

JOB NO: 31-6036
DESIGNED BY: SHG
DATE: 10/14/2009

PTC
10/21/09

PRELIMINARY INFORMATION

INTERMEDIATE SLAB THICKNESS = 8.250 IN
OVERHANG SLAB THICKNESS = 8.250 IN
GIRDER SPACING = 8.000 FT
NUMBER OF GIRDERS = 5
OVERHANG WIDTH = 3.000 FT
TOP FLANGE WIDTH = 12.000 IN
CONCRETE STRENGTH, f_c = 3500 PSI
STEEL STRENGTH, f_y = 60000 PSI
PARAPET HEIGHT = 2.667 FT
PARAPET WIDTH = 1.625 FT
PARAPET AREA = 2.700 SF
C.G. FROM OUTSIDE = 0.667 FT
TOP BAR CLEARANCE = 2.750 IN
BOTTOM BAR CLEARANCE = 1.000 IN
GROOVED DEPTH = 0.250 IN
DESIGN SPEED = 50.00 MPH (IF CENTRIFUGAL CONSIDERED)
RADIUS = 0.00 FT (IF CENTRIFUGAL CONSIDERED)
WHEEL LOAD = 16.00 KIPS
IMPACT FACTOR = 1.30
ADDITIONAL LOAD = 30.00 PSF
RAILING LOAD = 10.00 KIP

AT TOP OF PARAPET

BAR DETAILS		
SIZE	AREA	WEIGHT
Not Needed	0	0
No. 3	0.11	0.376
No. 4	0.20	0.668
No. 5	0.31	1.043
No. 6	0.44	1.502
No. 7	0.60	2.044
No. 8	0.79	2.670
No. 9	1.00	3.400
No. 10	1.27	4.300
No. 11	1.56	5.310
No. 14	2.25	7.650
No. 18	4.00	13.600

INTERMEDIATE SLAB DESIGN

BEAM TYPE: STEEL (TB, STEEL, PSC, BULB-T)

EFFECTIVE SPAN LENGTH = 7.500 FT

AASHTO 3.24.1.2

DEAD LOAD

SLAB D.L. = 0.103 KIP/FT/LF
ADDITIONAL D.L. = 0.030 KIP/FT/LF
TOTAL D.L. = 0.133 KIP / FT / LF

$$\text{DEAD LOAD MOMENT} = 1.3 * (\text{WT DL}) * (\text{SPAN})^2 / 10 = 0.973 \text{ KIP-FT / LF}$$

LIVE LOAD

WHEEL LOAD = 16.00 KIPS
CONT. FACTOR = 0.80
IMPACT = 1.30

$$\text{LIVE LOAD MOMENT} = 2.17 * ((S + 2)/32) * P(LL + I) * 0.8 = 10.720 \text{ KIP-FT / LF}$$

AASHTO 3.24.3.1

CENTRIFUGAL LOAD

$$C = 6.68 * S^2 / R = 0.000 \text{ FRACTION OF LIVE LOAD}$$

AASHTO 3.10.1

$$\text{CENTRIFUGAL FORCE MOMENT} = 1.3 * ((S + 2)/32) * P(LL + I) * 0.8 * C = 0.000 \text{ KIP-FT / LF}$$

AASHTO TABLE 3.22.1A

$$\text{TOTAL DESIGN MOMENT } (\phi M_u) = 11.693 \text{ KIP-FT / LF} = 140.32 \text{ K-IN / LF}$$

FLEXURE STRENGTH

AASHTO 8.16.3.2

$$\phi M_n > M_u \quad \phi = 0.90$$

$$\phi M_n = \phi * [A_s * f_y * (d - a/2)] \text{ where } a = A_s * f_y / [0.85 * f'_c * b]$$

$a = 1.681$ As
 $d_{top} = 5.188$ IN USE 5 BAR As = 0.31 IN² / LF
 $d_{bot} = 6.688$ IN USE 5 BAR As = 0.31 IN² / LF

TOP STEEL

$$280.125 \text{ As} - 45.38 \text{ As}^2 = 140.32 \text{ K-IN / LF}$$

TOP BAR = NO. 5 SPACED AT 6.000 IN As = 0.62 IN² / LF

$$\phi M_n = 156.23 \text{ K-IN / LF} \geq \phi M_u = 140.32 \text{ K-IN / LF} \text{ OK}$$

BOTTOM STEEL

$$361.125 \text{ As} - 45.38 \text{ As}^2 = 140.32 \text{ K-IN / LF}$$

BOT BAR = NO. 5 SPACED AT 6.000 IN As = 0.62 IN² / LF

$$\phi M_n = 206.45 \text{ K-IN / LF} \geq \phi M_u = 140.32 \text{ K-IN / LF} \text{ OK}$$

BRIDGE: I-75 over Noonday Creek
COUNTY: COBB
P.I. NO: 713640
PROJECT: NH000-0575-01(028)

J.B. TRIMBLE, INC.



SPAN 2

JOB NO: 31-6036
DESIGNED BY: SHG
DATE: 10/14/2009

OVERHANG SLAB DESIGN

EFFECTIVE SPAN LENGTH = 2.500 FT

AASHTO 3.24.5.1

DEAD LOAD

SLAB D.L. = 0.103 KIP/FT/LF
ADDITIONAL D.L. = 0.030 KIP/FT/LF
PARAPET D.L. = 0.405 KIP/FT/LF

DL MOMENT @ FLANGE:

SLAB MOM = 0.322 KIP-FT/LF
ADD'L MOM = 0.011 KIP-FT/LF
PARAPET MOM = 0.743 KIP-FT/LF

TOTAL MOM = 1.076 KIP-FT/LF

DL MOMENT @ EDGE OF BARRIER:

SLAB MOM = 0.136 KIP-FT/LF
ADD'L MOM = 0.000 KIP-FT/LF
PARAPET MOM = 0.388 KIP-FT/LF

TOTAL MOM = 0.524 KIP-FT/LF

DEAD LOAD MOMENT @ FLANGE = $1.3 \times \text{TOTAL MOMENT} = 1.399$ KIP-FT / LF
D.L. MOMENT @ EDGE OF BARRIER = $1.3 \times \text{TOTAL MOMENT} = 0.682$ KIP-FT / LF

LIVE LOAD

WHEEL LOAD 16.00 KIPS

IMPACT = 1.30
MOM ARM (X) = 0.38 FT
 $E = 0.8 \times X + 3.75 = 4.05$ FT

LIVE LOAD MOMENT = $2.17 \times (P(LL + I) / E) \times X = 4.179$ KIP-FT / LF

AASHTO 3.24.5.1.1

CENTRIFUGAL LOAD

$C = 6.68 \times S^2 / R = 0.000$ FRACTION OF LIVE LOAD

CENTRIFUGAL FORCE MOMENT = $1.3 \times (P(LL + I) / E) \times X \times C = 0.000$ KIP-FT / LF

RAILING LOAD

RAILING LOAD = 10.00 KIPS

AASHTO 3.24.5.2

RAILING LOAD @ FLANGE:

MOM ARM (H) = 3.125 FT
DISTANCE (X) = 1.83 FT
 $E = 0.8 \times X + 5.00 = 6.47$ FT

RAILING LOAD @ EDGE OF BARRIER:

MOM ARM (H) = 3.13 FT
DISTANCE (X) = 0.96 FT
 $E = 0.8 \times X + 5.00 = 5.77$ FT

RAIL MOM @ FLANGE = $2.17 \times (P_{rail} / E) \times H = 10.486$ KIP-FT / LF

RAIL MOM @ EDGE OF BARRIER = $2.17 \times (P_{rail} / E) \times H = 11.759$ KIP-FT / LF

SUMMARY OF MOMENTS:

DL + LL @ FLANGE = 5.578 KIP-FT / LF
DL + RAIL @ FLANGE = 11.886 KIP-FT / LF
DL + RAIL @ BARRIER = 12.441 KIP-FT / LF

TOTAL DESIGN MOMENT (ϕMu) = 12.441 KIP-FT / LF

FLEXURE STRENGTH

AASHTO 8.16.3.2

$\phi Mn > Mu$

$\phi = 0.90$

$\phi Mn = \phi \times [As \times fy \times (d - a/2)]$ where $a = As \times fy / [0.85 \times fc \times b]$

$a = 1.681$ As
 $d_{top} = 5.188$ IN

USE 5 BAR

As = 0.31 IN² / LF

TOP STEEL

280.125 As - 45.38 As² = 149.29 K-IN / LF

TOP BAR = NO. 5 SPACED AT 6.000 IN As = 0.62 IN² / LF

$\phi Mn = 156.23$ K-IN / LF $\geq \phi Mu = 149.29$ K-IN / LF OK

BRIDGE: I-75 over Noonday Creek
COUNTY: COBB
P.I. NO: 713640
PROJECT: NH000-0575-01(028)

J.B. TRIMBLE, INC.



SPAN 3

JOB NO: 31-6036
DESIGNED BY: SHG
DATE: 10/14/2009

PSC
10/21/09

PRELIMINARY INFORMATION

INTERMEDIATE SLAB THICKNESS = 8.500 IN
OVERHANG SLAB THICKNESS = 8.500 IN
GIRDER SPACING = 8.500 FT
NUMBER OF GIRDERS = 5
OVERHANG WIDTH = 3.000 FT
TOP FLANGE WIDTH = 12.000 IN
CONCRETE STRENGTH, f_c = 3500 PSI
STEEL STRENGTH, f_y = 60000 PSI
PARAPET HEIGHT = 2.667 FT
PARAPET WIDTH = 1.625 FT
PARAPET AREA = 2.700 SF
C.G. FROM OUTSIDE = 0.667 FT
TOP BAR CLEARANCE = 2.750 IN
BOTTOM BAR CLEARANCE = 1.000 IN
GROOVED DEPTH = 0.250 IN
DESIGN SPEED = 50.00 MPH (IF CENTRIFUGAL CONSIDERED)
RADIUS = 0.00 FT (IF CENTRIFUGAL CONSIDERED)
WHEEL LOAD = 16.00 KIPS HS20
IMPACT FACTOR = 1.30
ADDITIONAL LOAD = 30.00 PSF
RAILING LOAD = 10.00 KIP AT TOP OF PARAPET

BAR DETAILS		
SIZE	AREA	WEIGHT
Not Needed	0	0
No. 3	0.11	0.376
No. 4	0.20	0.668
No. 5	0.31	1.043
No. 6	0.44	1.502
No. 7	0.60	2.044
No. 8	0.79	2.670
No. 9	1.00	3.400
No. 10	1.27	4.300
No. 11	1.56	5.310
No. 14	2.25	7.650
No. 18	4.00	13.600

INTERMEDIATE SLAB DESIGN

BEAM TYPE: STEEL (TB, STEEL, PSC, BULB-T)

EFFECTIVE SPAN LENGTH = 8.000 FT

AASHTO 3.24.1.2

DEAD LOAD

SLAB D.L. = 0.106 KIP/FT/LF
ADDITIONAL D.L. = 0.030 KIP/FT/LF
TOTAL D.L. = 0.136 KIP / FT / LF

$$\text{DEAD LOAD MOMENT} = 1.3 \cdot (\text{WT DL}) \cdot (\text{SPAN})^2 / 10 = 1.134 \text{ KIP-FT / LF}$$

LIVE LOAD

WHEEL LOAD = 16.00 KIPS
CONT. FACTOR = 0.80
IMPACT = 1.30

$$\text{LIVE LOAD MOMENT} = 2.17 \cdot ((S + 2)/32) \cdot P(LL + I) \cdot 0.8 = 11.284 \text{ KIP-FT / LF}$$

AASHTO 3.24.3.1

CENTRIFUGAL LOAD

$$C = 6.68 \cdot S^2 / R = 0.000 \text{ FRACTION OF LIVE LOAD}$$

AASHTO 3.10.1

$$\text{CENTRIFUGAL FORCE MOMENT} = 1.3 \cdot ((S + 2)/32) \cdot P(LL + I) \cdot 0.8 \cdot C = 0.000 \text{ KIP-FT / LF}$$

AASHTO TABLE 3.22.1A

$$\text{TOTAL DESIGN MOMENT } (\phi M_u) = 12.418 \text{ KIP-FT / LF} = 149.01 \text{ K-IN / LF}$$

FLEXURE STRENGTH

AASHTO 8.16.3.2

$$\phi M_n > M_u \quad \phi = 0.90$$

$$\phi M_n = \phi \cdot [A_s \cdot f_y \cdot (d - a/2)] \quad \text{where } a = A_s \cdot f_y / [0.85 \cdot f_c \cdot b]$$

$a = 1.681$ As
 $d_{top} = 5.438$ IN USE 5 BAR As = 0.31 IN²/LF
 $d_{bot} = 6.938$ IN USE 5 BAR As = 0.31 IN²/LF

TOP STEEL

$$293.625 \text{ As} - 45.38 \text{ As}^2 = 149.01 \text{ K-IN / LF}$$

TOP BAR = NO. 5 SPACED AT 5.875 IN As = 0.63 IN²/LF

$$\phi M_n = 167.73 \text{ K-IN / LF} \geq \phi M_u = 149.01 \text{ K-IN / LF} \quad \text{OK}$$

BOTTOM STEEL

$$374.625 \text{ As} - 45.38 \text{ As}^2 = 149.01 \text{ K-IN / LF}$$

BOT BAR = NO. 5 SPACED AT 5.875 IN As = 0.63 IN²/LF

$$\phi M_n = 219.02 \text{ K-IN / LF} \geq \phi M_u = 149.01 \text{ K-IN / LF} \quad \text{OK}$$

BRIDGE: I-75 over Noonday Creek
COUNTY: COBB
P.I. NO: 713640
PROJECT: NH000-0575-01(028)



JOB NO: 31-6036
DESIGNED BY: SHG
DATE: 10/14/2009

OVERHANG SLAB DESIGN

EFFECTIVE SPAN LENGTH = 2.500 FT

AASHTO 3.24.5.1

DEAD LOAD

SLAB D.L. = 0.106 KIP/FT/LF
ADDITIONAL D.L. = 0.030 KIP/FT/LF
PARAPET D.L. = 0.405 KIP/FT/LF

DL MOMENT @ FLANGE:

SLAB MOM = 0.332 KIP-FT/LF
ADD'L MOM = 0.011 KIP-FT/LF
PARAPET MOM = 0.743 KIP-FT/LF

TOTAL MOM = 1.086 KIP-FT/LF

DL MOMENT @ EDGE OF BARRIER:

SLAB MOM = 0.140 KIP-FT/LF
ADD'L MOM = 0.000 KIP-FT/LF
PARAPET MOM = 0.388 KIP-FT/LF

TOTAL MOM = 0.528 KIP-FT/LF

DEAD LOAD MOMENT @ FLANGE = 1.3 * TOTAL MOMENT = 1.412 KIP-FT / LF
D.L. MOMENT @ EDGE OF BARRIER = 1.3 * TOTAL MOMENT = 0.687 KIP-FT / LF

LIVE LOAD

WHEEL LOAD 16.00 KIPS

IMPACT = 1.30
MOM ARM (X) = 0.38 FT
E = 0.8 * X + 3.75 = 4.05 FT

LIVE LOAD MOMENT = 2.17 * (P(LL + I) / E) * X = 4.179 KIP-FT / LF

AASHTO 3.24.5.1.1

CENTRIFUGAL LOAD

C = 6.68 * S^2 / R = 0.000 FRACTION OF LIVE LOAD

CENTRIFUGAL FORCE MOMENT = 1.3 * (P(LL + I) / E) * X * C = 0.000 KIP-FT / LF

RAILING LOAD

RAILING LOAD = 10.00 KIPS

RAILING LOAD @ FLANGE:

MOM ARM (H) = 3.139 FT
DISTANCE (X) = 1.83 FT
E = 0.8 * X + 5.00 = 6.47 FT

RAILING LOAD @ EDGE OF BARRIER:

MOM ARM (H) = 3.14 FT
DISTANCE (X) = 0.96 FT
E = 0.8 * X + 5.00 = 5.77 FT

RAIL MOM @ FLANGE = 2.17 * (P_{rail} / E) * H = 10.533 KIP-FT / LF

RAIL MOM @ EDGE OF BARRIER = 2.17 * (P_{rail} / E) * H = 11.612 KIP-FT / LF

AASHTO 3.24.5.2

SUMMARY OF MOMENTS:

DL + LL @ FLANGE = 5.591 KIP-FT / LF
DL + RAIL @ FLANGE = 11.945 KIP-FT / LF
DL + RAIL @ BARRIER = 12.499 KIP-FT / LF

TOTAL DESIGN MOMENT (Ø Mu) = 12.499 KIP-FT / LF

FLEXURE STRENGTH

AASHTO 8.16.3.2

Ø Mn > Mu

Ø = 0.90

Ø Mn = Ø * [As * fy * (d - a/2)] where a = As * fy / [0.85 * fc * b]

a = 1.681 As

d_{top} = 5.438 IN

USE 5 BAR

As = 0.31 IN^2 / LF

TOP STEEL

293.625 As - 45.38 As^2 = 149.98 K-IN / LF

TOP BAR = NO. 5 SPACED AT 5.875 IN As = 0.63 IN^2 / LF

Ø Mn = 167.73 K-IN / LF ≥ Ø Mu = 149.98 K-IN / LF OK

SERVICE LOAD DESIGN OF BRIDGE SLAB

Georgia Department of Transportation
Office of Bridge and Structural Design
October 2003

13-MAY-04
07:49:26

WHEEL LOAD (Kips)	fc (ksi)	fs (ksi)	n	SLAB COVER (in)	FUTURE PAVING (kips/ft ²)	CONTINUITY FACTOR
16.00	1.400	24.000	9	2.750	0.030	0.8
EFFECTIVE SPAN LENGTH (ft-in)	SLAB THICKNESS MINIMUM ACTUAL (in) (in)	SIZE AND SPACING OF MAIN REINFORCEMENT (in)	DISTRUBUTION REINFORCEMENT MIDDLE HALF	OUTER QUARTERS		
6 - 6	7.8889 8.000	# 5 at 6.500	7 -# 4	4 -# 4		
6 - 7	7.9167 8.000	# 5 at 6.375	7 -# 4	4 -# 4		
6 - 8	7.9445 8.000	# 5 at 6.375	7 -# 4	4 -# 4		
6 - 9	7.9722 8.000	# 5 at 6.250	7 -# 4	4 -# 4		
6 - 10	7.9998 8.000	# 5 at 6.250	7 -# 4	4 -# 4		
6 - 11	8.0309 8.125	# 5 at 6.250	7 -# 4	4 -# 4		
7 - 0	8.0585 8.125	# 5 at 6.250	7 -# 4	4 -# 4		
7 - 1	8.0860 8.125	# 5 at 6.125	8 -# 4	4 -# 4		
7 - 2	8.1134 8.125	# 5 at 6.125	8 -# 4	4 -# 4		
7 - 3	8.1446 8.250	# 5 at 6.125	8 -# 4	4 -# 4		
7 - 4	8.1719 8.250	# 5 at 6.125	8 -# 4	4 -# 4		
7 - 5	8.1992 8.250	# 5 at 6.000	8 -# 4	4 -# 4		
7 - 6	8.2265 8.250	# 5 at 6.000	8 -# 4	4 -# 4		
7 - 7	8.2577 8.375	# 5 at 6.000	8 -# 4	4 -# 4		
7 - 8	8.2849 8.375	# 5 at 6.000	8 -# 4	4 -# 4		
7 - 9	8.3121 8.375	# 5 at 5.875	9 -# 4	6 -# 4		
7 - 10	8.3392 8.375	# 5 at 5.875	9 -# 4	6 -# 4		
7 - 11	8.3662 8.375	# 5 at 5.750	9 -# 4	6 -# 4		
8 - 0	8.3976 8.500	# 5 at 5.875	9 -# 4	6 -# 4		
8 - 1	8.4246 8.500	# 5 at 5.750	9 -# 4	6 -# 4		
8 - 2	8.4515 8.500	# 5 at 5.750	9 -# 4	6 -# 4		
8 - 3	8.4784 8.500	# 5 at 5.625	9 -# 4	6 -# 4		
8 - 4	8.5099 8.625	# 5 at 5.750	9 -# 4	6 -# 4		
8 - 5	8.5367 8.625	# 5 at 5.625	10 -# 4	6 -# 4		
8 - 6	8.5636 8.625	# 5 at 5.625	10 -# 4	6 -# 4		
8 - 7	8.5903 8.625	# 5 at 5.500	10 -# 4	6 -# 4		
8 - 8	8.6170 8.625	# 5 at 5.500	10 -# 4	6 -# 4		
8 - 9	8.6487 8.750	# 5 at 5.625	10 -# 4	6 -# 4		
8 - 10	8.6754 8.750	# 5 at 5.500	10 -# 4	6 -# 4		
8 - 11	8.7020 8.750	# 5 at 5.500	11 -# 4	6 -# 4		
9 - 0	8.7286 8.750	# 5 at 5.375	11 -# 4	6 -# 4		
9 - 1	8.7605 8.875	# 5 at 5.500	11 -# 4	6 -# 4		
9 - 2	8.7871 8.875	# 5 at 5.375	11 -# 4	6 -# 4		
9 - 3	8.8136 8.875	# 5 at 5.375	11 -# 4	6 -# 4		
9 - 4	8.8401 8.875	# 5 at 5.375	11 -# 4	6 -# 4		
9 - 5	8.8665 8.875	# 5 at 5.250	12 -# 4	6 -# 4		

Span 1
7'-6"
-1'-0"
12' (12"/4)
7'-0" →

Span 2 →

Span 3 →

SECTION IV – CONCRETE AND REINFORCING STEEL

BRIDGE DECK DESIGN

No. 4.01

When designing bridge decks, the following criteria shall be applied:

For cast-in-place decks north of the fall line:

1. Specify Class AA concrete except for post-tensioned concrete boxes which shall have Class AA as a minimum, but may require a higher 28-day strength.
2. **Specify 2 ¾" (70 mm) cover to top bar reinforcement for bridge decks on interstate routes, state routes and routes with design year ADT equal to or greater than 2000.**
3. Specify 2 ½" (65 mm) cover to top bar reinforcement for bridge decks on all other routes.

For cast-in-place decks south of the fall line:

1. Specify Class AA concrete except for post-tensioned concrete boxes which shall have Class AA as a minimum, but may require a higher 28-day strength.
2. Specify 2 ¼" (60 mm) cover to top bar reinforcement for bridge decks on interstate routes, state routes and routes with design year ADT equal to or greater than 2000.
3. Specify 2" (50 mm) cover to top bar reinforcement for bridge decks on all other routes.

For bridge decks of precast concrete elements, specify 2" cover to top bar reinforcement statewide.

Note that ¼" of concrete thickness may be planed off of the top of cast-in-place decks on interstate routes, state routes and routes with design year ADT equal to or greater than 2000. Therefore, reduce slab thickness accordingly for strength calculations of composite slabs on steel or PSC beams and post-tensioned boxes.

Deck slabs shall be designed by the Service Load method with $f_c = 1400$ psi (10 MPa), as a rule.

The minimum 28 day strength (f'_c) for the deck concrete shall be 3500 psi (25 MPa). Slabs shall be designed so that the main slab reinforcement is the same in the bottom of the slab as in the top. To achieve this, the effective depth shall be taken as the distance from the bottom of the slab to the centroid of the top main reinforcing steel for both positive and negative moment. Positive and negative moments shall be assumed to be equal and shall be calculated in accordance with the AASHTO Specifications.

See Fig. 4-01 for a location map of the fall line for Georgia.



FALL LINE MAP
Figure 4-01






FIG. NO. 1 (cont'd)

CALCULATION COVER SHEET

PROJECT	JOB NO.	CALC NO.	SHEET
I-75 / I-575 NORTHWEST CORRIDOR	NH000-0073-03(242)	BR#31	1
SUBJECT	DISCIPLINE		
Beam Design Input	STRUCTURAL		

CALCULATION STATUS DESIGNATION	PRELIMINARY	CONFIRMED	SUPSEDED	VOIDED	INCOMPLETE
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

COMPUTER PROGRAM/TYPE	SCP	MAINFRAME	PC	PROGRAM	VERSION/RELEASE NO.
	<input checked="" type="radio"/> YES <input type="radio"/> NO	<input type="radio"/>	<input checked="" type="radio"/>	Excel	2003

Note 1: Georgia Department of Transportation (GDOT) terminated Contract Number TOURDPP160072 for its convenience prior to the completion of all work under that contract and directed that the work with respect to these calculations be discontinued.

(a) These calculations were not completed at the time of GDOT's direction and the information contained herein is not complete and/or has not been fully verified or checked. These calculations are a work-in-progress and are presented only as such.

(b) Any user is cautioned that the use of these calculations and any related information or calculations, without access to factors and without proper regard for their purpose, could lead to erroneous conclusions.

(c) If any such calculations or any information contained herein is used in future work efforts or any follow on design work activity, a complete confirmation of the information contained herein should be performed prior to any such use.

(d) GTP has no responsibility for the use of this information not under its direct control.

Beam Design Input calculations are included for span 1, and spans 2&3 (beams 1, 3 & 5).

A	As per GDOT's termination for convenience direction	9	9	JCR			11/30/09
NO.	REASON FOR REVISION	TOTAL NO. OF SHEETS	LAST SHEET NO.	BY	CHECKED	APPROVED/ ACCEPTED	DATE
RECORD OF REVISIONS							

CALCULATION SHEET

PROJECT: I-75 / I-575 NORTHWEST CORRIDOR
JOB NUMBER NH000-0073-03(242)
CALC NO. BR#31

SUBJECT: Beam Design Input - Span 1
BY: JCR DATE: 11/30/2009

SHEET NO.
SHEET REV.

Sufficient sample calculations representative of the scope and conditions in the design calculation were performed and the results compared to demonstrate the computer program adequacy.

BRIDGE: I-75 over Noonday Creek
COUNTY: COBB
P.I. NO: 713640
PROJECT: NH000-0575-01(028)

J.B. TRIMBLE, INC.



JOB NO: 31-6036
DESIGNED BY: SHG
DATE: 10/16/2009

SPAN 1

Beam Type

'D' DIMENSION = 9.75 IN
MIN. COPING DEPTH = 0.375 IN

AASHTO 8.10.1.1 - Compression Flange Width

wBM FLANGE = 12.00 in.
b = Bm Spacing = 90.00 in. CONTROLS
b = 1/4 Span Length = 234.75 in.
b = WBM FLANGE + 2[6 tSLAB] = 106.50 in.

BRIDGE GEOMETRY INPUT:

LARGER BEAM SPACING 7.500 FT
SMALLER BEAM SPACING 7.500 FT
SKEW ANGLE 90.00 DEGREES

SLAB:

'D' DIMENSION 9.75 IN
DESIGN SLAB DEPTH 7.875 IN
COPING WIDTH 1.000 FT
COPING DEPTH 1.125 IN
SLAB & COPING WEIGHT 0.752 KIP/FT
SIP FORMWORK 0.104 KIP/FT

DECK OVERLAY

AVERAGE THICKNESS 0.250 IN
DECK OVERLAY WEIGHT 0.023 KIP/FT
ROADWAY WIDTH 44.250 FT
FUTURE WEARING SURFACE 0.266 KIP/FT

UTILITIES

GAS MAIN (not added to W_{DL}) 0.00 KIP/FT
TLPHONE CONDUITS (not added to W_{DL}) 0.00 KIP/FT
WATER MAIN 0.00 KIP/FT

EDGE BEAM:

DEPTH (from top of slab) 2.31 FT
WIDTH 1.000 FT
EDGE BM. WEIGHT 1.863 KIP

DIAPHRAGM:

Plate (3/8" X 5" X 2'-8") 0.017 KIP
CHANNEL (MC 18" X 42.7") 0.043 KIP/FT
DIAPH. WEIGHT 0.353 KIP

END WALL:

DEPTH (from top of slab) 5.063 FT
WIDTH 0.667 FT
PAVING NOTCH WIDTH 0.667 FT
AVG. PAVING NOTCH DEPTH 0.833 FT
END WALL WEIGHT 3.932 KIP

PARAPET:

SW, PAR., FENCE, & MEDIAN WEIGHT 1.900 KIP/FT
NUMBER OF BEAMS 5
PARAPET WEIGHT 0.380 KIP/FT

SIDEWALK LIVE LOAD:

SIDEWALK WIDTH 0 FT
SIDEWALK LOAD 0.060 KIP/FT²
NUMBER OF BEAMS 5
SIDEWALK LIVE LOAD PER BEAM 0.000 KIP/FT

DEAD LOAD CALCULATION:

SPAN LENGTH 78.25 FT
BEAM WEIGHT 0.178 KLF

REACTION (K) MOMENT (K-FT)

TOTAL DL 1.703 KIP/LF 66.621 1303.280

P-LOADS:

TYPE	LOAD (K)	POSITION (FT)	REACTION (K)	MOMENT (K-FT)
END WALL:	3.932	0.00	3.932	0.000
DIAPHRAGM:	0.353	19.5625	0.265	5.181
DIAPHRAGM:	0.353	39.125	0.177	6.907
DIAPHRAGM:	0.353	58.6875	0.088	5.181
EDGE BEAM:	1.863	78.25	0.000	0.000

	REACTION (K)	MOMENT (K-FT)
TOTAL DL :	71.1	1320.5

LIVE LOAD CALCULATION:

BEAM DISTRIBUTION

MOMENT	WHEEL	VERIFY !!!!
1.364	AXLE	
0.682	AXLE	
SHEAR	WHEEL	VERIFY !!!!
1.667	AXLE	
0.833	AXLE	

IMPACT FACTOR

1.246

HS 20 LOADING:

MIDSPAN: 1128.5 KIP-FT
MAX: 1133.5 KIP-FT

HS 20 REACTION:

R x DF x I

TRUCK	LANE	KIP	KIP
63.41	51.04	59.91	48.27

	REACTION (K)	MOMENT (K-FT)
TOTAL LL+ I:	59.9	958.7
MAX TOTAL LL+ I:		963.0

	REACTION (K)	MOMENT (K-FT)
TOTAL D.L. + L.L. =	131.0	2279.3

DEFLECTIONS CALCULATION:

NO. LANES 3
NO. BEAMS 5
REDUCTION FACTOR 0.90 FACTOR 1.080

SIMPLE SPAN PROGRAM INPUT:

LENGTH = 78.25 FT
Moment Dist. Factor (DFM) = 1.364
End Shear Dist. Factor (DFV) = 1.667
LL Deflection Dist. Factor (DFD) = 1.080
Non- Composite DL (W_{DLNC}) = 0.880 KLF
Composite DL (W_{DLc}) = 0.646 KLF W/ F.W.S.
Sidewalk LL (W_{swk}) = 0.000 KLF
Effective Concrete Width (W_e) = 90.000 IN
Concrete Slab Thickness (T_s) = 7.875 IN
Minimum Coping (Df) = 0.750 IN
P-LOADS:
XP1 0.00 FT
P1 3.932 K
XP2 19.5625 FT
P2 0.353 K
XP3 39.125 FT
P3 0.353 K
XP4 58.6875 FT
P4 0.353 K
XP5 78.250 FT
P5 1.863 K

CALCULATION SHEET

PROJECT: I-75 / I-575 NORTHWEST CORRIDOR
JOB NUMBER NH000-0073-03(242)
CALC NO. BR#31


SUBJECT: Beam Design Input - Spans 2&3 (beam 1)
BY: JCR DATE: 11/30/2009

SHEET NO.
SHEET REV.

Sufficient sample calculations representative of the scope and conditions in the design calculation were performed and the results compared to demonstrate the computer program adequacy.

BRIDGE: I-75 over Noonday Creek
COUNTY: COBB
P.I. NO: 713640
PROJECT: NH000-0575-01(028)

J.B. TRIMBLE, INC.



JOB NO: 31-6036
DESIGNED BY: SHG
DATE: 10/16/2009

PSG 10-21-09

SPANS 2 & 3 (Beam 1)

Beam Type

'D' DIMENSION = 10.875 IN
MIN. COPING DEPTH = 0.375 IN

AASHTO 8.10.1.1 - Compression Flange Width

wBM FLANGE = 10.00 in.
b = 8m Spacing = 102.00 in. CONTROLS
b = 1/4 Span Length = 303.75 in.
b = WBM FLANGE + 2(6 tSLAB) = 109.00 in.

BRIDGE GEOMETRY INPUT:

LARGER BEAM SPACING	8.500	FT
SMALLER BEAM SPACING	8.500	FT
SKEW ANGLE	64.00	DEGREES
SLAB:		
'D' DIMENSION	10.875	IN
DESIGN SLAB DEPTH	8.250	IN
COPING WIDTH	0.833	FT
COPING DEPTH	1.5	IN
SLAB & COPING WEIGHT	0.892	KIP/FT
SIP FORMWORK	0.123	KIP/FT
DECK OVERLAY		
AVERAGE THICKNESS	0.250	IN
DECK OVERLAY WEIGHT	0.027	KIP/FT
ROADWAY WIDTH	48.000	FT
FUTURE WEARING SURFACE	0.288	KIP/FT
UTILITIES		
GAS MAIN (not added to W_{DL})	0.00	KIP/FT
TELEPHONE CONDUITS (not added to W_{DL})	0.00	KIP/FT
WATER MAIN	0.00	KIP/FT
EDGE BEAM:		
DEPTH (from top of slab)	2.41	FT
WIDTH	1.000	FT
EDGE BM. WEIGHT	2.438	KIP
DIAPHRAGM:		
Plate (3/8" X 5" X 2'-8")	0.017	KIP
CHANNEL (MC 18" X 42.7")	0.043	KIP/FT
DIAPH. WEIGHT	0.396	KIP
END WALL:		
DEPTH (from top of slab)	5.156	FT
WIDTH	0.667	FT
PAVING NOTCH WIDTH	0.667	FT
AVG. PAVING NOTCH DEPTH	0.833	FT
END WALL WEIGHT	5.017	KIP
PARAPET:		
SW, PAR., FENCE, & MEDIAN WEIGHT	1.900	KIP/FT
NUMBER OF BEAMS	5	
PARAPET WEIGHT	0.380	KIP/FT
SIDEWALK LIVE LOAD:		
SIDEWALK WIDTH	0	FT
SIDEWALK LOAD	0.066	KIP/FT ²
NUMBER OF BEAMS	5	
SIDEWALK LIVE LOAD PER BEAM	0.000	KIP/FT

DEAD LOAD CALCULATION:

SPAN LENGTH	101.25	FT		
BEAM WEIGHT	0.230	KLF		
			REACTION (K)	MOMENT (K-FT)
TOTAL DL	1.939	KIP/LF	96.183	2485.256
P-LOADS:				
TYPE	LOAD (K)	POSITION (FT)		
END WALL:	5.017	0.00	5.017	0.000
DIAPHRAGM:	0.395	20.25	0.316	6.395
DIAPHRAGM:	0.395	40.50	0.237	9.592
DIAPHRAGM:	0.395	60.75	0.158	9.592
DIAPHRAGM:	0.395	81.00	0.079	6.395
EDGE BEAM:	2.438	101.25	0.000	0.000
			REACTION (K)	MOMENT (K-FT)
TOTAL DL :			104.0	2517.2

LIVE LOAD CALCULATION:

BEAM DISTRIBUTION				
MOMENT	1.545	WHEEL	VERIFY !!!	
	0.773	AXLE		
SHEAR	1.824	WHEEL	VERIFY !!!	
	0.912	AXLE		
IMPACT FACTOR				
	1.221			
HS 20 LOADING:				
MIDSPAN:	1542.5	KIP-FT		
MAX:	1546.4	KIP-FT		
HS 20 REACTION:				
TRUCK	65.36	KIP	67.10	KIP
LANE	58.40	KIP	59.51	KIP
			REACTION (K)	MOMENT (K-FT)
TOTAL LL + I:			67.1	1455.3
MAX TOTAL LL + I:				1459.0
TOTAL D.L. + L.L. :				
			REACTION (K)	MOMENT (K-FT)
TOTAL D.L. + L.L. :			171.1	3972.6

DEFLECTIONS CALCULATION:

NO. LANES	3		
NO. BEAMS	5		
REDUCTION FACTOR	0.90	FACTOR	1.080

SIMPLE SPAN PROGRAM INPUT:

LENGTH =	101.25	FT
Moment Dist. Factor (DFM) =	1.545	
End Shear Dist. Factor (DFV) =	1.824	
LL Deflection Dist. Factor (DFD) =	1.080	
Non- Composite DL (W_{DLN}) =	1.041	KLF
Composite DL (W_{DLC}) =	0.668	KLF W/ F.W.S.
Sidewalk LL (W_{SWL}) =	0.000	KLF
Effective Concrete Width (W_e) =	102.000	IN
Concrete Slab Thickness (T_d) =	8.250	IN
Minimum Coping (Df) =	0.750	IN
P-LOADS:		
XP1	0.00	FT
P1	5.017	K
XP2	20.250	FT
P2	0.395	K
XP3	40.500	FT
P3	0.395	K
XP4	60.750	FT
P4	0.395	K
XP5	81.000	FT
P5	0.395	K
XP6	101.250	FT
P6	2.438	K

CALCULATION SHEET

PROJECT: I-75 / I-575 NORTHWEST CORRIDOR
JOB NUMBER NH000-0073-03(242)
CALC NO. BR#31


SUBJECT: Beam Design Input - Spans 2&3 (beam 3)
BY: JCR DATE: 11/30/2009

SHEET NO.
SHEET REV.

Sufficient sample calculations representative of the scope and conditions in the design calculation were performed and the results compared to demonstrate the computer program adequacy.

BRIDGE: I-75 over Noonday Creek
COUNTY: COBB
P.I. NO: 713640
PROJECT: NH000-0575-01(028)

J.B. TRIMBLE, INC.



JOB NO: 31-6036
DESIGNED BY: SHG
DATE: 10/16/2009

PJG 10-21-09

SPANS 2 & 3 (Beam 3)

Beam Type

D' DIMENSION = 10.875 IN
MIN. COPING DEPTH = 0.375 IN

AASHTO 8.10.1.1 - Compression Flange Width

wBM FLANGE = 12.00 in.
b = Bm Spacing = 102.00 in. CONTROLS
b = 1/4 Span Length = 279.75 in.
b = WBM FLANGE + 2(6 tSLAB) = 111.00 in.

BRIDGE GEOMETRY INPUT:

LARGER BEAM SPACING	8.500	FT
SMALLER BEAM SPACING	8.500	FT
SKEW ANGLE	64.00	DEGREES
SLAB:		
D' DIMENSION	10.875	IN
DESIGN SLAB DEPTH	8.250	IN
COPING WIDTH	1.000	FT
COPING DEPTH	1.5	IN
SLAB & COPING WEIGHT	0.895	KIP/FT
SIP FORMWORK	0.120	KIP/FT
DECK OVERLAY		
AVERAGE THICKNESS	0.250	IN
DECK OVERLAY WEIGHT	0.027	KIP/FT
ROADWAY WIDTH	48.000	FT
FUTURE WEARING SURFACE	0.288	KIP/FT
UTILITIES		
GAS MAIN (not added to W_{DL})	0.00	KIP/FT
TELEPHONE CONDUITS (not added to W_{DL})	0.00	KIP/FT
WATER MAIN	0.00	KIP/FT
EDGE BEAM:		
DEPTH (from top of slab)	2.41	FT
WIDTH	1.000	FT
EDGE BM. WEIGHT	2.438	KIP
DIAPHRAGM:		
Plate (3/8" X 5" X 2'-8")	0.017	KIP
CHANNEL (MC 18" X 42.7")	0.043	KIP/FT
DIAPH. WEIGHT	0.395	KIP
END WALL:		
DEPTH (from top of slab)	5.156	FT
WIDTH	0.667	FT
PAVING NOTCH WIDTH	0.667	FT
AVG. PAVING NOTCH DEPTH	0.833	FT
END WALL WEIGHT	5.017	KIP
PARAPET:		
SW, PAR., FENCE, & MEDIAN WEIGHT	1.900	KIP/FT
NUMBER OF BEAMS	5	
PARAPET WEIGHT	0.380	KIP/FT
SIDEWALK LIVE LOAD:		
SIDEWALK WIDTH	0	FT
SIDEWALK LOAD	0.060	KIP/FT ²
NUMBER OF BEAMS	5	
SIDEWALK LIVE LOAD PER BEAM	0.000	KIP/FT

DEAD LOAD CALCULATION:

SPAN LENGTH	93.25	FT		
BEAM WEIGHT	0.215	KLF	REACTION (K)	MOMENT (K-FT)
TOTAL DL	1.925	KIP/LF	89.747	2092.234
P-LOADS:				
TYPE	LOAD (K)	POSITION (FT)		
END WALL:	5.017	0.00	5.017	0.000
DIAPHRAGM:	0.395	18.65	0.316	5.889
DIAPHRAGM:	0.395	37.30	0.237	8.834
DIAPHRAGM:	0.395	55.95	0.158	8.834
DIAPHRAGM:	0.395	74.60	0.079	5.889
EDGE BEAM:	2.438	93.25	0.000	0.000
			REACTION (K)	MOMENT (K-FT)
TOTAL DL :			95.6	2121.7

LIVE LOAD CALCULATION:

BEAM DISTRIBUTION

MOMENT	1.545	WHEEL	VERIFY !!!
	0.773	AXLE	
SHEAR	1.824	WHEEL	VERIFY !!!
	0.912	AXLE	
IMPACT FACTOR			
	1.229		
HS 20 LOADING:			
MIDSPAN:	1398.5	KIP-FT	
MAX:	1402.7	KIP-FT	
HS 20 REACTION:			
TRUCK	64.79	KIP	R x DF x I
LANE	55.84	KIP	67.01 KIP
			57.48 KIP

	REACTION (K)	MOMENT (K-FT)
TOTAL LL+ I:	67.0	1328.2
MAX TOTAL LL+ I:		1332.2
	REACTION (K)	MOMENT (K-FT)
TOTAL D.L. + L.L. =	162.6	3449.9

DEFLECTIONS CALCULATION:

NO. LANES	3		
NO. BEAMS	5		
REDUCTION FACTOR	0.90	FACTOR	1.080

SIMPLE SPAN PROGRAM INPUT:

LENGTH =	93.25	FT
Moment Dist. Factor (DFM) =	1.545	
End Shear Dist. Factor (DFV) =	1.824	
LL Deflection Dist. Factor (DFD) =	1.080	
Non-Composite DL (W_{DLNC}) =	1.042	KLF
Composite DL (W_{DLC}) =	0.668	KLF W/ F.W.S.
Sidewalk LL (W_{swwk}) =	0.000	KLF
Effective Concrete Width (W_e) =	102.000	IN
Concrete Slab Thickness (T_s) =	8.250	IN
Minimum Coping (Df) =	0.750	IN
P-LOADS:		
XP1	0.00	FT
P1	5.017	K
XP2	18.650	FT
P2	0.395	K
XP3	37.300	FT
P3	0.395	K
XP4	55.950	FT
P4	0.395	K
XP5	74.600	FT
P5	0.395	K
XP6	93.250	FT
P6	2.438	K

CALCULATION SHEET

PROJECT: I-75 / I-575 NORTHWEST CORRIDOR
JOB NUMBER NH000-0073-03(242)
CALC NO. BR#31

SUBJECT: Beam Design Input - Spans 2&3 (beam 5)
BY: JCR DATE: 11/30/2009


SHEET NO.
SHEET REV.

Sufficient sample calculations representative of the scope and conditions in the design calculation were performed and the results compared to demonstrate the computer program adequacy.

BRIDGE: I-75 over Noonday Creek
COUNTY: COBB
P.I. NO: 713640
PROJECT: NH000-0575-01(028)

J.B. TRIMBLE, INC.

JOB NO: 31-6036
DESIGNED BY: SHG
DATE: 10/16/2009



PJC 10/21/09

SPANS 2 & 3 (Beam 5)

Beam Type Interior Plate Girder

'D' DIMENSION = 10.625 IN
MIN. COPING DEPTH = 0.375 IN

AASHTO 8.10.1.1 - Compression Flange Width

WBM FLANGE = 12.00 in.
b = Bm Spacing = 102.00 in. CONTROLS
b = 1/4 Span Length = 255.75 in.
b = WBM FLANGE + 2[6 tSLAB] = 111.00 in.

BRIDGE GEOMETRY INPUT:

LARGER BEAM SPACING 8.500 FT
SMALLER BEAM SPACING 8.500 FT
SKEW ANGLE 90.00 DEGREES
SLAB:
'D' DIMENSION 10.625 IN
DESIGN SLAB DEPTH 8.250 IN
COPING WIDTH 1.000 FT
COPING DEPTH 1.375 IN
SLAB & COPING WEIGHT 0.894 KIP/FT
SIP FORMWORK 0.120 KIP/FT
DECK OVERLAY
AVERAGE THICKNESS 0.250 IN
DECK OVERLAY WEIGHT 0.027 KIP/FT
ROADWAY WIDTH 48.000 FT
FUTURE WEARING SURFACE 0.288 KIP/FT
UTILITIES
GAS MAIN (not added to W_{DL}) 0.00 KIP/FT
TELEPHONE CONDUITS (not added to W_{DL}) 0.00 KIP/FT
WATER MAIN 0.00 KIP/FT
EDGE BEAM:
DEPTH (from top of slab) 2.39 FT
WIDTH 1.000 FT
EDGE BM. WEIGHT 2.165 KIP
DIAPHRAGM:
Plate (3/8" X 5" X 2'-8") 0.017 KIP
CHANNEL (MC 18" X 42.7") 0.043 KIP/FT
DIAPH. WEIGHT 0.396 KIP
PARAPET:
SW, PARL., FENCE, & MEDIAN WEIGHT 1.900 KIP/FT
NUMBER OF BEAMS 5
PARAPET WEIGHT 0.380 KIP/FT
SIDEWALK LIVE LOAD:
SIDEWALK WIDTH 0 FT
SIDEWALK LOAD 0.060 KIP/FT²
NUMBER OF BEAMS 5
SIDEWALK LIVE LOAD PER BEAM 0.000 KIP/FT

DEAD LOAD CALCULATION:

SPAN LENGTH 85.25 FT
BEAM WEIGHT 0.194 KLF
TOTAL DL 1.902 KIP/LF
P-LOADS:
TYPE LOAD (K) POSITION (FT)
EDGE BEAM: 2.165 0.00 2.165 0.000
DIAPHRAGM: 0.396 21.313 0.297 6.327
DIAPHRAGM: 0.396 42.625 0.198 8.435
DIAPHRAGM: 0.396 63.938 0.099 6.327
EDGE BEAM: 2.165 85.25 0.000 0.000
TOTAL DL : 83.8 REACTION (K) 1749.2

LIVE LOAD CALCULATION:

BEAM DISTRIBUTION
MOMENT 1.545 WHEEL VERIFY !!!
0.773 AXLE
SHEAR 1.824 WHEEL VERIFY !!!
0.912 AXLE
IMPACT FACTOR 1.238
HS 20 LOADING:
MIDSPAN: 1254.5 KIP-FT
MAX: 1259.1 KIP-FT
HS 20 REACTION:
TRUCK 64.12 KIP
LANE 53.28 KIP
R x DF x I 66.83 KIP
55.44 KIP
TOTAL LL+ I: 66.8 REACTION (K) 1199.9
MAX TOTAL LL+ I: 1204.3
TOTAL D.L. + L.L. = 150.7 REACTION (K) 2949.2

DEFLECTIONS CALCULATION:

NO. LANES 3
NO. BEAMS 5
REDUCTION FACTOR 0.90 FACTOR 1.080

SIMPLE SPAN PROGRAM INPUT:

LENGTH = 85.25 FT
Moment Dist. Factor (DFM) = 1.545
End Shear Dist. Factor (DFV) = 1.824
LL Deflection Dist. Factor (DFD) = 1.080
Non- Composite DL (W_{DLNC}) = 1.040 KLF
Composite DL (W_{DLC}) = 0.668 KLF W/ F.W.S.
Sidewalk LL (W_{SWLL}) = 0.000 KLF
Effective Concrete Width (W_e) = 102.00 IN
Concrete Slab Thickness (T_d) = 8.250 IN
Minimum Coping (Df) = 0.750 IN
P-LOADS:
XP1 0.00 FT
P1 2.165 K
XP2 21.313 FT
P2 0.396 K
XP3 42.625 FT
P3 0.396 K
XP4 63.938 FT
P4 0.396 K
XP5 85.250 FT
P5 2.165 K

CALCULATION COVER SHEET

PROJECT	JOB NO.	CALC NO.	SHEET
I-75 / I-575 NORTHWEST CORRIDOR	NH000-0073-03(242)	BR#31	1
SUBJECT	DISCIPLINE		
Beam Design Output	STRUCTURAL		

CALCULATION STATUS DESIGNATION	PRELIMINARY	CONFIRMED	SUPSEDED	VOIDED	INCOMPLETE
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

COMPUTER PROGRAM/TYPE	SCP	MAINFRAME	PC	PROGRAM	VERSION/RELEASE NO.
	<input checked="" type="radio"/> YES <input type="radio"/> NO	<input type="radio"/>	<input checked="" type="radio"/>	GDOT BRSPAN	06/26/2008

Note 1: Georgia Department of Transportation (GDOT) terminated Contract Number TOURDPPI60072 for its convenience the completion of all work under that contract and directed that the work with respect to these calculations be discontinued

- (a) These calculations were not completed at the time of GDOT's direction and the information contained herein is not and/or has not been fully verified or checked. These calculations are a work-in-progress and are presented only as such.
- (b) Any user is cautioned that the use of these calculations and any related information or calculations, without access to factors and without proper regard for their purpose, could lead to erroneous conclusions.
- (c) If any such calculations or any information contained herein is used in future work efforts or any follow on design work a complete confirmation of the information contained herein should be performed prior to any such use.
- (d) GTP has no responsibility for the use of this information not under its direct control.

Beam design output is included for span 1, and spans 2&3 (beams 1, 3 & 5).

A	As per GDOT's termination for convenience direction	17	17	JCR			11/30/09
NO.	REASON FOR REVISION	TOTAL NO. OF SHEETS	LAST SHEET NO.	BY	CHECKED	APPROVED/ ACCEPTED	DATE
RECORD OF REVISIONS							

CALCULATION SHEET

PROJECT: I-75 / I-575 NORTHWEST CORRIDOR
JOB NUMBER NH000-0073-03(242)
CALC NO. BR#31

SUBJECT: Beam Design Output - Span 1
BY: JCR DATE: 11/30/2009

SHEET NO.
SHEET REV.

Sufficient sample calculations representative of the scope and conditions in the design calculation were performed and the results compared to demonstrate the computer program adequacy.

P56
12-21-09

I-75 OVER NOONDAY CREEK - SPAN 1

SPAN DATA

BEAM	D/A	L.L.C.	T L M	LENGTH	D.F.M.	D.F.V.	D.F.D.	NPL
CG	1	HS20	0 0 0	78.250	1.364	1.667	1.080	5
WDLNC	WDLN	SWLL	E	W BM	FS	FC	WG	TYPE STEEL
0.880	0.646	0.000	29.00	0.000	27.00	1.400	0.490	572

CONCENTRATED LOADS

X1	P1	X2	P2	X3	P3	X4	P4
0.000	3.932	19.563	0.353	39.125	0.353	58.688	0.353
78.250	1.863	0.000	0.000	0.000	0.000	0.000	0.000

BEAM DATA

ROLLED	SECTION PROPERTIES			PLATE GIRDER WEB		TOP FLANGE		BOTTOM FLANGE	
BEAM	P	NP	I	Y TOP	Y BOT	D	T	W	T
OWF	0	0	0	0.0	0.000	0.000	48.00	0.6250	12.00
OWF	0								0.7500
									12.00
									1.0000

COMPOSITE SLAB

WIDTH	THICKNESS	COPING	SHEAR CAPACITY		ULTIMATE STRENGTH		N=ES/EC	
90.000	7.875	0.000	12.38	K/ROW	25.21	KIPS EACH		9
BOTTOM COVER	PLATE				TOP COVER	PLATE		CONSTANT
X-BEGIN	THICKNESS	WIDTH	LENGTH		X-BEGIN	THICKNESS	WIDTH	LENGTH
20.25	1.2500	12.00	37.75		0.00	0.0000	0.00	0.00
								0 0

PLATE GIRDER PROPERTIES

WEB		TOP FLANGE		BOTTOM FLANGE		WEB AND FLANGES PROPERTIES			
DEPTH	THICK	WIDTH	THICK	WIDTH	THICK	AREA	Y-TOP	Y-BOTTOM	I
48.00	0.6250	12.00	0.7500	12.00	1.0000	51.000	26.213	23.537	18202.5

WEB AND COVER PLATES

BOTTOM	COVER	PLATE		TOP	COVER	PLATE	
X-BEGIN	THICKNESS	WIDTH	LENGTH	X-BEGIN	THICKNESS	WIDTH	LENGTH
20.25	1.2500	12.00	37.75	0.00	0.7500	12.00	0.00

WEB WITH COVER PLATES PROPERTIES

AREA	Y-TOP	Y-BOTTOM	I
54.000	27.528	22.472	19788.8

COMPOSITE SECTION PROPERTIES

WEB AND FLANGES					WEB AND PLATES				
N	YTC	YTS	YBS	I	Q SLAB	YTC	YTS	YBS	I
9	15.79	7.91	41.84	46748.5	933.3	16.74	8.86	41.14	51911.4
27	23.84	15.97	33.78	34092.4		25.11	17.24	32.76	37412.5

NUMBER OF SHEAR CONNECTORS NEEDED TO PROVIDE FOR ULTIMATE STRENGTH 197

NUMBER OF LONGITUDINAL STIFFENERS NEEDED 0

TRANSVERSE STIFFENERS NOT REQUIRED

SIMPLE SPAN OUTPUT DATA PROBLEM NUMBER S2NW

SP	GIRDER	P-LOAD	MOMENTS (K-FT.) AT SPAN 1/20 POINTS		COMP.	SIDEWK	LIVE LOAD	RR-I
			NON-C.	TOT.NC				
1	26.0	2.1	128.0	156.0	93.9	0.0	198.9 T	0.0
2	49.3	4.1	242.5	295.9	178.0	0.0	373.8 T	0.0
3	70.0	6.2	343.5	419.7	252.2	0.0	524.8 T	0.0
4	88.0	8.3	431.1	527.4	316.4	0.0	651.8 T	0.0
5	103.4	10.4	505.2	618.9	370.8	0.0	754.9 T	0.0
6	116.0	11.0	565.8	692.9	415.3	0.0	834.1 T	0.0
7	125.9	11.7	612.9	750.5	449.9	0.0	894.1 T	0.0
8	132.9	12.4	646.6	791.9	474.7	0.0	939.6 T	0.0
9	137.1	13.1	666.8	817.1	489.5	0.0	961.3 T	0.0
10	138.5	13.8	673.5	825.9	494.4	0.0	959.0 T	0.0

STRESS (PSI) AT SPAN 1/20 POINTS

SP	MINIMUM STRESS		MAXIMUM STRESS			ALLOWABLE FS	R FACTOR	
	TOP-S	BOT-S	TOP-C	TOP-S	BOT-S		TOP-S	BOT-S
1	3224	-3538	118	3628	-5673	27000	0.889	0.624
2	6114	-6708	223	6873	-10722	27000	0.890	0.626
3	8670	-9511	314	9736	-15146	27000	0.891	0.628
4	10892	-11945	391	12216	-18945	27000	0.892	0.631
5	12779	-14012	455	14312	-22119	27000	0.893	0.633
6	13861	-13806	482	15570	-21738	27000	0.890	0.635
7	15016	-14956	518	16847	-23458	27000	0.891	0.638
8	15843	-15780	545	17768	-24715	27000	0.892	0.638
9	16345	-16278	559	18314	-25419	27000	0.892	0.640
10	16519	-16450	559	18484	-25570	27000	0.894	0.643

SHEARS (KIPS) AT SPAN 1/20 POINTS

S2NW

SP	GIRDER	P-LOAD	NON-C.	TOT.NC	COMP.	SIDEWK	LIVE LOAD	RR-I
0	7.0	4.5	34.4	45.9	25.3	0.0	59.9 T	0.0
1	6.3	0.5	31.0	37.8	22.7	0.0	51.0 T	0.0
2	5.6	0.5	27.5	33.7	20.2	0.0	48.1 T	0.0
3	4.9	0.5	24.1	29.6	17.7	0.0	45.2 T	0.0
4	4.3	0.5	20.7	25.5	15.2	0.0	42.3 T	0.0
5	3.6	0.5	17.2	21.3	12.6	0.0	39.4 T	0.0
6	2.9	0.2	13.8	16.8	10.1	0.0	36.4 T	0.0
7	2.2	0.2	10.3	12.7	7.6	0.0	33.5 T	0.0
8	1.4	0.2	6.9	8.5	5.1	0.0	30.5 T	0.0
9	0.7	0.2	3.4	4.3	2.5	0.0	27.4 T	0.0
10	0.0	0.2	0.0	0.2	0.0	0.0	24.3 T	0.0

DEAD LOAD DEFLECTIONS (INCHES)						SHEAR	
SP	GIRDER	P-LOAD	NON-C.	TOT.NC	COMP.	RANGE (KIPS)	CON.SPAC (IN)
0	0.000	0.000	0.000	0.000	0.000	59.9	10.35
1	0.043	0.004	0.212	0.259	0.083	52.4	11.82
2	0.086	0.008	0.417	0.511	0.163	51.3	12.09
3	0.125	0.012	0.611	0.748	0.238	50.5	12.27
4	0.161	0.015	0.787	0.964	0.306	49.8	12.46
5	0.193	0.018	0.942	1.153	0.367	49.0	12.67
6	0.220	0.021	1.072	1.313	0.417	48.4	13.18
7	0.241	0.023	1.176	1.440	0.458	48.3	13.21
8	0.257	0.024	1.252	1.533	0.487	48.4	13.18
9	0.266	0.025	1.298	1.590	0.505	48.6	13.13
10	0.270	0.026	1.314	1.609	0.511	48.6	13.12

LIVE LOAD DEFLECTIONS (INCHES)					
TRUCK	LANE	MILITARY	RAILROAD	SIDEWALK	L/ 800
0.520	0.387	0.373	0.000	0.000	1.174

CALCULATION SHEET

PROJECT: I-75 / I-575 NORTHWEST CORRIDOR
JOB NUMBER NH000-0073-03(242)
CALC NO. BR#31

SUBJECT: Beam Design Output - Spans 2&3 (beam 1)
BY: JCR DATE: 11/30/2009

SHEET NO.
SHEET REV.

Sufficient sample calculations representative of the scope and conditions in the design calculation were performed and the results compared to demonstrate the computer program adequacy.

16-OCT-09 GEORGIA DEPARTMENT OF TRANSPORTATION PROB. NO. S2NW
 11:44:08 PRECONSTRUCTION DIVISION - OFFICE OF BRIDGE & STRUCTURAL DESIGN
 SIMPLE SPAN
 REVISED: JUNE 26, 2008

PJC
 10-21-09

I-75 OVER NOONDAY CREEK - SPANS 2 & 3 (Beam 1)

SPAN DATA

BEAM	D/A	L.L.C.	T L M	LENGTH	D.F.M.	D.F.V.	D.F.D.	NPL
CG	1	HS20	0 0 0	101.250	1.545	1.824	1.080	6
	WDLNC	WDLN	SWLL	E	W BM	FS	PC	WG
	1.041	0.668	0.000	29.00	0.000	27.00	1.400	0.490
								572

CONCENTRATED LOADS

X1	P1	X2	P2	X3	P3	X4	P4
0.000	5.017	20.250	0.395	40.500	0.395	60.750	0.395
81.000	0.395	101.250	2.438	0.000	0.000	0.000	0.000

BEAM DATA

ROLLED	SECTION PROPERTIES	PLATE GIRDER WEB	TOP FLANGE	BOTTOM FLANGE
BEAM	P NP I	Y TOP Y BOT D T	W T	W T
OWF 0 0 0	0.0	0.000 0.000	48.00 0.6250	12.00 0.7500
OWF 0				16.00 1.3750

COMPOSITE SLAB

WIDTH	THICKNESS	COPING	SHEAR CAPACITY	ULTIMATE STRENGTH	N=ES/EC			
102.000	8.250	0.000	12.38 K/ROW	25.21 KIPS EACH	9			
BOTTOM COVER	PLATE			TOP COVER	PLATE	CONSTANT		
X-BEGIN	THICKNESS	WIDTH	LENGTH	X-BEGIN	THICKNESS	WIDTH	LENGTH	W T
25.63	2.0000	16.00	50.00	25.63	1.1250	12.00	50.00	0 0

PLATE GIRDER PROPERTIES

WEB	TOP FLANGE	BOTTOM FLANGE	WEB AND FLANGES PROPERTIES
DEPTH THICK	WIDTH THICK	WIDTH THICK	AREA Y-TOP Y-BOTTOM I
48.00 0.6250	12.00 0.7500	16.00 1.3750	61.000 30.057 20.068 22801.3

WEB AND COVER PLATES

BOTTOM	COVER	PLATE		TOP	COVER	PLATE	
X-BEGIN	THICKNESS	WIDTH	LENGTH	X-BEGIN	THICKNESS	WIDTH	LENGTH
25.63	2.0000	16.00	50.00	25.63	1.1250	12.00	50.00

WEB WITH COVER PLATES PROPERTIES

AREA	Y-TOP	Y-BOTTOM	I
75.500	31.329	19.796	31010.8

COMPOSITE SECTION PROPERTIES

	WEB AND FLANGES		WEB AND PLATES	
N	YTC YTS YBS I	Q SLAB	YTC YTS YBS I	Q SLAB
9	17.77 9.14 40.98 67417.0	1275.7	19.96 11.71 39.41 84046.5	1480.9
27	27.00 18.37 31.75 47611.7		29.22 20.97 30.16 58917.0	

NUMBER OF SHEAR CONNECTORS NEEDED TO PROVIDE FOR ULTIMATE STRENGTH 234

NUMBER OF LONGITUDINAL STIFFENERS NEEDED 0

TRANSVERSE STIFFENERS NOT REQUIRED

DEAD LOAD DEFLECTIONS (INCHES)						SHEAR	
SP	GIRDER	P-LOAD	NON-C.	TOT.NC	COMP.	RANGE (KIPS)	CON.SPAC (IN)
0	0.000	0.000	0.000	0.000	0.000	67.1	9.75
1	0.113	0.009	0.487	0.609	0.159	60.1	10.89
2	0.222	0.017	0.958	1.197	0.312	59.2	11.05
3	0.323	0.025	1.396	1.745	0.456	58.4	11.20
4	0.415	0.032	1.789	2.236	0.585	57.6	11.36
5	0.493	0.038	2.125	2.657	0.698	57.3	11.41
6	0.557	0.043	2.401	3.001	0.791	57.5	12.23
7	0.609	0.047	2.621	3.277	0.865	57.8	12.16
8	0.647	0.050	2.782	3.479	0.919	58.1	12.09
9	0.670	0.052	2.879	3.601	0.952	58.2	12.06
10	0.677	0.053	2.912	3.642	0.963	58.3	12.06

LIVE LOAD DEFLECTIONS (INCHES)					
TRUCK	LANE	MILITARY	RAILROAD	SIDEWALK	L/ 800
0.718	0.615	0.499	0.000	0.000	1.519

CALCULATION SHEET

PROJECT: I-75 / I-575 NORTHWEST CORRIDOR
JOB NUMBER NH000-0073-03(242)
CALC NO. BR#31

SUBJECT: Beam Design Output - Spans 2&3 (beam 3)
BY: JCR DATE: 11/30/2009

SHEET NO.
SHEET REV.

Sufficient sample calculations representative of the scope and conditions in the design calculation were performed and the results compared to demonstrate the computer program adequacy.

TRANSVERSE STIFFENERS NOT REQUIRED

DEAD LOAD DEFLECTIONS (INCHES)						SHEAR	
SP	GIRDER	P-LOAD	NON-C.	TOT.NC	COMP.	RANGE (KIPS)	CON.SPAC (IN)
0	0.000	0.000	0.000	0.000	0.000	67.0	9.61
1	0.082	0.007	0.379	0.468	0.122	59.9	10.74
2	0.161	0.015	0.745	0.920	0.241	58.9	10.93
3	0.235	0.021	1.086	1.342	0.352	58.1	11.08
4	0.302	0.027	1.394	1.722	0.452	57.3	11.24
5	0.359	0.033	1.658	2.049	0.538	56.7	11.36
6	0.407	0.037	1.876	2.319	0.610	56.6	12.12
7	0.445	0.040	2.050	2.534	0.668	56.9	12.06
8	0.472	0.043	2.176	2.691	0.710	57.2	12.00
9	0.489	0.044	2.253	2.786	0.735	57.4	11.95
10	0.495	0.045	2.278	2.817	0.744	57.4	11.94

LIVE LOAD DEFLECTIONS (INCHES)					
TRUCK	LANE	MILITARY	RAILROAD	SIDEWALK	L/ 800
0.605	0.494	0.424	0.000	0.000	1.399

CALCULATION SHEET

PROJECT: I-75 / I-575 NORTHWEST CORRIDOR
JOB NUMBER NH000-0073-03(242)
CALC NO. BR#31

SUBJECT: Beam Design Output - Spans 2&3 (beam 5)
BY: JCR DATE: 11/30/2009

SHEET NO.
SHEET REV.

Sufficient sample calculations representative of the scope and conditions in the design calculation were performed and the results compared to demonstrate the computer program adequacy.

16-OCT-09 GEORGIA DEPARTMENT OF TRANSPORTATION PROB. NO. S2NW
 11:36:16 PRECONSTRUCTION DIVISION - OFFICE OF BRIDGE & STRUCTURAL DESIGN
 SIMPLE SPAN
 REVISED: JUNE 26, 2008

psc 10/21/09

I-75 OVER NOONDAY CREEK - SPANS 2 & 3 (Beam 5)

SPAN DATA

BEAM	D/A	L.L.C.	T L M	LENGTH	D.F.M.	D.F.V.	D.F.D.	NPL
CG	1	HS20	0 0 0	85.250	1.545	1.824	1.080	5
WDLNC	WDLNC	SWLL	E	W BM	FS	FC	WG	TYPE STEEL
1.040	0.668	0.000	29.00	0.000	27.00	1.400	0.490	572

CONCENTRATED LOADS

X1	P1	X2	P2	X3	P3	X4	P4
0.000	2.165	21.313	0.396	42.625	0.396	63.938	0.396
85.250	2.165	0.000	0.000	0.000	0.000	0.000	0.000

BEAM DATA

ROLLED	SECTION PROPERTIES	PLATE GIRDER WEB	TOP FLANGE	BOTTOM FLANGE
BEAM	P NP I	Y TOP Y BOT D T	W T	W T
OWF 0 0 0	0.0	0.000 0.000	48.00 0.6250	12.00 0.7500
OWF 0				12.00 1.2500

COMPOSITE SLAB

WIDTH	THICKNESS	COPING	SHEAR CAPACITY	ULTIMATE STRENGTH	N=ES/EC
102.000	8.250	0.000	12.38 K/ROW	25.21 KIPS EACH	9
BOTTOM COVER	PLATE	TOP COVER	PLATE	CONSTANT	
X-BEGIN	THICKNESS	WIDTH	LENGTH	X-BEGIN	THICKNESS
22.23	1.7500	12.00	42.00	0.00	0.0000
				0.00	0.00
					0 0

PLATE GIRDER PROPERTIES

WEB	TOP FLANGE	BOTTOM FLANGE	WEB AND FLANGES PROPERTIES
DEPTH THICK	WIDTH THICK	WIDTH THICK	AREA Y-TOP Y-BOTTOM I
48.00 0.6250	12.00 0.7500	12.00 1.2500	54.000 27.528 22.472 19788.8

WEB AND COVER PLATES

BOTTOM	COVER	PLATE	TOP	COVER	PLATE
X-BEGIN	THICKNESS	WIDTH	LENGTH	X-BEGIN	THICKNESS
22.23	1.7500	12.00	42.00	0.00	0.7500
					12.00
					0.00

WEB WITH COVER PLATES PROPERTIES

AREA	Y-TOP	Y-BOTTOM	I
60.000	29.800	20.700	22577.0

COMPOSITE SECTION PROPERTIES

N	YTC	YTS	YBS	I	Q SLAB	YTC	YTS	YBS	I	Q SLAB
9	15.71	7.46	42.54	54614.6	1083.5	17.39	9.14	41.36	65169.7	1239.9
27	24.19	15.94	34.06	39764.4		26.45	18.20	32.30	46361.0	

NUMBER OF SHEAR CONNECTORS NEEDED TO PROVIDE FOR ULTIMATE STRENGTH 234

NUMBER OF LONGITUDINAL STIFFENERS NEEDED 0

TRANSVERSE STIFFENERS NOT REQUIRED

SIMPLE SPAN OUTPUT DATA PROBLEM NUMBER S2NW

SP	GIRDER	P-LOAD	MOMENTS (K-FT.) AT SPAN 1/20 POINTS					RR-I
			NON-C.	TOT.NC	COMP.	SIDEWK	LIVE LOAD	
1	33.5	2.5	179.5	215.6	115.3	0.0	246.7 T	0.0
2	63.7	5.1	340.1	408.9	218.5	0.0	464.0 T	0.0
3	90.5	7.6	481.8	580.0	309.5	0.0	651.9 T	0.0
4	114.0	10.1	604.7	728.8	388.4	0.0	810.6 T	0.0
5	134.2	12.7	708.6	855.5	455.1	0.0	939.8 T	0.0
6	150.9	13.5	793.6	958.0	509.7	0.0	1039.8 T	0.0
7	163.9	14.3	859.8	1038.0	552.2	0.0	1115.7 T	0.0
8	173.2	15.2	907.0	1095.4	582.6	0.0	1173.0 T	0.0
9	178.8	16.0	935.3	1130.2	600.8	0.0	1201.0 T	0.0
10	180.7	16.9	944.8	1142.4	606.8	0.0	1199.6 T	0.0

STRESS (PSI) AT SPAN 1/20 POINTS

SP	MINIMUM STRESS		MAXIMUM STRESS			ALLOWABLE FS	R FACTOR	
	TOP-S	BOT-S	TOP-C	TOP-S	BOT-S		TOP-S	BOT-S
1	4153	-4122	125	4557	-6427	27000	0.911	0.641
2	7876	-7817	237	8637	-12153	27000	0.912	0.643
3	11170	-11084	333	12239	-17177	27000	0.913	0.645
4	14035	-13923	415	15364	-21499	27000	0.913	0.648
5	16469	-16334	483	18011	-25118	27000	0.914	0.650
6	17576	-14802	499	19325	-22721	27000	0.909	0.651
7	19043	-16037	536	20920	-24535	27000	0.910	0.654
8	20095	-16922	564	22068	-25856	27000	0.911	0.654
9	20731	-17457	579	22751	-26604	27000	0.911	0.656
10	20953	-17641	580	22970	-26778	27000	0.912	0.659

SHEARS (KIPS) AT SPAN 1/20 POINTS

S2NW

SP	GIRDER	P-LOAD	NON-C.	TOT.NC	COMP.	SIDEWK	LIVE LOAD	RR-I
0	8.3	2.8	44.3	55.3	28.5	0.0	66.8 T	0.0
1	7.5	0.6	39.9	48.0	25.6	0.0	58.1 T	0.0
2	6.7	0.6	35.5	42.7	22.8	0.0	54.9 T	0.0
3	5.9	0.6	31.0	37.5	19.9	0.0	51.6 T	0.0
4	5.1	0.6	26.6	32.3	17.1	0.0	48.3 T	0.0
5	4.3	0.6	22.2	27.1	14.2	0.0	45.1 T	0.0
6	3.5	0.2	17.7	21.4	11.4	0.0	41.7 T	0.0
7	2.6	0.2	13.3	16.1	8.5	0.0	38.4 T	0.0
8	1.7	0.2	8.9	10.8	5.7	0.0	35.0 T	0.0
9	0.9	0.2	4.4	5.5	2.8	0.0	31.6 T	0.0
10	0.0	0.2	0.0	0.2	0.0	0.0	28.2 T	0.0

DEAD LOAD DEFLECTIONS (INCHES)						SHEAR	
SP	GIRDER	P-LOAD	NON-C.	TOT.NC	COMP.	RANGE (KIPS)	CON.SPAC (IN)
0	0.000	0.000	0.000	0.000	0.000	66.8	9.34
1	0.060	0.005	0.314	0.379	0.099	59.7	10.45
2	0.117	0.010	0.618	0.746	0.195	58.6	10.66
3	0.172	0.015	0.904	1.091	0.285	57.7	10.81
4	0.221	0.020	1.164	1.405	0.366	56.9	10.98
5	0.264	0.024	1.390	1.678	0.437	56.0	11.15
6	0.301	0.027	1.580	1.907	0.497	55.7	11.67
7	0.330	0.029	1.731	2.090	0.544	55.8	11.66
8	0.351	0.031	1.842	2.224	0.579	56.0	11.61
9	0.364	0.032	1.909	2.305	0.599	56.3	11.57
10	0.368	0.033	1.931	2.331	0.606	56.4	11.54

LIVE LOAD DEFLECTIONS (INCHES)					
TRUCK	LANE	MILITARY	RAILROAD	SIDEWALK	L/ 800
0.544	0.423	0.385	0.000	0.000	1.279

CALCULATION COVER SHEET

PROJECT	JOB NO.	CALC NO.	SHEET
I-75 / I-575 NORTHWEST CORRIDOR	NH000-0073-03(242)	BR#31	1
SUBJECT	DISCIPLINE		
Shear Stud Spacing Calculations	STRUCTURAL		

CALCULATION STATUS DESIGNATION	PRELIMINARY	CONFIRMED	SUPSEDED	VOIDED	INCOMPLETE
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

COMPUTER PROGRAM/TYPE	SCP	MAINFRAME	PC	PROGRAM	VERSION/RELEASE NO.
	<input checked="" type="radio"/> YES <input type="radio"/> NO	<input type="radio"/>	<input checked="" type="radio"/>	Excel	2003

Note 1: Georgia Department of Transportation (GDOT) terminated Contract Number TOURDPP160072 for its convenience prior to the completion of all work under that contract and directed that the work with respect to these calculations be discontinued.

(a) These calculations were not completed at the time of GDOT's direction and the information contained herein is not complete and/or has not been fully verified or checked. These calculations are a work-in-progress and are presented only as such.

(b) Any user is cautioned that the use of these calculations and any related information or calculations, without access to factors and without proper regard for their purpose, could lead to erroneous conclusions.

(c) If any such calculations or any information contained herein is used in future work efforts or any follow on design work activity, a complete confirmation of the information contained herein should be performed prior to any such use.

(d) GTP has no responsibility for the use of this information not under its direct control.

Design calculations for steel beam shear stud spacings are included for span 1, and spans 2&3 (beams 1, 3 & 5).

A	As per GDOT's termination for convenience direction	13	13	JCR			11/30/09
NO.	REASON FOR REVISION	TOTAL NO. OF SHEETS	LAST SHEET NO.	BY	CHECKED	APPROVED/ ACCEPTED	DATE
RECORD OF REVISIONS							

CALCULATION SHEET

PROJECT: I-75 / I-575 NORTHWEST CORRIDOR
JOB NUMBER NH000-0073-03(242)
CALC NO. BR#31

SUBJECT: Shear Stud Spacing Calculations - Span 1
BY: JCR DATE: 11/30/2009

SHEET NO.
SHEET REV.

Sufficient sample calculations representative of the scope and conditions in the design calculation were performed and the results compared to demonstrate the computer program adequacy.

BRIDGE: I-75 over Noonday Creek
COUNTY: COBB
P.I. NO: 713640
PROJECT: NH000-0575-01(028)



J.B. TRIMBLE, INC.
JOB NO: 31-6036
DESIGNED BY: SHG
DATE: 10/16/2009
PJC 10-21-09

STUD SHEAR CONNECTORS

Beam Type Top Flange Width = 12"

Stud $\varnothing = 0.75$ "

No. of Studs = 4

$Z_r = \alpha d^2$ (kips / studs)			
$\alpha \setminus d$ (in)	0.5	0.75	1
13000	3.25	7.31	13.00
10600	2.65	5.96	10.60
7850	1.96	4.42	7.85
5500	1.38	3.09	5.50

ADT (2001) = 1,000

ADT (2021) = 80,000

% TRUCKS = 4.4%

DIRECTIONAL = 100%

ADT (2031) = 119,500 in one direction


ADTT = 5,258 > 2500
USE 2,000,000 CYCLES

$Z_r = \alpha d^2$ (kips / row)			
Number of Studs : 3			
$\alpha \setminus d$ (in)	0.5	0.75	1
13000	9.75	21.94	39.00
10600	7.95	17.89	31.80
7850	5.89	13.25	23.55
5500	4.13	9.28	16.50

$Z_r = \alpha d^2$ (kips / row)			
Number of Studs : 4			
$\alpha \setminus d$	0.5	0.75	1
13000	13.00	29.25	52.00
10600	10.60	23.85	42.40
7850	7.85	17.66	31.40
5500	5.50	12.38	22.00

$$E_c = 150^{1.5} 33 (f'_c)^{1/2} \quad (\text{AASHTO 10.38.5.1.2})$$

$S_u = 0.4 d^2 (f'_c E_c)^{1/2}$ (AASHTO)			
d (in)	f'_c (psi)	E_c (psi)	S_u (kips)
0.5	3000	3320561	9.98
0.75	3000	3320561	22.46
1	3000	3320561	39.92
0.5	3500	3586616	11.20
0.75	3500	3586616	25.21
1	3500	3586616	44.82



AASHTO 10.38.2.4 The clear distance between the edge of a girder flange and the edge of the shear connector shall be not less than 1". Adjacent stud shear connectors shall not be closer than 4 diameters center to center.

GDOT calls for 3/4" \varnothing studs and 1 1/2" clear from edge of girder flange to CL of stud. Therefore, 4 studs are only allowed for beams with a minimum flange width of 12"+/-.

Shear Capacity (Z_r) = 12.38 K/Row

Ultimate Strength (S_u) = 25.21 kips

BRIDGE: I-75 over Noonday Creek
COUNTY: COBB
P.I. NO: 713640
PROJECT: NH000-0575-01(028)



J.B. TRIMBLE, INC.
JOB NO: 31-6036
DESIGNED BY: SHG
DATE: 10/16/2009


SHEAR STUD SPACING

PJC 10/21/09

Design Length = 78.25 ft.

Location (ft.)	s (in)
0.0	10.35
3.9	11.82
7.8	12.09
11.7	12.27
15.7	12.46
19.6	12.67
23.5	13.18
27.4	13.21
31.3	13.18
35.2	13.13
39.1	13.12

	Spacing 1	Spacing 2
Stud Spacing:	10 in.	13 in.



CALCULATION SHEET

PROJECT: I-75 / I-575 NORTHWEST CORRIDOR
JOB NUMBER NH000-0073-03(242)
CALC NO. BR#31

SUBJECT: Shear Stud Spacing Calculations - Spans 2&3 (beam 1)
BY: JCR DATE: 11/30/2009

SHEET NO.
SHEET REV.

Sufficient sample calculations representative of the scope and conditions in the design calculation were performed and the results compared to demonstrate the computer program adequacy.

BRIDGE: I-75 over Noonday Creek
COUNTY: COBB
P.I. NO: 713640
PROJECT: NH000-0575-01(028)



J.B. TRIMBLE, INC.
JOB NO: 31-6036
DESIGNED BY: SHG
DATE: 10/16/2009

PJC 10/21/09

STUD SHEAR CONNECTORS

Beam Type Top Flange Width = 16"

Stud $\varnothing = 0.75$ "

No. of Studs = 4

$Z_r = \alpha d^2$ (kips / studs)			
$\alpha \setminus d$ (in)	0.5	0.75	1
13000	3.25	7.31	13.00
10600	2.65	5.96	10.60
7850	1.96	4.42	7.85
5500	1.38	3.09	5.50

ADT (2001) = 1,000

ADT (2021) = 80,000

% TRUCKS = 4.4%

DIRECTIONAL = 100%

ADT (2031) = 119,500 in one direction


ADTT = 5,258 > 2500
USE 2,000,000 CYCLES

$Z_r = \alpha d^2$ (kips / row)			
Number of Studs : 3			
$\alpha \setminus d$ (in)	0.5	0.75	1
13000	9.75	21.94	39.00
10600	7.95	17.89	31.80
7850	5.89	13.25	23.55
5500	4.13	9.28	16.50

$Z_r = \alpha d^2$ (kips / row)			
Number of Studs : 4			
$\alpha \setminus d$	0.5	0.75	1
13000	13.00	29.25	52.00
10600	10.60	23.85	42.40
7850	7.85	17.66	31.40
5500	5.50	12.38	22.00

$E_c = 150^{1.5} 33 (f'_c)^{1/2}$ (AASHTO 10.38.5.1.2)

$S_U = 0.4 d^2 (f'_c E_c)^{1/2}$ (AASHTO)			
d (in)	f'_c (psi)	E_c (psi)	S_U (kips)
0.5	3000	3320561	9.98
0.75	3000	3320561	22.46
1	3000	3320561	39.92
0.5	3500	3586616	11.20
0.75	3500	3586616	25.21
1	3500	3586616	44.82



AASHTO 10.38.2.4 The clear distance between the edge of a girder flange and the edge of the shear connector shall be not less than 1". Adjacent stud shear connectors shall not be closer than 4 diameters center to center.

GDOT calls for 3/4" \varnothing studs and 1 1/2" clear from edge of girder flange to CL of stud. Therefore, 4 studs are only allowed for beams with a minimum flange width of 12"+/-.

Shear Capacity (Z_r) = 12.38 K/Row

Ultimate Strength (S_U) = 25.21 kips

BRIDGE: I-75 over Noonday Creek
COUNTY: COBB
P.I. NO: 713640
PROJECT: NH000-0575-01(028)




J.B. TRIMBLE, INC.
JOB NO: 31-6036
DESIGNED BY: SHG
DATE: 10/16/2009

SHEAR STUD SPACING

Design Length = 101.25 ft.

Location (ft.)	s (in)
0.0	9.75
5.1	10.89
10.1	11.05
15.2	11.20
20.3	11.36
25.3	11.41
30.4	12.23
35.4	12.16
40.5	12.09
45.6	12.06
50.6	12.06

	Spacing 1	Spacing 2
Stud Spacing:	9 in.	11 in.



CALCULATION SHEET

PROJECT: I-75 / I-575 NORTHWEST CORRIDOR
JOB NUMBER NH000-0073-03(242)
CALC NO. BR#31

SUBJECT: Shear Stud Spacing Calculations - Spans 2&3 (beam 3)
BY: JCR DATE: 11/30/2009

SHEET NO.
SHEET REV.

Sufficient sample calculations representative of the scope and conditions in the design calculation were performed and the results compared to demonstrate the computer program adequacy.

BRIDGE: I-75 over Noonday Creek
COUNTY: COBB
P.I. NO: 713640
PROJECT: NH000-0575-01(028)



J.B. TRIMBLE, INC.
JOB NO: 31-6036
DESIGNED BY: SHG
DATE: 10/16/2009
PJC 10/21/09

STUD SHEAR CONNECTORS

Beam Type Plate Girder Top Flange Width = 12"

Stud $\varnothing = 0.75$ "

No. of Studs = 4

$Z_r = \alpha d^2$ (kips / studs)			
$\alpha \backslash d$ (in)	0.5	0.75	1
13000	3.25	7.31	13.00
10600	2.65	5.96	10.60
7850	1.96	4.42	7.85
5500	1.38	3.09	5.50

ADT (2001) = 1,000

ADT (2021) = 80,000

% TRUCKS = 4.4%

DIRECTIONAL = 100%

ADT (2031) = 119,500 in one direction


ADTT = 5,258 > 2500
USE 2,000,000 CYCLES

$Z_r = \alpha d^2$ (kips / row)			
Number of Studs : 3			
$\alpha \backslash d$ (in)	0.5	0.75	1
13000	9.75	21.94	39.00
10600	7.95	17.89	31.80
7850	5.89	13.25	23.55
5500	4.13	9.28	16.50

$Z_r = \alpha d^2$ (kips / row)			
Number of Studs : 4			
$\alpha \backslash d$	0.5	0.75	1
13000	13.00	29.25	52.00
10600	10.60	23.85	42.40
7850	7.85	17.66	31.40
5500	5.50	12.38	22.00

$E_c = 150^{1.5} 33 (f'_c)^{1/4}$ (AASHTO 10.38.5.1.2)

$S_U = 0.4 d^2 (f'_c E_c)^{1/2}$ (AASHTO)			
d (in)	f'_c (psi)	E_c (psi)	S_U (kips)
0.5	3000	3320561	9.98
0.75	3000	3320561	22.46
1	3000	3320561	39.92
0.5	3500	3586616	11.20
0.75	3500	3586616	25.21
1	3500	3586616	44.82



AASHTO 10.38.2.4 The clear distance between the edge of a girder flange and the edge of the shear connector shall be not less than 1". Adjacent stud shear connectors shall not be closer than 4 diameters center to center.

GDOT calls for 3/4" \varnothing studs and 1 1/2" clear from edge of girder flange to CL of stud. Therefore, 4 studs are only allowed for beams with a minimum flange width of 12"+/-.

Shear Capacity (Z_r) = 12.38 K/Row

Ultimate Strength (S_U) = 25.21 kips

BRIDGE: I-75 over Noonday Creek
COUNTY: COBB
P.I. NO: 713640
PROJECT: NH000-0575-01(028)



J.B. TRIMBLE, INC.
JOB NO: 31-6036
DESIGNED BY: SHG
DATE: 10/16/2009


SHEAR STUD SPACING

PSC 10/21/09

Design Length = 93.25 ft.

Location (ft.)	s (in)
0.0	9.61
4.7	10.74
9.3	10.93
14.0	11.08
18.7	11.24
23.3	11.36
28.0	12.12
32.6	12.06
37.3	12.00
42.0	11.95
46.6	11.94

	Spacing 1	Spacing 2
Stud Spacing:	9 in.	11 in.



CALCULATION SHEET

PROJECT: I-75 / I-575 NORTHWEST CORRIDOR
JOB NUMBER NH000-0073-03(242)
CALC NO. BR#31

SUBJECT: Shear Stud Spacing Calculations - Spans 2&3 (beam 5)
BY: JCR DATE: 11/30/2009

SHEET NO.
SHEET REV.

Sufficient sample calculations representative of the scope and conditions in the design calculation were performed and the results compared to demonstrate the computer program adequacy.

BRIDGE: I-75 over Noonday Creek
COUNTY: COBB
P.I. NO: 713640
PROJECT: NH000-0575-01(028)



J.B. TRIMBLE, INC.
JOB NO: 31-6036
DESIGNED BY: SHG
DATE: 10/16/2009

STUD SHEAR CONNECTORS

Beam Type Top Flange Width = 12"

Stud $\varnothing = 0.75$ "

No. of Studs = 4

$Z_r = \alpha d^2$ (kips / studs)			
$\alpha \backslash d$ (in)	0.5	0.75	1
13000	3.25	7.31	13.00
10600	2.65	5.96	10.60
7850	1.96	4.42	7.85
5500	1.38	3.09	5.50

ADT (2001) = 1,000

ADT (2021) = 80,000

% TRUCKS = 4.4%

DIRECTIONAL = 100%

ADT (2031) = 119,500 in one direction


ADTT = 5,258 > 2500
USE 2,000,000 CYCLES

$Z_r = \alpha d^2$ (kips / row)			
Number of Studs : 3			
$\alpha \backslash d$ (in)	0.5	0.75	1
13000	9.75	21.94	39.00
10600	7.95	17.89	31.80
7850	5.89	13.25	23.55
5500	4.13	9.28	16.50

$Z_r = \alpha d^2$ (kips / row)			
Number of Studs : 4			
$\alpha \backslash d$	0.5	0.75	1
13000	13.00	29.25	52.00
10600	10.60	23.85	42.40
7850	7.85	17.66	31.40
5500	5.50	12.38	22.00

$$E_c = 150^{1.5} 33 (f'_c)^{1/4} \quad (\text{AASHTO 10.38.5.1.2})$$

$S_u = 0.4 d^2 (f'_c E_c)^{1/2}$ (AASHTO)			
d (in)	f'_c (psi)	E_c (psi)	S_u (kips)
0.5	3000	3320561	9.98
0.75	3000	3320561	22.46
1	3000	3320561	39.92
0.5	3500	3586616	11.20
0.75	3500	3586616	25.21
1	3500	3586616	44.82



AASHTO 10.38.2.4 The clear distance between the edge of a girder flange and the edge of the shear connector shall be not less than 1". Adjacent stud shear connectors shall not be closer than 4 diameters center to center.

GDOT calls for 3/4" \varnothing studs and 1 1/2" clear from edge of girder flange to CL of stud. Therefore, 4 studs are only allowed for beams with a minimum flange width of 12" +/-.

Shear Capacity (Z_r) = 12.38 K/Row

Ultimate Strength (S_u) = 25.21 kips

BRIDGE: I-75 over Noonday Creek
COUNTY: COBB
P.I. NO: 713640
PROJECT: NH000-0575-01(028)



J.B. TRIMBLE, INC.
JOB NO: 31-6036
DESIGNED BY: SHG
DATE: 10/16/2009


p5c 10/21/09

SHEAR STUD SPACING

Design Length = 85.25 ft.

Location (ft.)	s (in)
0.0	9.34
4.3	10.45
8.5	10.66
12.8	10.81
17.1	10.98
21.3	11.15
25.6	11.67
29.8	11.66
34.1	11.61
38.4	11.57
42.6	11.54

	Spacing 1	Spacing 2
Stud Spacing:	9 in.	11 in.



CALCULATION COVER SHEET

PROJECT	JOB NO.	CALC NO.	SHEET
I-75 / I-575 NORTHWEST CORRIDOR	NH000-0073-03(242)	BR#31	1
SUBJECT	DISCIPLINE		
Bearing Design	STRUCTURAL		

CALCULATION STATUS DESIGNATION	PRELIMINARY	CONFIRMED	SUPSEDED	VOIDED	INCOMPLETE
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

COMPUTER PROGRAM/TYPE	SCP <input checked="" type="radio"/> YES <input type="radio"/> NO	MAINFRAME <input type="radio"/>	PC <input checked="" type="radio"/>	PROGRAM Excel	VERSION/RELEASE NO. 2003
----------------------------------	--	--	--	----------------------	---------------------------------

Note 1: Georgia Department of Transportation (GDOT) terminated Contract Number TOURDPP160072 for its convenience prior to the completion of all work under that contract and directed that the work with respect to these calculations be discontinued.

(a) These calculations were not completed at the time of GDOT's direction and the information contained herein is not complete and/or has not been fully verified or checked. These calculations are a work-in-progress and are presented only as such.

(b) Any user is cautioned that the use of these calculations and any related information or calculations, without access to factors and without proper regard for their purpose, could lead to erroneous conclusions.

(c) If any such calculations or any information contained herein is used in future work efforts or any follow on design work activity, a complete confirmation of the information contained herein should be performed prior to any such use.

(d) GTP has no responsibility for the use of this information not under its direct control.

Bearing Design calculations are included for bearings at bents 1, 2, 3 and 4.

A	As per GDOT's termination for convenience direction	9	9	JCR			11/30/09
NO.	REASON FOR REVISION	TOTAL NO. OF SHEETS	LAST SHEET NO.	BY	CHECKED	APPROVED/ ACCEPTED	DATE
RECORD OF REVISIONS							

CALCULATION SHEET

PROJECT: I-75 / I-575 NORTHWEST CORRIDOR
JOB NUMBER NH000-0073-03(242)
CALC NO. BR#31

SUBJECT: Bearing Design
BY: JCR DATE: 11/30/2009

SHEET NO.
SHEET REV.

Sufficient sample calculations representative of the scope and conditions in the design calculation were performed and the results compared to demonstrate the computer program adequacy.



BRIDGE: I-75 over Noonday Creek
COUNTY: COBB
P.I. NO: 713640
PROJECT: NH000-0575-01(028)

J.B. TRIMBLE, INC.



JOB NO: 31-6036
DESIGNED BY: SHG
DATE: 10/30/2009

SUGGESTED SHAPE AND SIZE OF SELF LUBRICATING BRONZE PLATES



SIZE AND MAXIMUM LOAD					
W	L	T	WITH SLOTS 2-3 X 1 3/16	WITH HOLES 2-1 3/16 φ	PLAIN
10	7	1			140
10	8	1 1/4			160
10	9	1 1/4			180
10 1/2	7	1			147
10 1/2	8	1 1/4			168
10 1/2	9	1 1/4			189
12	6	1	131	140	144
12	7	1	155	164	168
12	8	1 1/4	179	188	192
12	9	1 1/4			216

USE ONLY THOSE PLATES WHICH HAVE A MAXIMUM LOAD SHOWN

PURPOSE: To standardize plate sizes within the office so that plates may be stocked by suppliers, thus making them more economical.

DESIGN SPECIFICATION: Bronze plates shall conform to ASTM Designation B 22 Alloy B and supplemental specifications and shall have an allowable unit stress of 2000 psi in compression.

LIMITATIONS: Sliding plate type bearings shall not be used where the anticipated total movement (expansion plus contraction) exceeds 3 inches for assemblies without anchor bolts through the flanges and 2 inches for assemblies with anchor bolts through the flanges.

When the gradient of the girder at the bearing exceeds 4.0%, the top of the upper plate (sole plate) shall be beveled to match the girder gradient.

COEFFICIENT OF FRICTION: For design purposes a value of 0.10 shall be used.

NOTE: WIDTH OF LBS A. IS TO BE 2" LESS THAN WIDTH OF SOLE B.



BRIDGE: I-75 over Noonday Creek
COUNTY: COBB
P.I. NO: 713640
PROJECT: NH000-0575-01(028)

J.B. TRIMBLE, INC.



JOB NO: 31-6036
DESIGNED BY: SHG
DATE: 10/30/2009

PSC 11/3/09



BENTS 1 (All Beams)
3 BK (Beams 5 & 6)
4 (Beams 5 & 6)

FIXED BEARING CALCULATIONS

GENERAL INPUT:

Beam Type
R (Reaction) = 150.7 Kips
Bottom Flange Thickness, t_{FLG} = 1.25 in 32 mm
 W_{SP} = 12.00 in 305 mm
 W_{BP} = 12.00 in 305 mm
 L_{SP} = 12.00 in 305 mm
 f'_c = 3500 psi
 $F_b = 0.3f'_c$ = 1.050 ksi

AASHTO Art. 8.15.2.1.3

SOLE PLATE:

$M = RL/8$ $S = Wt^2/6$ $t_v = M/S$

F_y = 36000 psi
 $F_{yb} = .55F_y$ = 19.8 ksi
 $t_{SP} = [3/4(RW_{SP})/(L_{SP}F_{yb})]^{1/2}$ = 2.39 in.
 $t'_{SP} = t_{SP} - t_{FLG}$ = 1.14 29 mm
Rad (Radius) = 18.00 in
 $= t'_{SP} + \text{Rad} - [\text{Rad}^2 - (1/2 L_{SP})^2]^{1/2}$ = 2.17 in -----> use = 2.25 in 57 mm

AASHTO Table 10.2B

AASHTO 10.32.1A

BASE (MASONRY) PLATE: $M = (R/W)(W/2)(W/4) = RW/8$

$S_x = W_{SP}T_{BP}^2/6$ $t_v = M/S$

$L_{BP} = R/(W_{BP}F_b)$ = 11.96 in -----> use = 12.00 in 305 mm
 $t_{BP} = [3/4(RL_{BP})/(W_{BP}F_{yb})]^{1/2}$ = 2.39 in -----> use = 2.50 in 64 mm

ALLOWABLE BEARING ON CONCRETE:

$f_b = R/(L_{BP} * W_{BP})$ = 1.046 ksi $f_b < F_b \rightarrow$ OK



BASE PLATE			SOLE PLATE			BEARING DEPTH
WIDTH	LENGTH	HEIGHT	WIDTH	LENGTH	HEIGHT	
12"	12"	2.5"	12"	12"	2.25"	4.75"

BRIDGE: I-75 over Noonday Creek
COUNTY: COBB
P.I. NO: 713640
PROJECT: NH000-0575-01(028)

J.B. TRIMBLE, INC.
JBT

JOB NO: 31-6036
DESIGNED BY: SHG
DATE: 10/30/2009

PJC
11/2/09



EXPANSION BEARING CALCULATIONS

BENTS 2 BK (All Beams)
2 AH (Beams 5 & 6)
3 AH (Beams 5 & 6)

GENERAL INPUT:

Beam Type	Plate Girder	
R (Reaction) =	150.68	Kips
Bottom Flange Thick, t _{FLG} =	1.25	in
W _{SP} =	12.00	in
W _{BZP} =	12.00	in
W _{BP} =	12.00	in
L _{SP} =	9.00	in
L _{BP} =	12.00	in
		32 mm
		305 mm
		305 mm
		305 mm
		229 mm
		305 mm

ALLOWABLE BEARING ON CONCRETE:

f _e =	3500	psi
F _b = 0.3f _c =	1.050	ksi
f _b = R/(L _{BP} * W _{BP}) =	1.046	ksi
		fb < Fb --> OK

BRONZE PLATE WIDTH (W_{BZP}):

TYPE = SELF LUBRICATING ASTM B22 ALLOY 911					
BEARING CAPACITY =	2000	psi			
L _{BZP} =	6.28	in	-----> use =	7.0	in
					178 mm

BASE (MASONRY) PLATE:

Max of W _{CH} or L _{CH} =	2.50	in
M = wL ² /2 = f _b Max(W _{CH} or L _{CH}) ² /2 =	3.27	K-in
F _y =	36000	psi
F _{yb} = .55F _y =	19.8	ksi
t _{BP} = [6M/F _{yb}] ^{1/3} =	1.00	in
use =	1.00	in
		25 mm

SOLE PLATE:

t _{SP} = [3/4(RW _{SP})/(L _{SP} F _{yb})] ^{1/3} =	2.76	in.
t _{SP} = t _{SP} - t _{FLG} =	1.51	in
use =	1.50	in
Rad (Radius) =	18.00	in
T _{SP} = t _{SP} + Rad - [Rad ² - (1/2L _{BZP}) ²] ^{1/2} =	1.84	in
use =	2.00	in

BRONZE PLATE THICKNESS (t_{BZP}):

A =	0.50	in
t _{BZP} = (T _{SP} - t _{SP}) + A =	1.00	in
use =	1.00	in
		25 mm

BASE PLATE			SOLE PLATE			BRONZE PLATE			BEARING DEPTH
WIDTH	LENGTH	HEIGHT	WIDTH	LENGTH	HEIGHT	WIDTH	LENGTH	HEIGHT	
12"	12"	1"	12"	9"	1.5"	12"	7"	1"	3.5"

BRIDGE: I-75 over Noonday Creek
COUNTY: COBB
P.I. NO: 713640
PROJECT: NH000-0575-01(028)



J.B. TRIMBLE, INC.



Beams 3 & 4

JOB NO: 31-6036
DESIGNED BY: SHG
DATE: 10/30/2009

PJC
11/3/09



FIXED BEARING CALCULATIONS

BENTS 3 BK (Beams 3 & 4) 4 (Beams 3 & 4)

GENERAL INPUT:

Beam Type	Plate Girder	
R (Reaction) =	162.6 Kips	
Bottom Flange Thickness, t_{FLG} =	1.375 in	35 mm
W_{SP} =	14.00 in	356 mm
W_{BP} =	14.00 in	356 mm
L_{SP} =	11.25 in	286 mm
f'_c =	3500 psi	
$F_b = 0.3f'_c$ =	1.050 ksi	
AASHTO Art. 8.15.2.1.3		

SOLE PLATE:

$$M = RL/8$$

$$S = wt^2/6$$

$$t_s = M/S$$

F_y =	36000 psi	AASHTO Table 10.2B
$F_{yb} = .55F_y$ =	19.8 ksi	AASHTO 10.32.1A
$t_{SP} = [3/4(RW_{SP})/(L_{SP}F_{yb})]^{1/3}$ =	2.77 in.	
$t'_{SP} = t_{SP} - t_{FLG}$ =	1.39	35 mm
Rad (Radius) =	18.00 in	
$= t'_{SP} + \text{Rad} - [\text{Rad}^2 - (\frac{1}{2}L_{SP})^2]^{1/2}$ =	2.29 in -----> use =	2.50 in 64 mm

BASE (MASONRY) PLATE: $M = (R/W)(W/2)(W/4) = RW/8$

$$S_x = W_{SP}T_{BP}^2/6$$

$$t_s = M/S$$

$L_{BP} = R/(W_{BP}F_b)$ =	11.06 in -----> use =	11.25 in	286 mm
$t_{BP} = [3/4(RL_{BP})/(W_{BP}F_{yb})]^{1/3}$ =	2.22 in -----> use =	2.25 in	57 mm

ALLOWABLE BEARING ON CONCRETE:

$$f_b = R/(L_{BP} * W_{BP}) = 1.032 \text{ ksi} \quad f_b < F_b \rightarrow \text{OK}$$

BASE PLATE			SOLE PLATE			BEARING DEPTH
WIDTH	LENGTH	HEIGHT	WIDTH	LENGTH	HEIGHT	
14"	11.25"	2.25"	14"	11.25"	2.5"	4.75"

BRIDGE: I-75 over Noonday Creek
COUNTY: COBB
P.I. NO: 713640
PROJECT: NH000-0575-01(028)



J.B. TRIMBLE, INC.



Beams 3 & 4

JOB NO: 31-6036
DESIGNED BY: SHG
DATE: 10/30/2009

PJC
11/3/09



EXPANSION BEARING CALCULATIONS

BENT 2 AH (Beams 3 & 4)
3 AH (Beams 3 & 4)

GENERAL INPUT:

Beam Type	Plate Girder	
R (Reaction) =	162.6	Kips
Bottom Flange Thick, t_{FLG} =	1.375	in
W_{SP} =	14.00	in
W_{BZP} =	12.00	in
W_{BP} =	14.00	in
L_{SP} =	10.00	in
L_{BP} =	11.25	in
		35 mm
		356 mm
		305 mm
		356 mm
		254 mm
		286 mm

ALLOWABLE BEARING ON CONCRETE:

f'_c =	3500	psi
$F_b = 0.3f'_c$ =	1.050	ksi
$f_b = R/(L_{BP} * W_{BP})$ =	1.032	ksi
		$f_b < F_b \rightarrow OK$

BRONZE PLATE WIDTH (W_{BZP}):

TYPE = SELF LUBRICATING ASTM B22 ALLOY 911				
BEARING CAPACITY =	2000	psi		
L_{BZP} =	6.77	in	-----> use =	8.0 in 203 mm

BASE (MASONRY) PLATE:

Max of W_{CH} or L_{CH} =	1.63	in
$M = wL^2/2 = f_b \text{ Max}(W_{CH} \text{ or } L_{CH})^2/2$ =	1.36	K-in
F_y =	36000	psi
$F_{yb} = .55F_y$ =	19.8	ksi
$t_{BP} = [6M/F_{yb}]^{1/3}$ =	0.64	in
	use =	0.75 in 19 mm
		AASHTO Table 10.2B
		AASHTO 10.32.1A

SOLE PLATE:

$t_{SP} = [3/4(RW_{SP})/(L_{SP}F_{yb})]^{1/3}$ =	2.94	in.
$t'_{SP} = t_{SP} - t_{FLG}$ =	1.56	in
Rad (Radius) =	18.00	in
$T_{SP} = t'_{SP} + \text{Rad} - [(Rad^2 - (1/2 L_{BZP})^2)^{1/2}]$ =	2.20	in
	use =	2.25 in

BRONZE PLATE THICKNESS (t_{BZP}):

A =	0.75	in
$t_{BZP} = (T_{SP} - t'_{SP}) + A$ =	1.25	in
	use =	1.25 in 32 mm

BASE PLATE			SOLE PLATE			BRONZE PLATE			BEARING DEPTH
WIDTH	LENGTH	HEIGHT	WIDTH	LENGTH	HEIGHT	WIDTH	LENGTH	HEIGHT	
14"	11.25"	0.75"	14"	10"	1.75"	12"	8"	1.25"	3.75"

BRIDGE: I-75 over Noonday Creek
COUNTY: COBB
P.I. NO: 713640
PROJECT: NH000-0575-01(028)



J.B. TRIMBLE, INC.



Beams 1 & 2

JOB NO: 31-6036
DESIGNED BY: SHG
DATE: 10/30/2009

PJC
11/3/09



FIXED BEARING CALCULATIONS

BENTS 3 BK (Beams 1 & 2) 4 (Beams 1 & 2)

GENERAL INPUT:

Beam Type	Plate Girder	
R (Reaction) =	171.1 Kips	
Bottom Flange Thickness, t_{FLG} =	1.375 in	35 mm
W_{SP} =	16.00 in	406 mm
W_{BP} =	16.00 in	406 mm
L_{SP} =	10.25 in	260 mm
f'_c =	3500 psi	
$F_b = 0.3f'_c$ =	1.050 ksi	
AASHTO Art. 8.15.2.1.3		

SOLE PLATE:

$$M = RL/8 \quad S = wt^2/6 \quad f_y = M/S$$

F_y =	36000 psi		
$F_{yb} = .55F_y$ =	19.8 ksi		
$t_{SP} = [3/4(RW_{SP})/(L_{SP}F_{yb})]^{1/2}$ =	3.18 in.		
$t'_{SP} = t_{SP} - t_{FLG}$ =	1.81		46 mm
Rad (Radius) =	18.00 in		
$= t'_{SP} + \text{Rad} - [\text{Rad}^2 - (\frac{1}{2}L_{SP})^2]^{1/2}$ =	2.55 in	-----> use =	2.75 in 70 mm
AASHTO Table 10.2B AASHTO 10.32.1A			

BASE (MASONRY) PLATE: $M = (R/W)(W/2)(W/4) = RW/8$

$$S_x = W_{SP}T_{BP}^2/6 \quad f_y = M/S$$

$L_{BP} = R/(W_{BP}F_b)$ =	10.18 in	-----> use =	10.25 in	260 mm
$t_{BP} = [3/4(RL_{BP})/(W_{BP}F_{yb})]^{1/2}$ =	2.04 in	-----> use =	2.25 in	57 mm

ALLOWABLE BEARING ON CONCRETE:

$$f_b = R/(L_{BP} * W_{BP}) = 1.043 \text{ ksi} \quad f_b < F_b \rightarrow \text{OK}$$

BASE PLATE			SOLE PLATE			BEARING DEPTH
WIDTH	LENGTH	HEIGHT	WIDTH	LENGTH	HEIGHT	
16"	10.25"	2.25"	16"	10.25"	2.75"	5"

BRIDGE: I-75 over Noonday Creek
COUNTY: COBB
P.I. NO: 713640
PROJECT: NH000-0575-01(028)



J.B. TRIMBLE, INC.



JOB NO: 31-6036
DESIGNED BY: SHG
DATE: 10/30/2009

Beams 1 & 2

PJC
11/3/09



EXPANSION BEARING CALCULATIONS

BENT 2 AH (Beams 1 & 2)
3 AH (Beams 1 & 2)

GENERAL INPUT:

Beam Type	Plate Girder	
R (Reaction) =	171.1	Kips
Bottom Flange Thick, t_{FLG} =	1.375	in
W_{SP} =	16.00	in
W_{BZP} =	12.00	in
W_{BP} =	16.00	in
L_{SP} =	10.00	in
L_{BP} =	10.25	in
		35 mm
		406 mm
		305 mm
		406 mm
		254 mm
		260 mm

ALLOWABLE BEARING ON CONCRETE:

f'_c =	3500	psi
$F_b = 0.3f'_c$ =	1.050	ksi
$f_b = R/(L_{BP} * W_{BP})$ =	1.043	ksi
		fb < Fb -> OK

BRONZE PLATE WIDTH (W_{BZP}):

TYPE = SELF LUBRICATING ASTM B22 ALLOY 911					
BEARING CAPACITY =	2000	psi			
L_{BZP} =	7.13	in	-----> use =	8.0	in 203 mm

BASE (MASONRY) PLATE:

Max of W_{CH} or L_{CH} =	2.00	in
$M = wL^2/2 = f_b \text{ Max}(W_{CH} \text{ or } L_{CH})^2/2$ =	2.09	K-in
F_y =	36000	psi
$F_{yb} = .55F_y$ =	19.8	ksi
$t_{BP} = [6M/F_{yb}]^{1/3}$ =	0.80	in
	use =	1.00 in 25 mm
		AASHTO Table 10.2B
		AASHTO 10.32.1A

SOLE PLATE:

$t_{SP} = [3/4(RW_{SP})/(L_{SP}F_{yb})]^{1/3}$ =	3.22	in.
$t'_{SP} = t_{SP} - t_{FLG}$ =	1.85	in
Rad (Radius) =	18.00	in
$T_{SP} = t'_{SP} + Rad + [Rad^2 - (1/2 L_{BZP})^2]^{1/2}$ =	2.45	in
	use =	2.50 in

BRONZE PLATE THICKNESS (t_{BZP}):

A =	0.75	in
$t_{BZP} = (T_{SP} - t'_{SP}) + A$ =	1.25	in
	use =	1.25 in 32 mm

BASE PLATE			SOLE PLATE			BRONZE PLATE			BEARING DEPTH
WIDTH	LENGTH	HEIGHT	WIDTH	LENGTH	HEIGHT	WIDTH	LENGTH	HEIGHT	
16"	10.25"	1"	16"	10"	2"	12"	8"	1.25"	4.25"

CALCULATION COVER SHEET

PROJECT	JOB NO.	CALC NO.	SHEET
I-75 / I-575 NORTHWEST CORRIDOR	NH000-0073-03(242)	BR#31	1
SUBJECT	DISCIPLINE		
Substructure Design Input	STRUCTURAL		

CALCULATION STATUS DESIGNATION	PRELIMINARY	CONFIRMED	SUPSEDED	VOIDED	INCOMPLETE
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

COMPUTER PROGRAM/TYPE	SCP	MAINFRAME	PC	PROGRAM	VERSION/RELEASE NO.
	<input checked="" type="radio"/> YES <input type="radio"/> NO	<input type="radio"/>	<input checked="" type="radio"/>	Excel	2003

Note 1: Georgia Department of Transportation (GDOT) terminated Contract Number TOURDPP160072 for its convenience prior to the completion of all work under that contract and directed that the work with respect to these calculations be discontinued.

(a) These calculations were not completed at the time of GDOT's direction and the information contained herein is not complete and/or has not been fully verified or checked. These calculations are a work-in-progress and are presented only as such.

(b) Any user is cautioned that the use of these calculations and any related information or calculations, without access to factors and without proper regard for their purpose, could lead to erroneous conclusions.

(c) If any such calculations or any information contained herein is used in future work efforts or any follow on design work activity, a complete confirmation of the information contained herein should be performed prior to any such use.

(d) GTP has no responsibility for the use of this information not under its direct control.

Substructure Design Input calculations are included for bents 2 and 3.

A	As per GDOT's termination for convenience direction	9	9	JCR			11/30/09
NO.	REASON FOR REVISION	TOTAL NO. OF SHEETS	LAST SHEET NO.	BY	CHECKED	APPROVED/ ACCEPTED	DATE
RECORD OF REVISIONS							

CALCULATION SHEET

PROJECT: I-75 / I-575 NORTHWEST CORRIDOR
JOB NUMBER NH000-0073-03(242)
CALC NO. BR#31

SUBJECT: Bent Design Input - Bent 2
BY: JCR DATE: 11/30/2009

SHEET NO.
SHEET REV.

Sufficient sample calculations representative of the scope and conditions in the design calculation were performed and the results compared to demonstrate the computer program adequacy.

PSC 10/24/09

PIER DESIGN CALCULATIONS

BENT 2


GENERAL REQUIREMENTS:

Live Load cases:	See GDOT Program BRLLCA														
Skew Angle:	63.50	° FROM CL BRIDGE		Is Bent Fix "F" or Exp. "E"?	E	F = Fix									
	26.5	° FROM CL BENT				E = Exp									
Concrete Strength:	3500	psi													
Rebar Strength:	60000	psi													
Ec =	3587	ksi		AASHTO 8.7.1											
Es =	29000	ksi		AASHTO 8.7.2											
Allowable Steel Stress:	24000	psi		AASHTO 8.15.2.2											
n = Ec/Es =	8			AASHTO 8.15.3.4											
Cap Bar size:	11	#													
Stirup Size:	5	#													
Maximum bars / row in cap:	12	bars													
Column Steel Ratios:	1	% min.													
	8	% max.													
Edge of Column to main rebar:	3.135	in.													
Impact Factor	<table><tr><th>Length (ft)</th><th>Impact</th></tr><tr><td>LEFT SPAN</td><td>80.75 1.243</td></tr><tr><td>RIGHT SPAN</td><td>95.00 1.227</td></tr><tr><td>Avg. Impact =</td><td>1.24</td></tr></table>						Length (ft)	Impact	LEFT SPAN	80.75 1.243	RIGHT SPAN	95.00 1.227	Avg. Impact =	1.24	
Length (ft)	Impact														
LEFT SPAN	80.75 1.243														
RIGHT SPAN	95.00 1.227														
Avg. Impact =	1.24														
Soil Weight	0.120	ksf													
Columns:	<table><tr><td>TYPE</td><td>S</td><td>(S-SQUARE or RECTANGULAR, C-CIRCULAR, P-PILES)</td></tr></table>						TYPE	S	(S-SQUARE or RECTANGULAR, C-CIRCULAR, P-PILES)						
TYPE	S	(S-SQUARE or RECTANGULAR, C-CIRCULAR, P-PILES)													
Pile Spacing:	0.00	ft. MIN	0	ft. MAX											
	0.00	ft. EMBED	0	ft. EDGE											
Pile Capacity:	<table><tr><td>TYPE</td><td>14 X 73</td><td>STEEL HP</td></tr><tr><td>ALLOWABLE LOAD</td><td>192</td><td>KIPS = 96 TONS</td></tr><tr><td>UPLIFT</td><td>0</td><td>KIPS =</td></tr></table>						TYPE	14 X 73	STEEL HP	ALLOWABLE LOAD	192	KIPS = 96 TONS	UPLIFT	0	KIPS =
TYPE	14 X 73	STEEL HP													
ALLOWABLE LOAD	192	KIPS = 96 TONS													
UPLIFT	0	KIPS =													

WIND ON SUPERSTRUCTURE

AASHTO 3.15.2.1.1


	Left Span	Right Span	
Parapet Height =	32 in.	32 in.	
Beam Height =	48 in.	48 in.	
"D" or "H" Dimension =	9.5 in.	9.5 in.	
Beam + Coping + Slab =	4.79 ft.	4.79 ft.	
Total Height =	7.46 ft.	7.46 ft.	
Span Lengths =	80.75 ft.	95.00 ft.	TOTAL
Wind Force Area =	301.1 ft ²	354.3 ft ²	655 ft ²
Height of Cap =	4.00 ft.	4.00 ft.	
Wind Force Arm =	5.73 ft.		




WIND ON SUBSTRUCTURE:

AASHTO 3.15.2.2

Wind Force =	0.040	ksf	PARA. & PERP.
Length of Cap =	42.00	ft.	
Width of Cap =	3.50	ft.	
CG of Cap ELEV =	952.00		
Ground Line ELEV =	935.00		
100 YR Scour ELEV =	0.00		
Depth to Point of Fixity =	2.00		
PL of Fixity ELEV =	933.00		
Bot. Cap to PL of Fixity =	17.00	ft.	CG Cap to PL of Fixity
Design Height of Column =	19.00	ft.	
Exposed Height of Column =	15.00	ft.	
Width of Column =	3.50	ft.	
Depth of Column =	3.50	ft.	
No. of Columns =	2	columns	
	PARA.	PERP.	
M _{cap} =	10.64	127.68	k-ft.
M _{col} =	19.95	39.90	k-ft.
M _{total} =	30.59	167.58	k-ft.
	PT = 1.61	PL = 8.82	kips





PIER DESIGN CALCULATIONS

BENT 2

WIND ON LIVE LOAD

AASHTO 3.15.2.1.2

Length = 67.88 ft.
APT = APL = 12.79 ft. Use--> 13.00 ft.

TRACTION FORCE: For One lane

AASHTO 3.9

LF = 0.00 k

TEMPERATURE FORCE:

AASHTO 3.16

Friction Force due to Temperature:

Δ = Temp. Deflection = ALPHA x Length x Change in Temp.

$T_{Rise} = 30^{\circ}$ $T_{Fall} = 40^{\circ}$ (Fahrenheit)
Material (C or S): C ALPHA = 0.000006 / $^{\circ}$ (Fahrenheit)

Force in Pad = $F_s = [G \times L \times W \times \text{Deflection}] / (T_{elas})$

	LEFT	RIGHT	
Expansion Length =	80.75	95.00	ft
Δ =	0.233	0.274	in
G = Shear Modulus of Pad =	200	200	psi
L = Length of Pad =	10.50	10.50	in
W = Width of Pad =	12.00	12.00	in
Telas = Bearing Elastomer Depth =	4.250	4.250	in
F_s =	1.38	1.62	KIPS /pad
No. of Beams =	6	6	
Total Temperature Force =	8.27	9.73	kips @ top of seat
	9.14	10.76	kips @ center of cap
P_L =	8.18	9.63	kips
P_T =	4.08	4.80	kips
Difference =	$P_L = 1.44$	kips	AT CL CAP
	$P_T = 0.72$	kips	AT CL CAP
	$P_L = 1.58$	kips	AT CL CAP ----->
	$P_T = 0.79$	kips	AT CL CAP

Use Total Lateral Force
= PL + Equiv. Lateral Force from MDL
due to eccentricity


Expansion of Concrete Cap = 0.00018 in/in
Contraction of Concrete Cap = 0.00044 in/in which includes 0.0002 for creep

STREAM FORCE:

AASHTO 3.18.1

100 yr Flood ELEV. = 942.5 ft.
Point of Fixity = 19.00 ft.
Bottom of Stream ELEV = 935.00 ft.
Pt. of Fixity ELEV = 933.00 ft.
 $V_{AVG} = 4.46$ FPS @ 100 yr. Flood
K = 1.4 for square ended piers
 $P_{AVG} = K * (V_{AVG})^2 = 27.85$ psf
 $P_{MAX} = 2 * P_{AVG} = 55.70$ psf
Piers Aligned with stream flow:
 $P_s = 0.731$ kips
M = 5.12 k-ft
 $P_{CLCAP} = 0.269$ k

AASHTO Eq. (3-4)



PIER DESIGN CALCULATIONS

BENT 2

DEAD LOAD:

AASHTO 3.3

LENGTH = 42.00 feet STEP HT = 0.000 ft
SKEW = 63.50 degrees STEP WT = 1.667 ft
SPAN 2

BEAM	BEAM SPACING	DISTANCE BETWEEN	DISTANCE ALONG	R dl	Addl DL	DL
1		-0.650	-0.650	71.1	0.00	71.1
2	7.750	8.660	8.010	71.1	0.00	71.1
3	7.750	8.660	16.670	71.1	0.00	71.1
4	7.750	8.660	25.330	71.1	0.00	71.1
5	7.750	8.660	33.990	71.1	0.00	71.1
6	7.750	8.660	42.650	71.1	0.0	71.1
		-0.650	42.000			
TOTAL		42.000				426.5
SPAN	3				CL Brg to CL Bent =	0.583

BEAM	BEAM SPACING	DISTANCE BETWEEN	DISTANCE ALONG	R dl	Addl DL	DL
1		-0.650	-0.650	104.0	0.00	104.0
2	7.750	8.660	8.010	104.0	0.0	104.0
3	7.750	8.660	16.670	95.6	0.0	95.6
4	7.750	8.660	25.330	95.6	0.0	95.6
5	7.750	8.660	33.990	83.8	0.0	83.8
6	7.750	8.660	42.650	83.8	0.00	83.8
		-0.650	42.000			
TOTAL		42.000				566.8
					CL Brg to CL Bent =	0.583
						993.3

COMBINED LOADS

COLUMN = 1.750 FT - checking ¼ points on column

POINT	MEMBER		DISTANCE ALONG	R dl	Addl DL	DL	CHECK POINT
8.25	G1 1	8.900	-0.650	175.1	0.0	175.1	1
	EC 1	8.025	7.375				2
25.50	EC 2	0.875	9.125				3
	G2 2	-1.115	8.010	175.1	0.0	175.1	4
	CHECK 2	4.330	12.340				5
	G3 2	4.330	16.670	166.6	0.0	166.6	6
	CHECK 2	4.330	21.000				7
	G4 2	4.330	25.330	166.6	0.0	166.6	8
	CHECK 2	4.330	29.660				9
	G5 2	8.660	33.990	154.9	0.0	154.9	9
	EC 2	-1.115	32.875				10
8.25	EC 3	0.875	34.625				11
	G6 3	8.025	42.650	154.9	0.0	154.9	12
			-0.650				
			42.000				

ADDITIONAL DL MOMENT DUE TO ECCENTRICITY:

$M_{DL} = 81.84$ KIP-FT
(EQUIV. LONG FORCE) $F_{EL} = M_{DL} / H_{DESIGN OF COLUMN} = 4.31$ KIP
(TOTAL LONG FORCE) $F_L = F_{EL} + P_{L TEMP} = 5.88$ KIP

LIVE LOADS:

AASHTO 3.4

Span Lengths = LEFT 80.75 RIGHT 95.00 ft
LIVE LOAD REACTION 65.90 KIPS AXLE LOAD NO IMPACT
82.24 KIPS LANE LOAD NO IMPACT
AVERAGE IMPACT 1.24
P-LOAD FOR BRLLCA INPUT 51 KIPS

VERIFY !!!!

CENTRIFUGAL FORCE:

AASHTO 3.10

LIVE LOAD REACTION = 65.90 KIPS AXLE LOAD NO IMPACT
Speed (S) = 70 mph
Curve Radius (R) = 3880 ft.
 $C = 6.68 S^2 / R = 8.44$ %
Cent. Force @ 6ft above Rdwy = 5.56 kips

CALCULATION SHEET

PROJECT: I-75 / I-575 NORTHWEST CORRIDOR
JOB NUMBER NH000-0073-03(242)
CALC NO. BR#31

SUBJECT: Bent Design Input - Bent 3
BY: JCR DATE: 11/30/2009

SHEET NO.
SHEET REV.

Sufficient sample calculations representative of the scope and conditions in the design calculation were performed and the results compared to demonstrate the computer program adequacy.

BRIDGE: I-75 over Noonday Creek
COUNTY: COBB
P.I. NO: 713640
PROJECT: NH000-0575-01(028)

J.B. TRIMBLE, INC.
JBT

JOB NO: 31-6036
DESIGNED BY: SHG
DATE: 10/24/2009

*PSC
10/29/09*

PIER DESIGN CALCULATIONS

BENT 3


GENERAL REQUIREMENTS:

Live Load cases:	See GDOT Program BRLLCA													
Skew Angle:	63.50	° FROM CL BRIDGE		Is Bent Fix "F" or Exp. "E"?	e	F = Fix								
	26.5	° FROM CL BENT				E = Exp								
Concrete Strength:	3500	psi												
Rebar Strength:	60000	psi												
Ec =	3587	ksi		AASHTO 8.7.1										
Es =	29000	ksi		AASHTO 8.7.2										
Allowable Steel Stress:	24000	psi		AASHTO 8.15.2.2										
n = Ec/Es =	8			AASHTO 8.15.3.4										
Cap Bar size:	11	#												
Stirup Size:	5	#												
Maximum bars / row in cap:	12	bars												
Column Steel Ratios:	1	% min.												
	8	% max.												
Edge of Column to main rebar:	3.135	in.												
Impact Factor	<table><tr><th>Length (ft)</th><th>Impact</th></tr><tr><td>LEFT SPAN</td><td>95.00 1.227</td></tr><tr><td>RIGHT SPAN</td><td>95.00 1.227</td></tr><tr><td>Avg. Impact =</td><td>1.23</td></tr></table>						Length (ft)	Impact	LEFT SPAN	95.00 1.227	RIGHT SPAN	95.00 1.227	Avg. Impact =	1.23
Length (ft)	Impact													
LEFT SPAN	95.00 1.227													
RIGHT SPAN	95.00 1.227													
Avg. Impact =	1.23													
Soil Weight	0.120	ksf												
Columns:	TYPE S (S-SQUARE or RECTANGULAR, C-CIRCULAR, P-PILES)													
Pile Spacing:	0.00	ft. MIN	0	ft. MAX										
	0.00	ft. EMBED	0	ft. EDGE										
Pile Capacity:	TYPE 14 X 73 STEEL HP													
ALLOWABLE LOAD		192	KIPS =	96	TONS									
UPLIFT		0	KIPS =											

WIND ON SUPERSTRUCTURE

AASHTO 3.15.2.1


	Left Span	Right Span	
Parapet Height =	32 in.	32 in.	
Beam Height =	48 in.	48 in.	
'D' or 'H' Dimension =	9.5 in.	9.5 in.	
Beam + Copping + Slab =	4.79 ft.	4.79 ft.	
Total Height =	7.46 ft.	7.46 ft.	
Span Lengths =	95.00 ft.	95.00 ft.	TOTAL
Wind Force Area =	354.3 ft ²	354.3 ft ²	709 ft ²
Height of Cap =	4.00 ft.	4.00 ft.	
Wind Force Arm =	5.73 ft.		




WIND ON SUBSTRUCTURE:

AASHTO 3.15.2.2

Wind Force =	0.040	ksf	PARA. & PERP.
Length of Cap =	49.00	ft.	
Width of Cap =	3.50	ft.	
CG of Cap ELEV =	952.00		
Ground Line ELEV =	933.00		
100 YR Scour ELEV =	0.00		
Depth to Point of Fixity =	2.00		
Pt. of Fixity ELEV =	931.00		
Bot. Cap to Pt. of Fixity =	19.00	ft.	CG Cap to Pt. of Fixity
Design Height of Column =	21.00	ft.	
Exposed Height of Column =	17.00	ft.	
Width of Column =	3.50	ft.	
Depth of Column =	3.50	ft.	
No. of Columns =	2	columns	
M _{cap} =	11.76	164.64	k-ft.
M _{col} =	24.99	49.98	k-ft.
M _{TOTAL} =	36.75	214.62	k-ft.
PT = 1.75	PL = 10.22	kips	





PIER DESIGN CALCULATIONS

BENT 3

WIND ON LIVE LOAD

AASHTO 3.15.2.1.2

Length = 95.00 ft.
APT = APL = 12.79 ft. Use--> 13.00 ft.

TRACTION FORCE: For One lane

AASHTO 3.9

LF = 0.00 k

TEMPERATURE FORCE:

AASHTO 3.16

Friction Force due to Temperature:

Δ = Temp. Deflection = ALPHA x Length x Change in Temp.

$T_{RESI} = 30$ ° $T_{FALL} = 40$ ° (Fahrenheit)
Material (C or S): C ALPHA = 0.000006 / ° (Fahrenheit)

Force in Pad = $F_s = (G \times L \times W \times \text{Deflection}) / (T_{elas})$

	LEFT	RIGHT	
Expansion Length =	0.00	95.00	ft
Δ =	0.000	0.274	in
G = Shear Modulus of Pad =	200	200	psi
L = Length of Pad =	10.50	10.50	in
W = Width of Pad =	12.00	12.00	in
Telas = Bearing Elastomer Depth =	4.250	4.250	in
F_s =	0.00	1.62	KIPS /pad
No. of Beams =	6	6	
Total Temperature Force =	0.00	9.73	kips @ top of seat
	0.00	10.66	kips @ center of cap
P_L =	0.00	9.54	kips
P_T =	0.00	4.76	kips
Difference =	$P_L = 9.54$	kips	AT CL CAP
	$P_T = 4.76$	kips	AT CL CAP
	$P_L = 10.34$	kips	AT CL CAP ---->
	$P_T = 5.15$	kips	AT CL CAP

Use Total Lateral Force
= PL + Equiv. Lateral Force from MDL
due to eccentricity

Expansion of Concrete Cap = 0.00018 in/in
Contraction of Concrete Cap = 0.00044 in/in which includes 0.0002 for creep

STREAM FORCE:

AASHTO 3.18.1

100 yr Flood ELEV. = 942.5 ft.
Point of Fixity = 21.00 ft.
Bottom of Stream ELEV = 933.00 ft.
Pt. of Fixity ELEV = 931.00 ft.
 $V_{AVG} = 4.46$ FPS @ 100 yr. Flood
K = 1.4 for square ended piers
 $P_{AVG} = K * (V_{AVG})^2 = 27.85$ psf
 $P_{MAX} = 2 * P_{AVG} = 55.70$ psf
Piers Aligned with stream flow:
 $P_s = 0.926$ kips
M = 7.72 k-ft.
 $P_{CL\ CAP} = 0.367$ k

AASHTO Eq. (3-4)

PIER DESIGN CALCULATIONS

BENT 3

DEAD LOAD:

AASHTO 3.3

LENGTH = 49.00 feet STEP HT = 0.000 ft
STEP WT = 1.667 ft
SKEW = 63.50 degrees
SPAN 3

BEAM	BEAM SPACING	DISTANCE BETWEEN	DISTANCE ALONG	R dl	Addl DL	DL
1		1.685	1.685	104.0	0.00	104.0
2	8.167	9.126	10.811	104.0	0.00	104.0
3	8.167	9.126	19.937	95.6	0.00	95.6
4	8.167	9.126	29.063	95.6	0.00	95.6
5	8.167	9.126	38.189	83.8	0.00	83.8
6	8.167	9.126	47.315	83.8	0.0	83.8
		1.685	49.000			
TOTAL		49.000				566.8

CL Brg to CL Bent = 0.583

SPAN 4

BEAM	BEAM SPACING	DISTANCE BETWEEN	DISTANCE ALONG	R dl	Addl DL	DL
1		1.685	1.685	104.0	0.00	104.0
2	8.167	9.126	10.811	104.0	0.0	104.0
3	8.167	9.126	19.937	95.6	0.0	95.6
4	8.167	9.126	29.063	95.6	0.0	95.6
5	8.167	9.126	38.189	83.8	0.0	83.8
6	8.167	9.126	47.315	83.8	0.00	83.8
		1.685	49.000			
TOTAL		49.000				566.8

CL Brg to CL Bent = 0.583

COMBINED LOADS

1133.5

COLUMN = 1.750 FT - checking ¼ points on column

POINT	MEMBER	DISTANCE ALONG	R dl	Addl DL	DL	CHECK POINT
9.75	G1 1	8.065	1.685	208.0	0.0	208.0 1
	EC 1	7.190	8.875			2
29.50	EC 2	0.875	10.625			3
	G2 2	0.186	10.811	208.0	0.0	208.0 4
	CHECK 2	4.563	15.374			5
	G3 2	4.563	19.937	191.1	0.0	191.1 6
	CHECK 2	4.563	24.500			7
	G4 2	4.563	29.063	191.1	0.0	191.1 8
	CHECK 2	4.563	33.626			9
	G5 2	9.126	38.189	167.7	0.0	167.7 9
	EC 2	0.186	38.375			10
9.75	EC 3	0.875	40.125			11
	G6 3	7.190	47.315	167.7	0.0	167.7 12
		1.685				
		49.000				

ADDITIONAL DL MOMENT DUE TO ECCENTRICITY:

$M_{DL} = 0.00$ KIP-FT
(EQUIV. LONG FORCE) $F_{EL} = M_{DL} / H_{DESIGN OF COLUMN} = 0.00$ KIP
(TOTAL LONG FORCE) $F_L = F_{EL} + P_L TEMP = 10.34$ KIP

LIVE LOADS:

AASHTO 3.4

Span Lengths = LEFT 95.00 RIGHT 95.00 ft
LIVE LOAD REACTION 66.11 KIPS AXLE LOAD NO IMPACT
66.80 KIPS LANE LOAD NO IMPACT
AVERAGE IMPACT 1.23
P-LOAD FOR BRLLCA INPUT 53 KIPS

VERIFY !!!!

CENTRIFUGAL FORCE:

AASHTO 3.10

LIVE LOAD REACTION = 66.11 KIPS AXLE LOAD NO IMPACT
Speed (S) = 70 mph
Curve Radius (R) = 3880 ft.
 $C = 6.68 S^2 / R = 8.44$ %
Cent. Force @ 6ft above Rdwy = 5.58 kips

CALCULATION COVER SHEET

PROJECT I-75 / I-575 NORTHWEST CORRIDOR	JOB NO. NH000-0073-03(242)	CALC NO. BR#31	SHEET 1
SUBJECT Live Load Case Output		DISCIPLINE STRUCTURAL	

CALCULATION STATUS DESIGNATION	PRELIMINARY <input type="checkbox"/>	CONFIRMED <input type="checkbox"/>	SUPSEDED <input type="checkbox"/>	VOIDED <input type="checkbox"/>	INCOMPLETE <input checked="" type="checkbox"/>
---	---	---------------------------------------	--------------------------------------	------------------------------------	---

COMPUTER PROGRAM/TYPE	SCP <input checked="" type="radio"/> YES <input type="radio"/> NO	MAINFRAME <input type="radio"/>	PC <input checked="" type="radio"/>	PROGRAM GDOT BRLLCA	VERSION/RELEASE NO. 06/26/2008
----------------------------------	--	--	--	-------------------------------	---------------------------------------

Note 1: Georgia Department of Transportation (GDOT) terminated Contract Number TOURDPPI60072 for its convenience the completion of all work under that contract and directed that the work with respect to these calculations be discontinued.

(a) These calculations were not completed at the time of GDOT's direction and the information contained herein is not and/or has not been fully verified or checked. These calculations are a work-in-progress and are presented only as such.

(b) Any user is cautioned that the use of these calculations and any related information or calculations, without access to factors and without proper regard for their purpose, could lead to erroneous conclusions.

(c) If any such calculations or any information contained herein is used in future work efforts or any follow on design work a complete confirmation of the information contained herein should be performed prior to any such use.

(d) GTP has no responsibility for the use of this information not under its direct control.

Live Load Case output is included for bents 2 and 3.

A	As per GDOT's termination for convenience direction	5	5	JCR			11/30/09
NO.	REASON FOR REVISION	TOTAL NO. OF SHEETS	LAST SHEET NO.	BY	CHECKED	APPROVED/ ACCEPTED	DATE
RECORD OF REVISIONS							

CALCULATION SHEET

PROJECT: I-75 / I-575 NORTHWEST CORRIDOR
JOB NUMBER NH000-0073-03(242)
CALC NO. BR#31

SUBJECT: Live Load Case Output - Bent 2
BY: JCR DATE: 11/30/2009

SHEET NO.
SHEET REV.

Sufficient sample calculations representative of the scope and conditions in the design calculation were performed and the results compared to demonstrate the computer program adequacy.

17-OCT-09
12:22:53

GEORGIA DEPARTMENT OF TRANSPORTATION
PRECONSTRUCTION DIVISION - OFFICE OF BRIDGE & STRUCTURAL DESIGN
SUMMARY OF THE LIVE LOAD CASE PROGRAM
REVISED: JUNE 26, 2008

PROB. NO.

I-75 OVER NOONDAY CREEK - BT 2

[illegible]

CALCULATION SHEET

PROJECT: I-75 / I-575 NORTHWEST CORRIDOR
JOB NUMBER NH000-0073-03(242)
CALC NO. BR#31

SUBJECT: Live Load Case Output - Bent 3
BY: JCR DATE: 11/30/2009

SHEET NO.
SHEET REV.

Sufficient sample calculations representative of the scope and conditions in the design calculation were performed and the results compared to demonstrate the computer program adequacy.

GEORGIA DEPARTMENT OF TRANSPORTATION
PRECONSTRUCTION DIVISION - OFFICE OF BRIDGE & STRUCTURAL DESIGN
SUMMARY OF THE LIVE LOAD CASE PROGRAM
REVISED: JUNE 26, 2008

I-75 OVER NOONDAY CREEK - BT 3

[illegible]

QJC
10/26/09

CALCULATION COVER SHEET

PROJECT	JOB NO.	CALC NO.	SHEET
I-75 / I-575 NORTHWEST CORRIDOR	NH000-0073-03(242)	BR#31	1
SUBJECT	DISCIPLINE		
Intermediate Bent Design Output	STRUCTURAL		

CALCULATION STATUS DESIGNATION	PRELIMINARY	CONFIRMED	SUPSEDED	VOIDED	INCOMPLETE
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

COMPUTER PROGRAM/TYPE	SCP	MAINFRAME	PC	PROGRAM	VERSION/RELEASE NO.
	<input checked="" type="radio"/> YES <input type="radio"/> NO	<input type="radio"/>	<input checked="" type="radio"/>	GDOT BRPIER	06/26/2008

Note 1: Georgia Department of Transportation (GDOT) terminated Contract Number TOURDPP160072 for its convenience the completion of all work under that contract and directed that the work with respect to these calculations be discontinued.

- (a) These calculations were not completed at the time of GDOT's direction and the information contained herein is not and/or has not been fully verified or checked. These calculations are a work-in-progress and are presented only as such.
- (b) Any user is cautioned that the use of these calculations and any related information or calculations, without access to factors and without proper regard for their purpose, could lead to erroneous conclusions.
- (c) If any such calculations or any information contained herein is used in future work efforts or any follow on design work a complete confirmation of the information contained herein should be performed prior to any such use.
- (d) GTP has no responsibility for the use of this information not under its direct control.

Intermediate bent design output is included for bents 2 and 3.

A	As per GDOT's termination for convenience direction	13	13	JCR			11/30/09
NO.	REASON FOR REVISION	TOTAL NO. OF SHEETS	LAST SHEET NO.	BY	CHECKED	APPROVED/ ACCEPTED	DATE
RECORD OF REVISIONS							

CALCULATION SHEET

PROJECT: I-75 / I-575 NORTHWEST CORRIDOR
JOB NUMBER NH000-0073-03(242)
CALC NO. BR#31

SUBJECT: Bent Design Output - Bent 2
BY: JCR DATE: 11/30/2009

SHEET NO.
SHEET REV.

Sufficient sample calculations representative of the scope and conditions in the design calculation were performed and the results compared to demonstrate the computer program adequacy.

24-OCT-09
15:35:16

GEORGIA DEPARTMENT OF TRANSPORTATION
PRECONSTRUCTION DIVISION - OFFICE OF BRIDGE & STRUCTURAL DESIGN
THE ANALYSIS AND DESIGN OF PIERS FOR BRIDGES - V 4.2.07 - AASHTO SPECS 1984 INTERIM
REVISED: JUNE 30, 2008
I-75 OVER NOONDAY CREEK - BENT 2

PROB. NO.

PSC 10/24/09

DESIGN DATA																										
DESIGN NO.	NO.	NO.	SKW	ANG	F'C	FC	N	FY	FS	EC	ES	CONC.	Z	* * *												
OPTIONS	CAN	COL	LLC	D	M	S	PSI	PSI	PSI	PSI	KSI	KSI	STRAIN	FACT												
D	D	D	L	2	2	13	0-00-00	3500.	1400.	8.	60000.	24000.	3587.	29000.	0.0030	170.	11	5	10	11	6	4	2.00	4.00	3.00	2.00

COLUMN REINFORCING STEEL															R	KL	OC	OF	CM	BD1	BD2	IMPACT	SOIL	WT	ALL.S.P.	MIN	MAX	EDGE	PILE	REBAR	ALL.PILE	ALL.PILE	I
MIN.P	MAX.P	CL.SP.	CLEAR	MODE	COEF								%	KCF	KSF	PL	SP	PL	SP	DIST	DEPTH	CLEAR	CAPACITY	UPLIFT	P								
1.00	8.00	2.25	2.625	2	2.00	0.00	0.90	0.00	1.00	0.00	0.00	24.00	0.120	0.000	3.00	5.00	1.500	1.000	1.000	192.000	0.000	P											

CAP DATA

CN	C	L	A	DE	BC	BE	DH	LH	XB1	XB2	XB3	XB4	XB5	XB6	XB7	XB8
11	C	8.250	0.000	4.000	3.500	0.000	0.000	0.000	6.625	5.750						
12	C	25.500	0.000	4.000	3.500		0.000	0.000	0.875	0.250	3.875	3.875	3.875	3.875	7.750	0.250
13	C	8.250	0.000	4.000	3.500	0.000	0.000	0.000	0.875	5.750						

COLUMN DATA

CN	P	I	T	S	HT	A	DT	BT	DB	BB	DL	PLEX	ND	NB	SZ	ND	NB	SZ	ND	NB	SZ	SLOPE	EP	AP			
21	O	C	T		19.000	0.000	3.500	3.500	0.000	0.000	2.000	0.000	2	4	11	0	0	0	99	99	11	0	0	0	0.000	0.000	0.000
22	O	C	T		19.000	0.000	3.500	3.500	0.000	0.000	2.000	0.000	2	4	11	0	0	0	99	99	11	0	0	0	0.000	0.000	0.000

FOOTING DATA

CN	S/P	B	D	T	DEL.B	DEL.D	DEL.T	R.B/D	R.D/B	S.H.T.	NP	SYM.	BP	DP	SET.
31	P	6.000	6.000	3.500	0.500	0.500	0.500	0.000	0.000	0.000	4	1	0.000	0.000	0.000
32	P	6.000	6.000	3.500	0.500	0.500	0.500	0.000	0.000	0.000	4	1	0.000	0.000	0.000

GROUP II WIND

SUPERSTRUCTURE AREA*STD.				WIND ON SUPERSTRUCTURE INTENSITIES										* WIND FORCE ARM		* WIND ON PIER	
TRANS.	LONG.	WIND	FT1	FL1	FT2	FL2	FT3	FL3	FT4	FL4	FT5	FL5	APT	APL	PT	PL	
655.	655.	1	50	0	44	6	41	12	33	16	17	19	5.729	5.729	1.610	8.820	

GROUP III WIND

STD. * WIND ON SUPERSTRUCTURE INTENSITIES										STD. * WIND ON LIVE LOAD INTENSITIES										* LENGTHS OF LL * WIND ON LL ARMS					
WIND	FT1	FL1	FT2	FL2	FT3	FL3	FT4	FL4	FT5	FL5	WIND	FT1	FL1	FT2	FL2	FT3	FL3	FT4	FL4	FT5	FL5	TRANS.	LONGI.	APT	APL
50	0	44	6	41	12	33	16	17	19	1	100	0	88	12	82	24	66	32	34	38	87.9	87.9	13.000	13.000	

MISCELLANEOUS FORCES

CENTRI.		TRACTION FORCE AND ARMS		EXPANSION		SHRINKAGE		STREAM FLOW	
FT	PL	APT	APL	COEFFICIENT	COEFFICIENT	PT	PL		
5.560	0.000	13.000	13.000	0.00018000	0.00044000	1.056	5.885		

DEAD LOAD SUPERSTRUCTURE AND LIVE LOAD CASES

I.D.	NL	P1	P2	P3	P4	P5	P6	P7	P8	P9	P10	P11	P12
D.L.	0	154.900	0.000	0.000	154.900	0.000	166.600	0.000	166.600	175.100	0.000	0.000	175.100
LL 1	1	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	39.483	0.000	0.000	62.516
LL 2	2	0.000	0.000	0.000	0.000	0.000	3.290	0.000	62.516	75.677	0.000	0.000	62.516
LL 3	3	0.000	0.000	0.000	18.096	0.000	65.806	0.000	83.903	75.677	0.000	0.000	62.516
LL 4	1	42.774	0.000	0.000	8.225	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
LL 5	2	59.225	0.000	0.000	70.741	0.000	23.032	0.000	0.000	0.000	0.000	0.000	0.000
LL 6	3	59.225	0.000	0.000	72.387	0.000	85.548	0.000	37.838	0.000	0.000	0.000	0.000
LL 7	1	0.000	0.000	0.000	19.741	0.000	62.516	0.000	19.741	0.000	0.000	0.000	0.000
LL 8	2	0.000	0.000	0.000	19.741	0.000	67.451	0.000	82.258	34.548	0.000	0.000	0.000
LL 9	3	34.548	0.000	0.000	82.258	0.000	72.387	0.000	82.258	34.548	0.000	0.000	0.000
LL10	2	0.000	0.000	0.000	31.258	0.000	78.967	0.000	70.741	23.032	0.000	0.000	0.000
LL11	3	0.000	0.000	0.000	31.258	0.000	78.967	0.000	72.387	85.548	0.000	0.000	37.838
LL12	2	42.774	0.000	0.000	8.225	0.000	0.000	0.000	0.000	39.483	0.000	0.000	62.516
LL13	3	42.774	0.000	0.000	8.225	0.000	3.290	0.000	62.516	75.677	0.000	0.000	62.516

MEMBER PROPERTIES

COLUMN PROPERTIES

CN	KT KTM	COTB COBT	COTBM COBTM	TLR TRL	TRC TCR	TLC TCL	DFC DFL	KL PDF	FKBR FKUBR	PCBR PCUBR	PCL FLU	UFMT UFMB	EITTB EILTB	PSIT PSIB	RGTB RGL
	1359850.6	0.5000	0.5000	0.4913	1.0000	0.5087	0.5087	0.065635	9.8	208179.9	12187.1	107356.6	313663.1	0.6	12.4
	1359850.6	0.5000	0.2814	0.0000	1.0000	0.0000	0.0000	0.5000	19.7	51658.3	17.0	107356.6	313663.1	0.0	12.4
2	1359850.6	0.5000	0.5000	0.0000	0.5087	1.0000	0.5087	0.065635	9.8	208179.9	12187.1	107356.6	313663.1	0.6	12.4
	1359850.6	0.5000	0.2814	0.4913	0.0000	1.0000	0.4913	0.5000	19.7	51658.3	17.0	107356.6	313663.1	0.0	12.4

CAP PROPERTIES

CN	CO K	KML KMR	COMLR COMRL	FMWT UFEM	FMLP1 FMRP1	FMLP2 FMRP2	FMLP3 FMRP3	FMLP4 FMRP4	FMLP5 FMRP5	FMLP6 FMRP6	FMLP7 FMRP7	FMLP8 FMRP8
2	0.5000	1313348.0	0.2726	113.7938	0.8160	1.0279	3.2314	3.7723	3.1875	2.0138	0.0474	0.0290
	1512448.0	1313348.0	0.2726	88967.5	0.0290	0.0474	0.7882	2.0138	3.1875	3.7723	1.0279	0.8160

COLUMN MOMENTS (KIP-FeET), SHEARS (KIPS), REACTIONS (KIPS)

LOAD	COL	PC	MT	TRANSVERSE						MT	LONGITUDINAL		
				V	MB	RF	ML	MR	V		MB	MF	
UNIT F.A.T CL.CAP	1	0.324	4.131	0.500	5.369	0.324	0.000	-4.131	1.000	0.500	9.500	9.500	
	2	-0.324	4.131	0.500	5.369	-0.324	-4.131	0.000	1.000	0.500	9.500	9.500	
EXPANSION OF CAP	1	0.000	88.050	13.435	167.217	0.000	0.000	-88.050	0.000	0.000	0.000	0.000	
	2	0.000	-88.050	-13.435	-167.217	0.000	88.050	0.000	0.000	0.000	0.000	0.000	
SHRINKAGE OF CAP	1	0.000	-215.234	-32.841	-408.752	0.000	0.000	215.234	0.000	0.000	0.000	0.000	
	2	0.000	215.234	32.841	408.752	0.000	-215.234	0.000	0.000	0.000	0.000	0.000	
DEAD LOAD TOTAL	1	516.726	65.659	4.597	21.685	547.963	1097.678	-1163.337	0.000	0.000	0.000	0.000	
		547.963											
	2	564.674	-50.800	-4.597	-36.545	595.912	1282.303	-1231.503	0.000	0.000	0.000	0.000	
		595.912											
STREAM FLOW	1	0.342	4.362	0.528	5.670	0.342	0.000	-4.362	5.885	2.943	55.908	55.908	
	2	-0.342	4.362	0.528	5.670	-0.342	-4.362	0.000	5.885	2.943	55.908	55.908	
CENT. FORCE 1 LN	1	4.636	22.968	2.780	29.852	4.636	0.000	-22.968	0.000	0.000	0.000	0.000	
	2	-4.636	22.968	2.780	29.852	-4.636	-22.968	0.000	0.000	0.000	0.000	0.000	
ON SUBSTR.	1	0.522	6.651	0.805	8.644	0.522	0.000	-6.651	-8.820	-4.410	-83.790	-83.790	
	2	-0.522	6.651	0.805	8.644	-0.522	-6.651	0.000	-8.820	-4.410	-83.790	-83.790	
GROUP 2 WIND 1 1	1	18.490	141.940	17.180	184.480	18.490	0.000	-141.940	-8.820	-4.410	-83.790	-83.790	
	2	-18.490	141.940	17.180	184.480	-18.490	-141.940	0.000	-8.820	-4.410	-83.790	-83.790	
GROUP 2 WIND 1 2	1	18.490	141.940	17.180	184.480	18.490	0.000	-141.940	8.820	4.410	83.790	83.790	
	2	-18.490	141.940	17.180	184.480	-18.490	-141.940	0.000	8.820	4.410	83.790	83.790	
GROUP 2 WIND 2 1	1	16.334	125.705	15.215	163.380	16.334	0.000	-125.705	-24.007	-6.375	-132.382	-132.382	
	2	-16.334	125.705	15.215	163.380	-16.334	-125.705	0.000	-24.007	-6.375	-132.382	-132.382	
GROUP 2 WIND 2 2	1	16.334	125.705	15.215	163.380	16.334	0.000	-125.705	24.007	6.375	132.382	132.382	
	2	-16.334	125.705	15.215	163.380	-16.334	-125.705	0.000	24.007	6.375	132.382	132.382	
GROUP 2 WIND 3 1	1	15.256	117.588	14.233	152.829	15.256	0.000	-117.588	-39.195	-8.340	-180.975	-180.975	
	2	-15.256	117.588	14.233	152.829	-15.256	-117.588	0.000	-39.195	-8.340	-180.975	-180.975	
GROUP 2 WIND 3 2	1	15.256	117.588	14.233	152.829	15.256	0.000	-117.588	39.195	8.340	180.975	180.975	
	2	-15.256	117.588	14.233	152.829	-15.256	-117.588	0.000	39.195	8.340	180.975	180.975	
GROUP 2 WIND 4 1	1	12.381	95.942	11.613	124.696	12.381	0.000	-95.942	-49.320	-9.650	-213.370	-213.370	
	2	-12.381	95.942	11.613	124.696	-12.381	-95.942	0.000	-49.320	-9.650	-213.370	-213.370	
GROUP 2 WIND 4 2	1	12.381	95.942	11.613	124.696	12.381	0.000	-95.942	49.320	9.650	213.370	213.370	
	2	-12.381	95.942	11.613	124.696	-12.381	-95.942	0.000	49.320	9.650	213.370	213.370	
GROUP 2 WIND 5 1	1	6.631	52.649	6.372	68.428	6.631	0.000	-52.649	-56.914	-10.632	-237.666	-237.666	
	2	-6.631	52.649	6.372	68.428	-6.631	-52.649	0.000	-56.914	-10.632	-237.666	-237.666	
GROUP 2 WIND 5 2	1	6.631	52.649	6.372	68.428	6.631	0.000	-52.649	56.914	10.632	237.666	237.666	
	2	-6.631	52.649	6.372	68.428	-6.631	-52.649	0.000	56.914	10.632	237.666	237.666	
GROUP 3 WIND 1 1	1	12.876	78.893	9.549	102.538	12.876	0.000	-78.893	-2.646	-1.323	-25.137	-25.137	
	2	-12.876	78.893	9.549	102.538	-12.876	-78.893	0.000	-2.646	-1.323	-25.137	-25.137	
GROUP 3 WIND 1 2	1	12.876	78.893	9.549	102.538	12.876	0.000	-78.893	2.646	1.323	25.137	25.137	
	2	-12.876	78.893	9.549	102.538	-12.876	-78.893	0.000	2.646	1.323	25.137	25.137	
JP 3 WIND 2 1	1	11.350	69.666	8.432	90.544	11.350	0.000	-69.666	-15.113	-2.440	-56.592	-56.592	
	2	-11.350	69.666	8.432	90.544	-11.350	-69.666	0.000	-15.113	-2.440	-56.592	-56.592	
GROUP 3 WIND 2 2	1	11.350	69.666	8.432	90.544	11.350	0.000	-69.666	15.113	2.440	56.592	56.592	
	2	-11.350	69.666	8.432	90.544	-11.350	-69.666	0.000	15.113	2.440	56.592	56.592	

COLUMN MOMENTS (KIP-FEET) , SHEARS (KIPS) , REACTIONS (KIPS)

LOAD	COL	PC	MT	TRANSVERSE			RF	ML	MR	MT	LONGITUDINAL		
				V	MB						V	MB	MF
JP 3 WIND 3 1	1	10.587	65.052	7.874	84.548		10.587	0.000	-65.052	-27.580	-3.557	-88.046	-88.046
	2	-10.587	65.052	7.874	84.548		-10.587	-65.052	0.000	-27.580	-3.557	-88.046	-88.046
GROUP 3 WIND 3 2	1	10.587	65.052	7.874	84.548		10.587	0.000	-65.052	27.580	3.557	88.046	88.046
	2	-10.587	65.052	7.874	84.548		-10.587	-65.052	0.000	27.580	3.557	88.046	88.046
GROUP 3 WIND 4 1	1	8.552	52.748	6.384	68.557		8.552	0.000	-52.748	-35.892	-4.301	-109.016	-109.016
	2	-8.552	52.748	6.384	68.557		-8.552	-52.748	0.000	-35.892	-4.301	-109.016	-109.016
GROUP 3 WIND 4 2	1	8.552	52.748	6.384	68.557		8.552	0.000	-52.748	35.892	4.301	109.016	109.016
	2	-8.552	52.748	6.384	68.557		-8.552	-52.748	0.000	35.892	4.301	109.016	109.016
GROUP 3 WIND 5 1	1	4.481	28.141	3.406	36.574		4.481	0.000	-28.141	-42.126	-4.860	-124.743	-124.743
	2	-4.481	28.141	3.406	36.574		-4.481	-28.141	0.000	-42.126	-4.860	-124.743	-124.743
GROUP 3 WIND 5 2	1	4.481	28.141	3.406	36.574		4.481	0.000	-28.141	42.126	4.860	124.743	124.743
	2	-4.481	28.141	3.406	36.574		-4.481	-28.141	0.000	42.126	4.860	124.743	124.743
LIVE LOAD LL 1	1	-12.581	-94.971	-9.429	-84.183		-12.581	0.000	94.971	0.000	0.000	0.000	0.000
	2	114.580	143.901	9.429	35.253		114.580	270.268	-414.168	0.000	0.000	0.000	0.000
LIVE LOAD LL 2	1	12.205	30.781	1.217	-7.658		12.205	0.000	-30.781	0.000	0.000	0.000	0.000
	2	191.794	-0.049	-1.217	-23.074		191.794	414.218	-414.168	0.000	0.000	0.000	0.000
LIVE LOAD LL 3	1	70.348	179.004	12.623	60.835		70.348	0.000	-179.004	0.000	0.000	0.000	0.000
	2	205.050	-140.781	-12.623	-99.058		205.050	513.532	-372.752	0.000	0.000	0.000	0.000
LIVE LOAD LL 4	1	60.342	-106.151	-6.964	-26.166		60.342	283.378	-177.227	0.000	0.000	0.000	0.000
	2	-9.343	70.272	6.964	62.045		-9.343	-70.272	0.000	0.000	0.000	0.000	0.000
LIVE LOAD LL 5	1	155.804	-77.217	-4.643	-10.996		155.804	392.366	-315.148	0.000	0.000	0.000	0.000
	2	-2.806	40.401	4.643	47.813		-2.806	-40.401	0.000	0.000	0.000	0.000	0.000
LIVE LOAD LL 6	1	190.381	101.574	9.119	71.679		190.381	353.129	-454.703	0.000	0.000	0.000	0.000
	2	39.117	-129.429	-9.119	-43.823		39.117	129.429	0.000	0.000	0.000	0.000	0.000
LIVE LOAD LL 7	1	66.982	165.914	12.612	73.713		66.982	0.000	-165.914	0.000	0.000	0.000	0.000
	2	35.016	-153.588	-12.612	-86.038		35.016	153.588	0.000	0.000	0.000	0.000	0.000
3 LOAD LL 8	1	92.791	294.451	23.455	151.190		92.791	0.000	-294.451	0.000	0.000	0.000	0.000
	2	111.207	-299.736	-23.455	-145.904		111.207	299.736	0.000	0.000	0.000	0.000	0.000
LIVE LOAD LL 9	1	178.632	217.199	18.071	126.146		178.632	205.992	-423.192	0.000	0.000	0.000	0.000
	2	96.767	-240.594	-18.071	-102.751		96.767	240.594	0.000	0.000	0.000	0.000	0.000
LIVE LOAD LL10	1	107.114	298.560	23.455	147.078		107.114	0.000	-298.560	0.000	0.000	0.000	0.000
	2	96.884	-295.624	-23.455	-150.014		96.884	295.624	0.000	0.000	0.000	0.000	0.000
LIVE LOAD LL11	1	91.411	229.345	17.138	96.286		91.411	0.000	-229.345	0.000	0.000	0.000	0.000
	2	183.987	-204.829	-17.138	-120.801		183.987	430.438	-225.609	0.000	0.000	0.000	0.000
LIVE LOAD LL12	1	47.761	-201.122	-16.393	-110.349		47.761	283.378	-82.256	0.000	0.000	0.000	0.000
	2	105.237	214.172	16.393	97.298		105.237	199.996	-414.168	0.000	0.000	0.000	0.000
LIVE LOAD LL13	1	65.292	-67.833	-5.172	-30.442		65.292	255.040	-187.207	0.000	0.000	0.000	0.000
	2	164.206	63.200	5.172	35.074		164.206	309.551	-372.752	0.000	0.000	0.000	0.000

CAP ANALYSIS AND DESIGN DATA

CAP MOMENTS AND SHEARS

MOMENTS (KIP- FEET)								**		SHEARS (KIPS)					
NT	D.L.TOT.	G1 MAX.+	G1 MAX.-	G2 MAX.+	G2 MAX.-	G3 MAX.+	G3 MAX.-	DL T.LT	DL T.RT	G1 + LT	G1 + RT	G1 - LT	G1 - RT		
P 1	-3.604	-3.604	-3.604	-3.604	-3.604	-3.604	-3.604	-4.436	-205.806	-4.436	-205.806	-4.436	-334.384		
P 2	-1232.121	-1232.121	-1971.441	-1232.121	-1232.121	-1232.121	-1674.827	-221.504	-221.504	-221.504	-221.504	-350.081	-350.081		
C 1L	-1426.981	-1426.981	-2278.807	-1426.981	-1426.981	-1426.981	-1937.057	-223.892		-223.892		-352.470			
C 1R	-1512.338	-1306.157	-2585.788	-1327.816	-1702.532	-1286.315	-2292.303		447.851		774.926		420.537		
P 3	-1121.514	-939.232	-1928.644	-949.655	-1298.655	-916.840	-1732.591	445.462	445.462	772.537	772.537	418.149	418.149		
P 4	-1010.234	-834.780	-1741.272	-841.993	-1183.645	-811.660	-1573.057	444.780	243.410	771.854	413.222	417.466	216.096		
P 5	-87.517	170.178	-372.366	24.644	-203.124	129.132	-329.091	232.831	232.831	402.644	402.644	205.517	205.517		
P 6	794.208	1683.947	553.453	850.288	736.404	1358.156	610.899	222.252	5.672	392.065	48.114	194.939	-27.490		
P 7	795.692	1659.267	547.568	795.692	795.692	1312.803	647.115	-4.906	-4.906	37.536	37.536	-38.068	-38.068		
P 8	756.183	1686.737	480.817	813.987	700.103	1352.545	560.123	-15.485	-232.065	26.957	-208.995	-48.647	-407.214		
P 9	-1124.307	-962.171	-1875.795	-950.895	-1292.547	-920.711	-1667.811	-253.223	-480.853	-230.152	-457.782	-428.371	-806.357		
P10	-1244.605	-1076.702	-2076.847	-1067.464	-1416.464	-1035.266	-1838.476	-481.535	-481.535	-458.465	-458.465	-807.040	-807.040		
C 2L	-1666.994	-1478.905	-2781.873	-1476.801	-1851.516	-1437.550	-2437.148	-483.924		-460.854		-809.428			
C 2R	-1600.954	-1600.954	-2500.114	-1600.954	-1600.954	-1600.954	-2139.373		250.152		385.875		250.152		
P11	-1383.116	-1383.116	-2163.518	-1383.116	-1383.116	-1383.116	-1850.423	247.764	247.764	383.486	383.486	247.764	247.764		
P12	-3.605	-3.604	-3.605	-3.605	-3.605	-3.604	-3.605	232.066	4.436	367.789	4.436	232.066	4.436		

PT.	CAP DESIGN DATA		LEPT STIRRUPS		RIGHT STIRRUPS		D	FC	PS	FS/FF	FS/FZ
	M+ UNF. K-FT.	M- UNF. K-FT.	TOP REINFORCE. AS NO.SIZE	BOT. REINFORCE. AS NO.SIZE	M.S.P. AV/IN BAR&SPAC	M.S.P. AV/IN BAR&SPAC					
P 1	-2.773	-2.773	1.76 4 # 11	1.76 4 # 11	0.00 0.000 #5@ 0.00	21.98 0.066 #5@ 9.35	48.00		0.10	0.000	0.005
P 2	-947.785	-1288.329	10.26 7 # 11	1.76 4 # 11	22.50 0.070 #5@ 8.89	22.50 0.070 #5@ 8.89	48.00		0.60	0.607	0.963
C 1	-1068.367	-1684.417	13.66 9 # 11	1.76 4 # 11	22.50 0.071 #5@ 8.76	11.25 0.255D#5@ 4.87	48.00		0.80	0.811	0.910
P 3	-778.741	-1259.284	10.03 7 # 11	1.76 4 # 11	11.25 0.254D#5@ 4.89	11.25 0.254D#5@ 4.89	48.00		0.59	0.779	0.942
P 4	-696.286	-1138.112	9.01 6 # 11	1.76 4 # 11	11.25 0.253D#5@ 4.89	22.50 0.097 #5@ 6.38	48.00		0.52	0.844	1.039
P 5	51.378	-205.192	2.76 4 # 11	1.76 4 # 11	21.98 0.097 #5@ 6.41	21.98 0.097 #5@ 6.41	48.00		0.26	0.427	0.000
P 6	1020.758	493.900	1.76 4 # 11	8.70 6 # 11	22.50 0.088 #5@ 7.04	0.00 0.000 #5@ 0.00	48.00		0.51	0.891	0.932
P 7	1009.848	497.780	1.76 4 # 11	8.57 6 # 11	0.00 0.000 #5@ 0.00	0.00 0.000 #5@ 0.00	48.00		0.50	0.868	0.922
P 8	1016.442	454.841	1.76 4 # 11	8.72 6 # 11	0.00 0.000 #5@ 0.00	22.50 0.095 #5@ 6.55	48.00		0.51	0.929	0.928
P 9	-780.171	-1211.000	9.74 7 # 11	1.76 4 # 11	22.50 0.104 #5@ 5.97	11.25 0.269D#5@ 4.62	48.00		0.57	0.699	0.905
P10	-869.837	-1340.733	10.84 7 # 11	1.76 4 # 11	11.25 0.269D#5@ 4.61	11.25 0.269D#5@ 4.61	48.00		0.63	0.803	1.002
C 2	-1184.701	-1795.836	14.78 10 # 11	1.76 4 # 11	11.25 0.270D#5@ 4.59	22.50 0.085 #5@ 7.27	48.00		0.86	0.728	0.847
P11	-1063.935	-1423.402	11.31 8 # 11	1.76 4 # 11	22.50 0.084 #5@ 7.36	22.50 0.084 #5@ 7.36	48.00		0.66	0.560	0.895
P12	-2.773	-2.773	1.76 4 # 11	1.76 4 # 11	21.98 0.081 #5@ 7.64	0.00 0.000 #5@ 0.00	48.00		0.10	0.000	0.005

NOTE: *** FS/FZ RATIO EXCEEDS 1.0! ***

COLUMN ANALYSIS AND DESIGN OUTPUT

CRITICAL COLUMN LOADS																
T	B	GR	LLC	WC	R	S	F	F	PF	MTF	MLF	PM	MTM	MLM	PU	MTU
1	T	1	LL10	0.0		C	S		916.8	798.9	7.7	916.8	798.9	360.5	2083.7	1816.0
1	B	1	LL 6	0.0		C	S		1142.4	296.0	72.7	1142.4	399.8	460.4	2927.9	1028.3
2	T	1	LL 8	0.0		C	S		963.0	-651.4	7.7	963.0	651.4	381.0	2381.6	1611.6
2	B	1	LL 3	0.0		C	S		1203.1	-150.4	72.7	1203.1	421.1	488.9	2922.1	1026.0

COLUMN DESIGN DATA																
T	B	FACE 1	B	FACE 2	D	FACE 3	D	FACE 4	AS	PS	BD12	BD	SUMPU	SUMPC	DEL.T	DEL.L
1	T	4 # 11	4 # 11	2 # 11	2 # 11	18.72	1.061	1.00	0.086	1889.	65190.	1.000	1.123	0.400	2	0.70
1	B	4 # 11	4 # 11	2 # 11	2 # 11	18.72	1.061	1.00	0.156	1945.	56248.	1.000	1.151	0.400	2	0.70
2	T	4 # 11	4 # 11	2 # 11	2 # 11	18.72	1.061	1.00	0.136	1889.	65137.	1.000	1.130	0.428	2	0.70
2	B	4 # 11	4 # 11	2 # 11	2 # 11	18.72	1.061	1.00	0.274	2044.	60452.	1.000	1.161	0.400	2	0.70

FOOTING 1 DESIGN LOADS																			
P	G	LLID	WC	ES	C	S	P	MT	VT	ML	VL	P4	P3	P2	P1	MTF	VBF	VPF	LOAD
		LL 9	0.0		C	S	704.880	209.685	27.204	55.908	2.943	118.004	102.240	174.835	190.599	16.866	0.000	-0.384	MAX.P1
1	1	LL 9	0.0		C	S	1041.819	361.198	48.059	72.680	3.825	162.662	142.169	268.218	288.710	25.905	0.000	-0.499	MAX.MT
1	1	LL 9	0.0		C	S	1041.819	361.198	48.059	72.680	3.825	162.662	142.169	268.218	288.710	25.905	0.000	-0.499	MAX.VT
1	1	LL 9	0.0		C	S	1041.819	361.198	48.059	72.680	3.825	162.662	142.169	268.218	288.710	25.905	0.000	-0.499	MAX.VP
1	1	LL 6	0.0		C	S	1062.390	265.837	32.385	72.680	3.825	184.659	164.167	254.449	274.941	21.174	0.000	-0.499	MAX.ML
1	1	LL 9	0.0		C	S	1041.819	361.198	48.059	72.680	3.825	162.662	142.169	268.218	288.710	20.774	0.000	-0.499	MAX.VL
1	4	LL 9	0.0	E	C	S	704.881	376.902	40.639	55.908	2.943	92.499	76.735	200.340	216.104	19.345	0.000	-0.384	MAX.P3

FOOTING SIZE			* BAR REINFORCEMENT STEEL *						SECTION CAPACITIES			
B	D	T	P1/PA	AS	NO.SIZE	SPAC.	PLACEMENT	MT.	VB	VP	DS	FC
7.200	7.200	3.500	0.993	0.22	9 # 4 @	9.500	TOP LONG	31.545	34.094	68.189	28.250	0.000
				0.27	10 # 4 @	8.625	BOT. TRAN	35.646	34.698	69.396	28.750	0.000
NUMBER OF PILES = 5 BP = 2.100 DP = 2.100												

F	G	LLID	WC	ES	C	S	P	MT	VT	ML	VL	P4	P3	P2	P1	MTF	VBF	VPF	LOAD
2	4	LL13	0.0	S	C	S	715.477	486.763	40.450	55.908	2.943	81.618	65.854	215.459	231.223	20.815	0.000	-0.384	MAX.P1
2	4	LL13	0.0	S	C	S	930.120	632.792	52.584	72.680	3.825	106.104	85.612	280.096	300.589	27.060	0.000	-0.499	MAX.MT
2	1	LL 3	0.0		C	S	1116.971	-108.789	-17.633	72.680	3.825	220.418	199.926	240.522	261.015	23.212	0.000	-0.499	MAX.VT
2	1	LL 3	0.0		C	S	1116.971	-108.789	-17.633	72.680	3.825	220.418	199.926	240.522	261.015	23.212	0.000	-0.499	MAX.VP
		LL 3	0.0		C	S	1116.971	-108.789	-17.633	72.680	3.825	220.418	199.926	240.522	261.015	22.235	0.000	-0.499	MAX.ML
2	1	LL 3	0.0		C	S	1116.971	-108.789	-17.633	72.680	3.825	220.418	199.926	240.522	261.015	22.235	0.000	-0.499	MAX.VL
2	4	LL12	0.0	S	C	S	671.166	516.047	47.553	55.908	2.943	66.310	50.547	213.042	228.806	20.580	0.000	-0.384	MAX.P3

FOOTING SIZE				* BAR REINFORCEMENT STEEL *				SECTION CAPACITIES				*
B	D	T	PI/PA	AS	NO.SIZE	SPAC.	PLACEMENT	MT.	VB	VP	DS	FC
7.200	7.200	3.500	0.963	0.23	9 # 4 @	9.500	TOP LONG	31.545	34.094	68.189	28.250	0.000
				0.28	11 # 4 @	7.750	BOT. TRAN	39.178	34.698	69.396	28.750	0.000
NUMBER OF PILES = 5 BP = 2.100 DP = 2.100												

CALCULATION SHEET

PROJECT: I-75 / I-575 NORTHWEST CORRIDOR
JOB NUMBER NH000-0073-03(242)
CALC NO. BR#31

SUBJECT: Bent Design Output - Bent 3
BY: JCR DATE: 11/30/2009

SHEET NO.
SHEET REV.

Sufficient sample calculations representative of the scope and conditions in the design calculation were performed and the results compared to demonstrate the computer program adequacy.

PROB. NO.

PRB. NO. *PSC 10/26/09*

DESIGN DATA

DESIGN NO.	NO.	NO.	SKEW	ANG	F'C	FC	N	FY	PS	EC	ES	CONC.	Z	* * *	CAP	REINFORCING	STEEL	* * *	CAP								
OPTIONS	CAN	COL	LLC	D	M	S		PSI	PSI	KSI	KSI	STRAIN	FACT	MAIN	STR	MAX	MAX	MIN	MIN	TOP							
														SIZE	SIZE	BOT	SIZE	NO.	CL.	S.SP							
D	D	D	L	2	2	13		26-30-00	3500.	1400.	8.	60000.	24000.	3587.	29000.	0.0030	170.	11	5	10	11	6	4	2.00	4.00	3.00	2.00

COLUMN REINFORCING STEEL	R	KL	OC	OF	CM	BD1	BD2	IMPACT	SOIL	WT	ALL.S.P.	MIN	MAX	EDGE	PILE	REBAR	ALL.PILE	ALL.PILE I
--------------------------	---	----	----	----	----	-----	-----	--------	------	----	----------	-----	-----	------	------	-------	----------	------------

MIN.P	MAX.P	CL.SP.	CLEAR	MODE	COEF						%	KCF	KSF	PL SP	PL SP	DIST	DEPTH	CLEAR	CAPACITY	UPLIFT	P
1.00	8.00	2.25	2.625	2	2.00	0.00	0.90	0.00	1.00	0.00	23.00	0.120	0.000	3.00	5.00	1.500	1.000	1.000	192.000	0.000	P

CAP DATA

CN	C	L	A	DE	BC	BE	DH	LH	XB1	XB2	XB3	XB4	XB5	XB6	XB7	XB8
11	C	9.750	0.000	4.250	3.500	0.000	0.000	0.000	8.065	7.190						
12	C	29.500	0.000	4.250	3.500		0.000	0.000	0.875	0.186	4.563	4.563	4.563	4.563	9.126	0.186
13	C	9.750	0.000	4.250	3.500	0.000	0.000	0.000	0.875	7.190						

COLUMN DATA

C N F I T S		HT	A	DT	BT	DB	BB	DL	FLEX	ND	NB	SZ	ND	NB	SZ	ND	NB	SZ	ND	NB	SZ	SLOPE	EP	AP	
21	0	C	T	21,000	0.000	3,500	3,500	0.000	0.000	2.125	0.000	2	4	11	0	0	99	99	11	0	0	0	0.000	0.000	0.000
22	0	C	T	21,000	0.000	3,500	3,500	0.000	0.000	2.125	0.000	2	4	11	0	0	99	99	11	0	0	0	0.000	0.000	0.000

FOOTING DATA

CN	S/P	B	D	T	DEL.B	DEL.D	DEL.T	R.B/D	R.D/B	S.H.T.	NP	SYM.	BP	DP	SET.
31	P	6.000	6.000	3.500	0.500	0.500	0.500	0.000	0.000	0.000	7	1	0.000	0.000	0.000
32	P	6.000	6.000	3.500	0.500	0.500	0.500	0.000	0.000	0.000	7	1	0.000	0.000	0.000

GROUP II WIND

SUPERSTRUCTURE AREA*STD.				WIND ON SUPERSTRUCTURE INTENSITIES										* WIND FORCE ARM		* WIND ON PIER	
TRANS.	LONG.	WIND		FT1	FL1	FT2	FL2	FT3	FL3	FT4	FL4	FT5	FL5	APT	APL	PT	PL
709.	709.	1	50	0		44	6	41	12	33	16	17	19	5.729	5.729	1.750	10.220

GROUP III WIND

* WIND ON SUPERSTRUCTURE INTENSITIES											* WIND ON LIVE LOAD INTENSITIES											* LENGTHS OF LL		* WIND ON LL ARMS	
DIR	FT1	FL1	FT2	FL2	FT3	FL3	FT4	FL4	FT5	FL5	WIND	FT1	FL1	FT2	FL2	FT3	FL3	FT4	FL4	FT5	FL5	TRANS.	LONGI.	AFT	APL
1	50	0	44	6	41	12	33	16	17	19	1	100	0	88	12	82	24	66	32	34	38	95.0	95.0	13.000	13.000

MISCELLANEOUS FORCES

CENTRI. FT	TRACTION FORCE AND ARMS			EXPANSION		SHRINKAGE		STREAM FLOW	
	FL	APT	APL	COEFFICIENT	COEFFICIENT	PT	PL		
5.580	3.480	13.000	13.000	0.00018000	0.00044000	5.521	10.336		

DEAD LOAD SUPERSTRUCTURE AND LIVE LOAD CASES

I.D.	NL	P1	P2	P3	P4	P5	P6	P7	P8	P9	P10	P11	P12
D.L.	0	167.700	0.000	0.000	167.700	0.000	191.100	0.000	191.100	208.000	0.000	0.000	208.000
LL 1	1	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	38.937	0.000	0.000	67.062
LL 2	2	0.000	0.000	0.000	0.000	0.000	0.000	0.000	62.727	82.209	0.000	0.000	67.062
LL 3	3	0.000	0.000	0.000	9.727	0.000	67.062	0.000	91.937	82.209	0.000	0.000	67.062
LL 4	1	44.336	0.000	0.000	8.663	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
LL 5	2	62.714	0.000	0.000	75.726	0.000	20.558	0.000	0.000	0.000	0.000	0.000	0.000
LL 6	3	62.714	0.000	0.000	82.209	0.000	87.621	0.000	32.454	0.000	0.000	0.000	0.000
LL 7	1	0.000	0.000	0.000	19.468	0.000	67.062	0.000	19.468	0.000	0.000	0.000	0.000
LL 8	2	0.000	0.000	0.000	19.468	0.000	74.636	0.000	86.531	31.363	0.000	0.000	0.000
LL 9	3	31.363	0.000	0.000	86.531	0.000	82.209	0.000	86.531	31.363	0.000	0.000	0.000
LL10	2	0.000	0.000	0.000	29.196	0.000	84.363	0.000	76.803	21.636	0.000	0.000	0.000
LL11	3	0.000	0.000	0.000	29.196	0.000	84.363	0.000	82.209	88.698	0.000	0.000	33.531
LL12	2	44.336	0.000	0.000	8.663	0.000	0.000	0.000	0.000	38.937	0.000	0.000	67.062
LL13	3	44.336	0.000	0.000	8.663	0.000	62.727	0.000	0.000	82.209	0.000	0.000	67.062

$$F_L = 0.05 \times \left[(2 \times \frac{8095}{2}) \times 0.64^{1/2} + 18^k \right] = \underline{348^k}$$

MEMBER PROPERTIES

COLUMN PROPERTIES

CN	KT KTM	COTB COBT	COTBM COBTM	TLR TRL	TRC TCR	TLC TCL	DFC DFL	KL PDF	FKBR FKUBR	PCBR PCUBR	PCL FLU	UFMT UFMB	EITTB EILTB	PSIT PSIB	RGTB RGL
	1230341.0	0.5000	0.5000	0.5229	1.0000	0.4771	0.4771	0.048611	10.8	172792.2	10050.3	87881.5	313663.1	0.5	12.4
	1230341.0	0.5000	0.2969	0.0000	1.0000	0.0000	0.0000	0.5000	21.9	41904.8	18.9	87881.5	313663.1	0.0	12.4
2	1230341.0	0.5000	0.5000	0.0000	0.4771	1.0000	0.4771	0.048611	10.8	172792.2	10050.3	87881.5	313663.1	0.5	12.4
	1230341.0	0.5000	0.2969	0.5229	0.0000	1.0000	0.5229	0.5000	21.9	41904.8	18.9	87881.5	313663.1	0.0	12.4

CAP PROPERTIES

CN	CO K	KML KMR	COMLR COMRL	FMWT UFEM	FMLP1 FMRP1	FMLP2 FMRP2	FMLP3 FMRP3	FMLP4 FMRP4	FMLP5 FMRP5	FMLP6 FMRP6	FMLP7 FMRP7	FMLP8 FMRP8
2	0.5000	1348463.4	0.2556	161.8121	0.8239	0.9861	3.6840	4.3662	3.6875	2.3030	0.0368	0.0252
	1568142.1	1348463.4	0.2556	79736.0	0.0252	0.0368	0.8678	2.3030	3.6875	4.3662	0.9861	0.8239

COLUMN MOMENTS (KIP-FeET), SHEARS (KIPS), REACTIONS (KIPS)

LOAD	COL	PC	MT	TRANSVERSE						MT	LONGITUDINAL		
				V	MB	RF	ML	MR	*		V	MB	MF
UNIT F.AT CL.CAP	1	0.315	4.643	0.500	5.857	0.315	0.000	-4.643		1.062	0.500	10.500	10.500
	2	-0.315	4.643	0.500	5.857	-0.315	-4.643	0.000		1.062	0.500	10.500	10.500
EXPANSION OF CAP	1	0.000	90.817	12.042	162.071	0.000	0.000	-90.817		0.000	0.000	0.000	0.000
	2	0.000	-90.817	-12.042	-162.071	0.000	90.817	0.000		0.000	0.000	0.000	0.000
SHRINKAGE OF CAP	1	0.000	-221.998	-29.437	-396.174	0.000	0.000	221.998		0.000	0.000	0.000	0.000
	2	0.000	221.998	29.437	396.175	0.000	-221.998	0.000		0.000	0.000	0.000	0.000
DEAD LOAD TOTAL	1	572.722	21.084	0.322	-14.329	607.404	1458.554	-1479.639		0.000	0.000	0.000	0.000
	2	607.404 670.210 704.893	12.078	-0.322	-18.833	704.893	1771.496	-1783.574		0.000	0.000	0.000	0.000
STREAM FLOW	1	1.738	25.633	2.760	32.337	1.738	0.000	-25.633		10.982	5.168	108.528	108.528
	2	-1.738	25.633	2.760	32.337	-1.738	-25.633	0.000		10.982	5.168	108.528	108.528
TRAC. FORCE 1 LN	1	1.173	7.209	0.776	9.095	1.173	0.000	-7.209		-23.552	-1.557	-52.944	-52.944
	2	-1.173	7.209	0.776	9.095	-1.173	-7.209	0.000		-23.552	-1.557	-52.944	-52.944
T. FORCE 1 LN	1	3.773	23.185	2.497	29.249	3.773	0.000	-23.185		18.829	1.245	42.326	42.326
	2	-3.773	23.185	2.497	29.249	-3.773	-23.185	0.000		18.829	1.245	42.326	42.326
WIND ON SUBSTR.	1	0.551	8.125	0.875	10.250	0.551	0.000	-8.125		-10.859	-5.110	-107.310	-107.310
	2	-0.551	8.125	0.875	10.250	-0.551	-8.125	0.000		-10.859	-5.110	-107.310	-107.310
GROUP 2 WIND 1 1	1	16.698	155.422	16.738	196.070	16.698	0.000	-155.422		51.257	2.799	104.086	104.086
	2	-16.698	155.422	16.738	196.070	-16.698	-155.422	0.000		51.257	2.799	104.086	104.086
GROUP 2 WIND 1 2	1	16.698	155.422	16.738	196.070	16.698	0.000	-155.422		72.975	13.019	318.706	318.706
	2	-16.698	155.422	16.738	196.070	-16.698	-155.422	0.000		72.975	13.019	318.706	318.706
GROUP 2 WIND 2 1	1	15.727	146.559	15.783	184.889	15.727	0.000	-146.559		28.853	-0.054	27.839	27.839
	2	-15.727	146.559	15.783	184.889	-15.727	-146.559	0.000		28.853	-0.054	27.839	27.839
GROUP 2 WIND 2 2	1	13.794	128.934	13.885	162.654	13.794	0.000	-128.934		80.471	13.973	344.218	344.218
	2	-13.794	128.934	13.885	162.654	-13.794	-128.934	0.000		80.471	13.973	344.218	344.218
GROUP 2 WIND 3 1	1	15.724	146.534	15.781	184.857	15.724	0.000	-146.534		10.176	-2.432	-35.724	-35.724
	2	-15.724	146.534	15.781	184.857	-15.724	-146.534	0.000		10.176	-2.432	-35.724	-35.724
GROUP 2 WIND 3 2	1	11.860	111.283	11.984	140.387	11.860	0.000	-111.283		91.695	15.402	382.413	382.413
	2	-11.860	111.283	11.984	140.387	-11.860	-111.283	0.000		91.695	15.402	382.413	382.413
GROUP 2 WIND 4 1	1	13.784	128.842	13.875	162.538	13.784	0.000	-128.842		-9.730	-4.966	-103.467	-103.467
	2	-13.784	128.842	13.875	162.538	-13.784	-128.842	0.000		-9.730	-4.966	-103.467	-103.467
GROUP 2 WIND 4 2	1	8.632	81.841	8.814	103.244	8.632	0.000	-81.841		91.723	15.406	382.509	382.509
	2	-8.632	81.841	8.814	103.244	-8.632	-81.841	0.000		91.723	15.406	382.509	382.509
GROUP 2 WIND 5 1	1	9.100	86.113	9.274	108.634	9.100	0.000	-86.113		-37.082	-8.449	-196.553	-196.553
	2	-9.100	86.113	9.274	108.634	-9.100	-86.113	0.000		-37.082	-8.449	-196.553	-196.553
GROUP 2 WIND 5 2	1	2.982	30.299	3.263	38.223	2.982	0.000	-30.299		79.321	13.827	340.302	340.302
	2	-2.982	30.299	3.263	38.223	-2.982	-30.299	0.000		79.321	13.827	340.302	340.302
GROUP 3 WIND 1 1	1	11.432	86.100	9.272	108.617	11.432	0.000	-86.100		47.434	2.959	103.287	103.287
	2	-11.432	86.100	9.272	108.617	-11.432	-86.100	0.000		47.434	2.959	103.287	103.287
UP 3 WIND 1 2	1	11.432	86.100	9.272	108.617	11.432	0.000	-86.100		53.949	6.025	167.673	167.673
	2	-11.432	86.100	9.272	108.617	-11.432	-86.100	0.000		53.949	6.025	167.673	167.673
GROUP 3 WIND 2 1	1	10.754	81.066	8.730	102.267	10.754	0.000	-81.066		29.150	1.339	54.421	54.421
	2	-10.754	81.066	8.730	102.267	-10.754	-81.066	0.000		29.150	1.339	54.421	54.421

COLUMN MOMENTS (KIP-FeET), SHEARS (KIPS), REACTIONS (KIPS)													
LOAD	COL	PC	MT	TRANSVERSE						MT	LONGITUDINAL		
				V	MB	RF	ML	MR	V		MB	MF	
GROUP 3 WIND 2 2	1	9.406	71.055	7.652	89.638	9.406	0.000	-71.055	60.067	6.567	184.023	184.023	
	2	-9.406	71.055	7.652	89.638	-9.406	-71.055	0.000	60.067	6.567	184.023	184.023	
GROUP 3 WIND 3 1	1	10.752	81.052	8.729	102.249	10.752	0.000	-81.052	13.908	-0.012	13.685	13.685	
	2	-10.752	81.052	8.729	102.249	-10.752	-81.052	0.000	13.908	-0.012	13.685	13.685	
GROUP 3 WIND 3 2	1	8.056	61.030	6.572	76.991	8.056	0.000	-61.030	69.226	7.379	208.502	208.502	
	2	-8.056	61.030	6.572	76.991	-8.056	-61.030	0.000	69.226	7.379	208.502	208.502	
GROUP 3 WIND 4 1	1	9.399	71.003	7.646	89.572	9.399	0.000	-71.003	-2.336	-1.451	-29.730	-29.730	
	2	-9.399	71.003	7.646	89.572	-9.399	-71.003	0.000	-2.336	-1.451	-29.730	-29.730	
GROUP 3 WIND 4 2	1	5.804	44.307	4.771	55.894	5.804	0.000	-44.307	69.249	7.381	208.563	208.563	
	2	-5.804	44.307	4.771	55.894	-5.804	-44.307	0.000	69.249	7.381	208.563	208.563	
GROUP 3 WIND 5 1	1	6.131	46.733	5.033	58.956	6.131	0.000	-46.733	-24.658	-3.429	-89.387	-89.387	
	2	-6.131	46.733	5.033	58.956	-6.131	-46.733	0.000	-24.658	-3.429	-89.387	-89.387	
GROUP 3 WIND 5 2	1	1.861	15.032	1.619	18.963	1.861	0.000	-15.032	59.128	6.484	181.514	181.514	
	2	-1.861	15.032	1.619	18.963	-1.861	-15.032	0.000	59.128	6.484	181.514	181.514	
LIVE LOAD LL 1	1	-14.958	-123.871	-10.929	-105.639	-14.958	0.000	123.871	0.000	0.000	0.000	0.000	
	2	120.957	182.142	10.929	47.368	120.957	358.713	-540.855	0.000	0.000	0.000	0.000	
LIVE LOAD LL 2	1	7.591	7.542	-0.838	-25.145	7.591	0.000	-7.542	0.000	0.000	0.000	0.000	
	2	204.407	31.013	0.838	-13.410	204.407	509.842	-540.855	0.000	0.000	0.000	0.000	
LIVE LOAD LL 3	1	64.171	190.534	12.046	62.425	64.171	0.000	-190.534	0.000	0.000	0.000	0.000	
	2	222.026	-146.745	-12.046	-106.214	222.026	633.515	-486.770	0.000	0.000	0.000	0.000	
LIVE LOAD LL 4	1	63.439	-126.690	-7.606	-33.046	63.439	357.570	-230.880	0.000	0.000	0.000	0.000	
	2	-10.440	86.291	7.606	73.445	-10.440	-86.291	0.000	0.000	0.000	0.000	0.000	
LIVE LOAD LL 5	1	164.786	-111.573	-6.353	-21.832	164.786	505.788	-394.216	0.000	0.000	0.000	0.000	
	2	-5.788	66.300	6.353	67.105	-5.788	-66.300	0.000	0.000	0.000	0.000	0.000	
LIVE LOAD LL 6	1	203.806	87.858	7.443	68.434	203.806	455.210	-543.068	0.000	0.000	0.000	0.000	
	2	34.692	-120.532	-7.442	-35.761	34.692	120.532	0.000	0.000	0.000	0.000	0.000	
LIVE LOAD LL 7	1	69.852	189.061	13.022	84.411	69.852	0.000	-189.061	0.000	0.000	0.000	0.000	
	2	36.146	-175.568	-13.022	-97.903	36.146	175.568	0.000	0.000	0.000	0.000	0.000	
LIVE LOAD LL 8	1	98.499	342.050	24.580	174.133	98.499	0.000	-342.050	0.000	0.000	0.000	0.000	
	2	113.499	-346.194	-24.580	-169.989	113.499	346.194	0.000	0.000	0.000	0.000	0.000	
LIVE LOAD LL 9	1	186.628	262.022	19.495	147.364	186.628	227.648	-489.670	0.000	0.000	0.000	0.000	
	2	99.569	-283.826	-19.495	-125.560	99.569	283.826	0.000	0.000	0.000	0.000	0.000	
LIVE LOAD LL10	1	110.766	345.437	24.580	170.743	110.766	0.000	-345.437	0.000	0.000	0.000	0.000	
	2	101.232	-342.803	-24.580	-173.377	101.232	342.803	0.000	0.000	0.000	0.000	0.000	
LIVE LOAD LL11	1	95.980	275.509	18.867	120.707	95.980	0.000	-275.509	0.000	0.000	0.000	0.000	
	2	190.217	-252.779	-18.867	-143.437	190.217	496.164	-243.385	0.000	0.000	0.000	0.000	
LIVE LOAD LL12	1	48.481	-250.561	-18.535	-138.685	48.481	357.570	-107.009	0.000	0.000	0.000	0.000	
	2	110.517	268.433	18.535	120.812	110.517	272.422	-540.855	0.000	0.000	0.000	0.000	
LIVE LOAD LL13	1	82.304	-93.764	-7.600	-65.841	82.304	321.813	-228.049	0.000	0.000	0.000	0.000	
	2	156.193	119.043	7.600	40.562	156.193	367.727	-486.770	0.000	0.000	0.000	0.000	

CAP ANALYSIS AND DESIGN DATA

POINT	D.L.TOT.	CAP MOMENTS AND SHEARS						SHEARS (KIPS)					
		MOMENTS (KIP-FeET)						SHEARS (KIPS)					
		G1 MAX. +	G1 MAX. -	G2 MAX. +	G2 MAX. -	G3 MAX. +	G3 MAX. -	DL T.LT	DL T.RT	G1 + LT	G1 - RT	G1 - LT	G1 - RT
P 1	-4.118	-4.118	-4.118	-4.118	-4.118	-4.118	-4.118	-4.888	-222.898	-4.888	-222.898	-4.888	-359.050
P 2	-1681.727	-1681.727	-2660.660	-1681.727	-1681.727	-1681.727	-2267.914	-243.753	-243.753	-243.753	-243.753	-379.905	-379.905
C 1L	-1896.121	-1896.121	-2994.187	-1896.121	-1896.121	-1896.121	-2553.646	-246.291		-246.291		-382.443	
C 1R	-1923.531	-1654.607	-3217.234	-1721.481	-2158.903	-1641.197	-2881.457		498.247		849.913		465.772
P 3	-1488.675	-1248.167	-2495.638	-1298.612	-1710.084	-1230.552	-2264.029	495.709	495.709	847.375	847.375	463.234	463.234
P 4	-1396.523	-1162.055	-2342.533	-1209.008	-1614.964	-1143.547	-2133.067	495.169	277.159	846.835	460.593	462.695	244.685
P 5	-162.041	151.413	-579.691	-37.031	-307.669	110.565	-516.216	263.924	263.924	447.358	447.358	231.449	231.449
P 6	1012.046	2133.348	670.798	1074.551	939.232	1723.909	755.664	250.688	2.258	434.122	29.226	218.214	-45.176
P 7	992.154	2085.791	635.103	992.154	992.154	1647.027	778.351	-10.977	-10.977	15.991	15.991	-58.412	-58.412
P 8	911.868	2078.000	510.057	984.682	849.363	1662.193	630.838	-24.213	-272.643	2.755	-245.675	-71.647	-463.001
P 9	-1697.058	-1474.869	-2700.021	-1478.616	-1884.573	-1410.705	-2424.997	-299.114	-569.514	-272.146	-542.546	-489.473	-920.501
	-1803.038	-1575.833	-2871.285	-1581.628	-1993.101	-1512.457	-2571.800	-570.053	-570.053	-543.086	-543.086	-921.040	-921.040
	-2302.945	-2052.144	-3678.305	-2067.573	-2504.994	-1992.476	-3263.749	-572.591		-545.624		-923.578	
C 2R	-2318.646	-2318.646	-3492.843	-2318.646	-2318.646	-2318.646	-3021.758		298.681		444.273		298.681
P11	-2058.411	-2058.411	-3105.214	-2058.411	-2058.411	-2058.411	-2685.240	296.143	296.143	441.735	441.735	296.143	296.143
P12	-4.118	-4.118	-4.118	-4.118	-4.118	-4.118	-4.118	275.288	4.888	420.879	4.888	275.288	4.888

PT.	M+ UNF. K-FT.	M- UNF. K-FT.	TOP REINFORCE. AS NO.SIZE		BOT.REINFORCE. AS NO.SIZE		CAP DESIGN DATA								D IN.	FC PSI	PS %	FS/FF RATIO	FS/FZ RATIO
							LEFT STIRRUPS		RIGHT STIRRUPS										
							M.SP.	AV/IN	BAR&SPAC	M.SP.	AV/IN	BAR&SPAC							
P 1	-3.168	-3.168	1.76	4 # 11	1.76	4 # 11	0.00	0.000	#5@ 0.00	23.48	0.067	#5@ 9.24	51.00			0.09	0.000	0.006	
.	-1293.636	-1744.550	13.09	9 # 11	1.76	4 # 11	24.00	0.072	#5@ 8.57	24.00	0.072	#5@ 8.57	51.00			0.72	0.592	0.881	
C 1	-1355.768	-2110.940	16.32	11 # 11	1.76	4 # 11	23.64	0.076	#5@ 8.18	11.82	0.270D#5@ 4.60	51.00				0.90	0.778	0.967	
P 3	-1034.352	-1642.258	12.24	8 # 11	1.76	4 # 11	12.00	0.263D#5@ 4.71	12.00	0.263D#5@ 4.71	51.00					0.67	0.843	0.966	
P 4	-966.248	-1542.850	11.45	8 # 11	1.76	4 # 11	12.00	0.263D#5@ 4.71	24.00	0.105	#5@ 5.89	51.00				0.63	0.775	0.908	
P 5	19.735	-334.897	3.90	4 # 11	1.76	4 # 11	23.48	0.104	#5@ 5.96	23.48	0.104	#5@ 5.96	51.00			0.35	0.633	0.000	
P 6	1294.988	612.376	1.76	4 # 11	10.38	7 # 11	24.00	0.095	#5@ 6.56	0.00	0.000	#5@ 0.00	51.00			0.57	0.931	0.905	
P 7	1266.944	598.732	1.76	4 # 11	10.14	7 # 11	0.00	0.000	#5@ 0.00	0.00	0.000	#5@ 0.00	51.00			0.56	0.905	0.886	
P 8	1247.514	516.356	1.76	4 # 11	10.10	7 # 11	0.00	0.000	#5@ 0.00	24.00	0.106	#5@ 5.83	51.00			0.55	0.955	0.872	
P 9	-1178.446	-1767.411	13.30	9 # 11	1.76	4 # 11	24.00	0.117	#5@ 5.29	12.00	0.293D#5@ 4.23	51.00				0.73	0.736	0.893	
P10	-1257.984	-1879.005	14.20	10 # 11	1.76	4 # 11	12.00	0.293D#5@ 4.23	12.00	0.293D#5@ 4.23	51.00					0.78	0.690	0.829	
C 2	-1633.193	-2405.011	18.96	13 # 11	1.76	4 # 11	11.79	0.301D#5@ 4.12	23.58	0.102	#5@ 6.09	51.00				1.05	0.689	0.907	
P11	-1583.393	-2065.569	15.71	11 # 11	1.76	4 # 11	23.64	0.100	#5@ 6.18	23.64	0.100	#5@ 6.18	51.00			0.87	0.539	0.946	
P12	-3.168	-3.168	1.76	4 # 11	1.76	4 # 11	23.48	0.093	#5@ 6.67	0.00	0.000	#5@ 0.00	51.00			0.09	0.000	0.006	

COLUMN ANALYSIS AND DESIGN OUTPUT
CRITICAL COLUMN LOADS

CN	T B	GR	LLC	WC	R	E S	C F	S F	PF	MTF	MLF	PM	MTM	MLM	PU	MTU	MLU	PU/PM	B	D
1	T	1	LL10	0.0			C	S	997.1	871.0	63.2	997.1	871.0	408.1	2064.4	1803.4	845.1	2.071	42.00	42.00
1	B	3	LL 6	3.2			C	S	1076.4	283.2	746.5	1076.4	376.8	878.1	2211.2	774.1	1804.1	2.054	42.00	42.00
2	T	1	LL 3	0.0			C	S	1337.8	-188.2	80.4	1337.8	468.2	580.5	2872.4	1007.9	1249.6	2.148	42.00	42.00
	B	3	LL 3	4.2			C	S	1186.1	22.9	746.6	1186.1	415.1	894.6	2309.0	808.3	1741.9	1.947	42.00	42.00

COLUMN DESIGN DATA

CN	T B	B NO.SIZE	FACE 1 NO.SIZE	B NO.SIZE	FACE 2 NO.SIZE	D NO.SIZE	FACE 3 NO.SIZE	D NO.SIZE	FACE 4 NO.SIZE	AS	PS	BD12	BD	SUMPU	SUMPC	DEL.T	DEL.L	CM	R	PHIC
1	T	4	# 11	4	# 11	2	# 11	2	# 11	18.72	1.061	1.00	0.016	2121.	56995.	1.000	1.169	0.400	2	0.70
1	B	4	# 11	4	# 11	2	# 11	2	# 11	18.72	1.061	1.00	0.044	1971.	50957.	1.000	1.176	0.400	2	0.70
2	T	4	# 11	4	# 11	2	# 11	2	# 11	18.72	1.061	1.00	0.111	2282.	55032.	1.000	1.240	0.400	2	0.70
2	B	4	# 11	4	# 11	2	# 11	2	# 11	18.72	1.061	1.00	0.000	2033.	57744.	1.000	1.198	0.926	2	0.70

FOOTING 1 DESIGN LOADS

P	G	LLID	WC	ES	C	S	P	MT	VT	ML	VL	P4	P3	P2	P1	MTF	VBF	VPF	LOAD
		. LL 9	0.0		C	S	771.058	216.788	25.673	222.809	8.529	104.709	76.636	127.743	155.816	37.398	-0.191	15.474	MAX.P1
1	1	LL 9	0.0		C	S	1134.532	386.177	47.180	289.652	11.088	142.279	105.783	197.668	234.164	57.396	-0.249	22.798	MAX.MT
1	1	LL 9	0.0		C	S	1134.532	386.177	47.180	289.652	11.088	142.279	105.783	197.668	234.164	57.396	-0.249	22.798	MAX.VT
1	1	LL 6	0.0		C	S	1164.853	246.863	25.907	289.652	11.088	164.425	127.929	184.185	220.681	53.651	-0.249	23.413	MAX.VP
1	3	LL 6	3.2		C	S	1026.887	266.568	26.456	746.538	26.146	171.224	78.107	137.968	231.084	81.233	-0.249	20.614	MAX.ML
1	1	LL 9	0.0		C	S	1134.532	386.177	47.180	289.652	11.088	142.279	105.783	197.668	234.164	75.845	-0.249	22.798	MAX.VL
1	3	LL11	1.2		C	S	705.625	279.178	32.339	533.431	18.759	107.464	40.899	106.293	172.858	36.786	-0.191	14.147	MAX.P3

FOOTING 1 ANALYSIS/DESIGN RESULTS

FOOTING SIZE			* BAR REINFORCEMENT STEEL *						SECTION CAPACITIES			
B	D	T	PI/PA	AS	NO.SIZE	SPAC.	PLACEMENT	MT.	VB	VP	DS	FC
9.000	9.000	3.500	0.812	0.61	18 # 5 @	6.000	TOP TRAN	76.841	33.868	67.736	28.062	0.000
				0.64	19 # 5 @	5.625	BOT.LONG	82.865	34.622	69.245	28.688	0.000

NUMBER OF PILES = 7 BP = 3.000 DP = 3.000

FOOTING 2 DESIGN LOADS

F	G	LLID	WC	ES	C	S	P	MT	VT	ML	VL	P4	P3	P2	P1	MTF	VBF	VPF	LOAD
2	4	LL13	0.0	S	C	S	819.955	521.628	44.796	222.809	8.529	80.714	52.640	165.709	193.783	47.944	-0.191	16.466	MAX.P1
2	4	LL13	0.0	S	C	S	1065.942	678.117	58.235	289.652	11.088	104.928	68.432	215.422	251.918	62.328	-0.249	21.406	MAX.MT
2	1	LL 3	0.0		C	S	1292.745	-67.253	-9.327	289.652	11.088	202.498	166.003	182.652	219.148	53.225	-0.249	26.008	MAX.VT
2	1	LL 3	0.0		C	S	1292.745	-67.253	-9.327	289.652	11.088	202.498	166.003	182.652	219.148	53.225	-0.249	26.008	MAX.VP
		LL 3	4.2		C	S	1132.094	48.700	2.681	746.619	26.149	211.348	118.222	127.902	221.029	87.498	-0.249	22.749	MAX.ML
2	1	LL 3	0.0		C	S	1292.745	-67.253	-9.327	289.652	11.088	202.498	166.003	182.652	219.148	85.262	-0.249	26.008	MAX.VL
2	4	LL13	0.0	S	C	S	819.955	521.628	44.796	222.809	8.529	80.714	52.640	165.709	193.783	47.944	-0.191	16.466	MAX.P3

FOOTING 2 ANALYSIS/DESIGN RESULTS

FOOTING SIZE			* BAR REINFORCEMENT STEEL *						SECTION CAPACITIES			
B	D	T	PL/PA	AS	NO.SIZE	SPAC.	PLACEMENT	MT.	VB	VP	DS	FC
9.000	9.000	3.500	0.807	0.64	19 # 5 @	5.625	TOP TRAN	81.024	33.868	67.736	28.062	0.000
				0.69	21 # 5 @	5.125	BOT.LONG	91.399	34.622	69.245	28.688	0.000

NUMBER OF PILES = 7 BP = 3.000 DP = 3.000

CALCULATION COVER SHEET

PROJECT	JOB NO.	CALC NO.	SHEET
I-75 / I-575 NORTHWEST CORRIDOR	NH000-0073-03(242)	BR#31	1
SUBJECT	DISCIPLINE		
References for Design	STRUCTURAL		

CALCULATION STATUS DESIGNATION	PRELIMINARY	CONFIRMED	SUPSEDED	VOIDED	INCOMPLETE
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

COMPUTER PROGRAM/TYPE	SCP	MAINFRAME	PC	PROGRAM	VERSION/RELEASE NO.
	<input type="radio"/> YES <input type="radio"/> NO	<input type="radio"/>	<input type="radio"/>	NONE	

Note 1: Georgia Department of Transportation (GDOT) terminated Contract Number TOURDPPI60072 for its convenience the completion of all work under that contract and directed that the work with respect to these calculations be discontinued

- (a) These calculations were not completed at the time of GDOT's direction and the information contained herein is not and/or has not been fully verified or checked. These calculations are a work-in-progress and are presented only as such.
- (b) Any user is cautioned that the use of these calculations and any related information or calculations, without access to factors and without proper regard for their purpose, could lead to erroneous conclusions.
- (c) If any such calculations or any information contained herein is used in future work efforts or any follow on design work a complete confirmation of the information contained herein should be performed prior to any such use.
- (d) GTP has no responsibility for the use of this information not under its direct control.

Included Reference Information:

- Roadway information
- Creek Survey Shots
- Bridge Survey Shots
- Existing Bridge Plans
- Existing Bridge Maintenance Reports
- Hydraulic Information

A	As per GDOT's termination for convenience direction	53	53	JCR			11/30/09
NO.	REASON FOR REVISION	TOTAL NO. OF SHEETS	LAST SHEET NO.	BY	CHECKED	APPROVED/ ACCEPTED	DATE

RECORD OF REVISIONS

CALCULATION SHEET

PROJECT: I-75 / I-575 NORTHWEST CORRIDOR

JOB NUMBER NH000-0073-03(242)

CALC NO. BR#31

SUBJECT: Roadway Information

BY: JCR

DATE: 11/30/2009

SHEET NO.

SHEET REV.

Horizontal Alignment Review Report

Report Created: 9/18/2009
Time: 5:40pm

Project: I-75/I-575
Description: I-75/I-575 PPI
File Name: N:\TRA\255717\Drawings\Civil\Rdy\InRoads\I-75 I-575.alg
Last Revised: san49773 9/18/2009 5:39:37 PM
Input Grid Factor: 1.00000000 **Note:** All units in this report are in feet unless specified otherwise.

Alignment Name: I-75 NB CL
Alignment Description: I-75 NB CL corrected for topo
Alignment Style: MAIN_P_CONSTCL

		Station	Northing	Easting
Element: Linear				
POB	()	800+00.0591	1459076.3730	2175089.1100
PI	()	807+46.4608	1459808.7490	2174945.0930
Tangential Direction:		N 11°07'29.6349" W		
Tangential Length:		746.4017		
Element: Linear				
PI	()	807+46.4608	1459808.7490	2174945.0930
PI	()	833+19.8800	1462334.3070	2174451.0860
Tangential Direction:		N 11°04'02.9823" W		
Tangential Length:		2573.4192		
Element: Linear				
PI	()	833+19.8800	1462334.3070	2174451.0860
PI	()	837+55.3219	1462761.1592	2174365.0229
Tangential Direction:		N 11°23'57.4843" W		
Tangential Length:		435.4419		
Element: Linear				
PI	()	837+55.3219	1462761.1592	2174365.0229
PC	()	837+82.0505	1462787.3799	2174359.8368
Tangential Direction:		N 11°11'16.8430" W		
Tangential Length:		26.7286		
Element: Circular				
PC	()	✓ 837+82.0505	✓ 1462787.3799	✓ 2174359.8368
PI	()	844+76.9091	✓ 1463469.0332	✓ 2174225.0140
CC	()		1462034.5470	2170553.5732
PT	()	✓ 851+57.1900	✓ 1464061.5315	✓ 2173862.0069
Radius:		✓ 3880.0000		
Delta:		20°18'23.8359" Left		
Degree of Curvature (Arc):		1°28'36.1033"		
Length:		1375.1395		
Tangent:		694.8586		

BR#31

PROJECT:	NW Corridor
COUNTY:	COBB
BRIDGE:	31
DESCRIPTION:	I-75 over Noonday Creek NB

VERTICAL GRADE DATA FOR NEW ALIGNMENT, ADJUSTED FOR SURVEY DIFF.:

PVC =	832+93.13
PVI EL. =	970.6328

PVI =	841+93.13
PVI EL. =	946.07
VC Length (ft) =	1800

PVT =	850+93.13
PVI EL. =	965.9690

ELEVATION COMPARISON, ADJUSTED FOR SURVEY DIFF.

BENT 1R LEFT SIDE

Geomath Rdy EL. =	958.835
Survey EL. =	958.871
DIFFERENCE =	-0.036

BENT 1R RIGHT SIDE

Geomath Rdy EL. =	961.209
Survey EL. =	961.269
DIFFERENCE =	-0.060

BENT 2R LEFT SIDE

Geomath Rdy EL. =	958.138
Survey EL. =	958.064
DIFFERENCE =	0.074

BENT 2R RIGHT SIDE

Geomath Rdy EL. =	960.562
Survey EL. =	956.363
DIFFERENCE =	4.199

BENT 3R LEFT SIDE

Geomath Rdy EL. =	957.622
Survey EL. =	957.563
DIFFERENCE =	0.059

BENT 3R RIGHT SIDE

Geomath Rdy EL. =	960.057
Survey EL. =	955.836
DIFFERENCE =	4.221

BENT 4R LEFT SIDE

Geomath Rdy EL. =	957.291
Survey EL. =	957.290
DIFFERENCE =	0.001

BENT 4R RIGHT SIDE

Geomath Rdy EL. =	959.680
Survey EL. =	959.705
DIFFERENCE =	-0.025

Mean EL. Difference =	0.002
-----------------------	-------

Horizontal Alignment Review Report

Report Created: 9/18/2009

Time: 5:37pm

Project: I-75/I-575

Description: I-75/I-575 PPI

File Name: N:\TRA\255717\Drawings\Civil\Rdy\InRoads\I-75 I-575.alg

Last Revised: san49773 9/18/2009 5:36:07 PM

Input Grid Factor: 1.00000000

Note: All units in this report are in feet unless specified otherwise.

Alignment Name: I-75 Ramp A

Alignment Description: Big Shanty Road

Alignment Style: MAIN_P_SIDECL

		Station	Northing	Easting
Element: Linear				
POB	()	29+01.8158	1461922.1084	2174505.2206
PC	()	37+78.2808	1462778.7364	2174319.8036
Tangential Direction:		N 12°12'47.7283" W		
Tangential Length:		876.4651		
Element: Circular				
PC	()	✓ 37+78.2808	✓ 1462778.7364	✓ 2174319.8036
PI	()	42+12.1146	✓ 1463202.3255	✓ 2174226.0804
CC	()		1461951.6368	2170581.6659
PCC	()	✓ 46+42.2631	✓ 1463594.2030	✓ 2174039.9521
Radius:		✓ 3828.5463		
Delta:		12°55'47.4647" Left		
Degree of Curvature (Arc):		1°29'47.5489"		
Length:		863.9822		
Tangent:		433.8338		
Chord:		862.1501		
Middle Ordinate:		24.3458		
External:		24.5017		
Tangent Direction:		N 12°28'34.4937" W		
Radial Direction:		N 77°31'25.5062" E		
Chord Direction:		N 18°56'28.2261" W		
Radial Direction:		N 64°35'38.0417" E		
Tangent Direction:		N 25°24'21.9584" W		
Element: Circular				
PCC	()	46+42.2631	1463574.1814	2174049.3908
PI	()	49+00.4856	1463810.3802	2173945.0405
CC	()		1462030.6828	2170555.6547
PT	()	51+57.9235	1464030.3844	2173809.8479
Radius:		3819.5000		
Delta:		7°44'07.2566" Left		
Degree of Curvature (Arc):		1°30'00.3090"		
Length:		515.6604		

BR#31


CALCULATION SHEET

PROJECT: I-75 / I-575 NORTHWEST CORRIDOR
JOB NUMBER NH000-0073-03(242)
CALC NO. BR#31

SUBJECT: Creek Survey Shots
BY: JCR DATE: 11/30/2009

SHEET NO.
SHEET REV.

Creek ~~Bank~~ Bank
Survey
from McWhorter



channel points all.tpr

```

15 - >>>> Describe Points <<<< [Mon Aug 31 15:03:55 2009]
SVXA32748 N 1463053.559400 E 2174369.033400 Z 933.618 DSB
      "TCB320"
12 - SVXA32735 N 1463026.704900 E 2174218.219200 Z 932.117 DSB
      "TCB320"
6 - SVXA32679 N 1463214.980000 E 2174099.136300 Z 939.168 DSB
      "TCB324"
SVXA32960 N 1462787.434200 E 2174592.019000 Z 933.513 DSB
      "TCB324"
SVXA32963 N 1462746.945300 E 2174641.740800 Z 932.183 DSB
      "TCB324"
SVXA32964 N 1462734.587400 E 2174675.934600 Z 932.682 DSB
      "TCB324"
SVXA32967 N 1462725.322200 E 2174708.488800 Z 931.410 DSB
      "TCB324"
SVXA32761 N 1463127.840800 E 2174497.627100 Z 932.431 DSB
      "TCB325"
SVXA32765 N 1463119.735100 E 2174512.712200 Z 932.590 DSB
      "TCB327"
SVXA32673 N 1463358.422700 E 2173844.861000 Z 935.312 DSB
      "TCB324"
SVXA32592 N 1463329.158300 E 2173759.027900 Z 936.600 DSB
      "TCB313"
21 - SVXA32787 N 1462933.780600 E 2174445.504400 Z 934.166 DSB
      "TCB320"
7 - SVXA32792 N 1462821.902300 E 2174460.882500 Z 935.245 DSB
      "TCB320"
SVXA32617 N 1463156.530200 E 2173550.457300 Z 935.842 DSB
      "TCB316"
SVXA32616 N 1463176.213100 E 2173594.620600 Z 935.827 DSB
      "TCB316"
SVXA32643 N 1463252.246500 E 2173362.067800 Z 936.563 DSB
      "TCB313"
SVXA32634 N 1463246.322900 E 2173414.006600 Z 936.911 DSB
      "TCB313"
SVXA32633 N 1463231.342400 E 2173462.331400 Z 937.280 DSB
      "TCB313"
SVXA32624 N 1463206.012800 E 2173510.861900 Z 936.010 DSB
      "TCB313"
SVXA32623 N 1463197.595300 E 2173547.754100 Z 936.423 DSB
      "TCB313"
SVXA32612 N 1463207.326500 E 2173576.651200 Z 934.236 DSB
      "TCB313"
SVXA32611 N 1463248.413000 E 2173620.218300 Z 936.245 DSB
      "TCB313"
SVXA32602 N 1463276.140800 E 2173662.699200 Z 934.772 DSB
      "TCB313"
SVXA32601 N 1463304.334700 E 2173708.638500 Z 935.228 DSB
      "TCB313"
SVXA32591 N 1463341.367600 E 2173811.217500 Z 934.769 DSB
      "TCB313"
/ SVXA32674 N 1463362.192000 E 2173908.516900 Z 939.789 DSB
      "TCB324"
18 - SVXA32675 N 1463356.243700 E 2173965.178200 Z 942.011 DSB
      "TCB324"
3 - SVXA32676 N 1463331.180800 E 2174022.625600 Z 941.961 DSB
      "TCB324"
4 - SVXA32677 N 1463297.367900 E 2174059.236100 Z 940.265 DSB
      "TCB324"
5 - SVXA32678 N 1463260.890100 E 2174087.328700 Z 939.718 DSB
      "TCB324"

```

					channel points all.tpr	
7	SVXA32721	N	1463195.766400	E	2174097.669600	Z 933.270 DSB
	"TCB324"					
8	SVXA32722	N	1463189.103000	E	2174094.562100	Z 932.515 DSB
	"TCB324"					
9	SVXA32723	N	1463161.096900	E	2174112.734600	Z 933.052 DSB
	"TCB324"					
10	SVXA32724	N	1463145.672100	E	2174144.925500	Z 935.320 DSB
	"TCB324"					
11	SVXA32725	N	1463129.614300	E	2174164.390100	Z 935.523 DSB
	"TCB324"					
12	SVXA32726	N	1463096.153400	E	2174202.012400	Z 934.564 DSB
	"TCB324"					
13	SVXA32729	N	1463064.563200	E	2174239.641100	Z 932.907 DSB
	"TCB324"					
14	SVXA32742	N	1463064.646000	E	2174272.286500	Z 933.991 DSB
	"TCB324"					
15	SVXA32743	N	1463082.944300	E	2174310.402900	Z 933.241 DSB
	"TCB324"					
16	SVXA32744	N	1463094.124600	E	2174357.508900	Z 932.970 DSB
	"TCB324"					
17	SVXA32750	N	1463101.453200	E	2174405.784900	Z 931.778 DSB
	"TCB324"					
18	SVXA32754	N	1463102.533000	E	2174448.948500	Z 932.747 DSB
	"TCB324"					
19	SVXA32762	N	1463090.541800	E	2174472.175200	Z 930.087 DSB
	"TCB325"					
20	SVXA32767	N	1463076.910700	E	2174504.752100	Z 934.114 DSB
	"TCB324"					
21	SVXA32768	N	1463054.985500	E	2174505.373600	Z 932.437 DSB
	"TCB324"					
22	SVXA32856	N	1463019.577400	E	2174518.578800	Z 932.978 DSB
	"TCB324"					
23	SVXA32770	N	1462973.022900	E	2174519.792400	Z 933.243 DSB
	"TCB324"					
24	SVXA32773	N	1462944.114300	E	2174495.861200	Z 931.506 DSB
	"TCB324"					
25	SVXA32774	N	1462909.274100	E	2174477.862700	Z 932.396 DSB
	"TCB324"					
26	SVXA32777	N	1462872.196700	E	2174486.248700	Z 933.097 DSB
	"TCB324"					
27	SVXA32778	N	1462829.537000	E	2174508.038100	Z 933.464 DSB
	"TCB324"					
28	SVXA32779	N	1462811.645700	E	2174520.850600	Z 931.665 DSB
	"TCB324"					
29	SVXA32783	N	1462791.145400	E	2174557.765200	Z 932.642 DSB
	"TCB324"					
30	SVXA32959	N	1462785.296500	E	2174588.767200	Z 931.256 DSB
	"TCB324"					
	SVXA32642	N	1463244.876300	E	2173360.999700	Z 929.534 DSB
	"BCB314"					
	SVXA32635	N	1463241.878300	E	2173415.247300	Z 929.624 DSB
	"BCB314"					
	SVXA32632	N	1463228.003000	E	2173459.909200	Z 930.239 DSB
	"BCB314"					
	SVXA32625	N	1463198.218600	E	2173506.664300	Z 929.840 DSB
	"BCB314"					
	SVXA32622	N	1463191.291600	E	2173550.415300	Z 930.312 DSB
	"BCB314"					
	SVXA32613	N	1463202.067500	E	2173581.747000	Z 929.956 DSB
	"BCB314"					
	SVXA32610	N	1463244.200400	E	2173626.634700	Z 929.900 DSB
	"BCB314"					
	SVXA32603	N	1463272.023900	E	2173665.434700	Z 930.164 DSB

channel points all.tpr

"BCB314"						
SVXA32600	N	1463298.596500	E	2173710.100200	Z	929.982 DSB
"BCB314"						
SVXA32593	N	1463320.971400	E	2173757.982700	Z	930.155 DSB
"BCB314"						
SVXA32590	N	1463334.819600	E	2173813.349400	Z	930.039 DSB
"BCB314"						
SVXA32672	N	1463350.617600	E	2173848.394400	Z	929.801 DSB
"BCB323"						
SVXA32684	N	1463341.173900	E	2173911.245700	Z	928.325 DSB
"BCB323"						
SVXA32685	N	1463332.702200	E	2173958.781600	Z	928.461 DSB
"BCB323"						
SVXA32690	N	1463302.025100	E	2174020.492900	Z	928.418 DSB
"BCB323"						
SVXA32691	N	1463264.963200	E	2174070.189700	Z	928.205 DSB
"BCB323"						
SVXA32696	N	1463210.184600	E	2174078.595100	Z	928.330 DSB
"BCB323"						
SVXA32703	N	1463174.967400	E	2174101.175300	Z	928.485 DSB
"BCB323"						
SVXA32708	N	1463154.593900	E	2174117.593600	Z	928.650 DSB
"BCB323"						
SVXA32714	N	1463112.034500	E	2174166.177400	Z	927.857 DSB
"BCB323"						
SVXA32718	N	1463088.884200	E	2174197.662900	Z	927.681 DSB
"BCB323"						
SVXA32730	N	1463058.526700	E	2174238.592600	Z	927.350 DSB
"BCB323"						
SVXA32737	N	1463056.370400	E	2174276.292600	Z	927.175 DSB
"BCB323"						
SVXA32738	N	1463075.538000	E	2174317.011700	Z	927.016 DSB
"BCB323"						
SVXA32745	N	1463088.079900	E	2174358.227400	Z	927.211 DSB
"BCB323"						
SVXA32749	N	1463098.169100	E	2174406.129200	Z	926.628 DSB
"BCB323"						
SVXA32755	N	1463096.479500	E	2174449.096400	Z	927.142 DSB
"BCB323"						
SVXA32760	N	1463072.444900	E	2174500.019800	Z	926.929 DSB
"BCB323"						
SVXA32769	N	1463054.020000	E	2174501.299800	Z	922.753 DSB
"BCB323"						
SVXA32858	N	1463019.322300	E	2174515.312800	Z	926.847 DSB
"BCB323"						
SVXA32771	N	1462975.487700	E	2174515.848000	Z	926.250 DSB
"BCB323"						
SVXA32772	N	1462946.637000	E	2174492.321500	Z	926.829 DSB
"BCB323"						
SVXA32775	N	1462910.760500	E	2174473.325700	Z	926.928 DSB
"BCB323"						
SVXA32776	N	1462886.869900	E	2174472.631400	Z	926.736 DSB
"BCB323"						
SVXA32780	N	1462827.452200	E	2174496.422100	Z	927.122 DSB
"BCB323"						
SVXA32781	N	1462803.047300	E	2174505.634300	Z	926.173 DSB
"BCB323"						
SVXA32782	N	1462782.099100	E	2174555.347000	Z	927.350 DSB
"BCB323"						
SVXA32961	N	1462778.285700	E	2174587.830000	Z	927.187 DSB
"BCB323"						
SVXA32962	N	1462744.351000	E	2174638.742600	Z	926.980 DSB
"BCB323"						

				channel	points	all.tpr	
SVXA32965	N	1462728.958300	E	2174674.667500	Z	928.401	DSB
"BCB323"							
SVXA32640	N	1463217.362200	E	2173356.542300	Z	930.455	DSB
"BCB315"							
SVXA32637	N	1463211.296400	E	2173405.111500	Z	930.374	DSB
"BCB315"							
SVXA32630	N	1463194.635700	E	2173446.803200	Z	930.770	DSB
"BCB315"							
SVXA32627	N	1463165.417500	E	2173490.558400	Z	930.002	DSB
"BCB315"							
SVXA32620	N	1463166.402800	E	2173550.077300	Z	930.255	DSB
"BCB315"							
SVXA32615	N	1463179.799000	E	2173593.384700	Z	929.993	DSB
"BCB315"							
SVXA32608	N	1463219.782200	E	2173646.110900	Z	930.212	DSB
"BCB315"							
SVXA32605	N	1463248.625800	E	2173683.374400	Z	930.174	DSB
"BCB315"							
SVXA32598	N	1463274.786400	E	2173724.308500	Z	930.137	DSB
"BCB315"							
SVXA32595	N	1463296.657100	E	2173768.063200	Z	930.200	DSB
"BCB315"							
SVXA32588	N	1463313.887000	E	2173821.571600	Z	934.516	DSB
"BCB315"							
SVXA32670	N	1463328.378600	E	2173856.156400	Z	929.989	DSB
"BCB321"							
SVXA32682	N	1463329.347700	E	2173910.075400	Z	928.369	DSB
"BCB321"							
SVXA32687	N	1463315.884500	E	2173959.074800	Z	928.152	DSB
"BCB321"							
SVXA32688	N	1463289.935000	E	2174012.149400	Z	928.207	DSB
"BCB321"							
SVXA32693	N	1463251.320800	E	2174050.499600	Z	928.425	DSB
"BCB321"							
SVXA32694	N	1463204.253000	E	2174061.675000	Z	928.274	DSB
"BCB321"							
SVXA32700	N	1463162.719200	E	2174083.992900	Z	928.670	DSB
"BCB321"							
SVXA32706	N	1463142.033700	E	2174099.736800	Z	928.559	DSB
"BCB321"							
SVXA32712	N	1463098.623500	E	2174157.627600	Z	928.335	DSB
"BCB321"							
SVXA32720	N	1463073.820000	E	2174185.482000	Z	927.824	DSB
"BCB321"							
SVXA32733	N	1463029.846700	E	2174220.107300	Z	927.574	DSB
"BCB321"							
SVXA32734	N	1463030.069800	E	2174275.504400	Z	926.695	DSB
"BCB321"							
SVXA32741	N	1463056.006300	E	2174316.035500	Z	927.378	DSB
"BCB321"							
SVXA32747	N	1463072.331000	E	2174363.145600	Z	927.135	DSB
"BCB321"							
SVXA32752	N	1463063.430700	E	2174407.423500	Z	928.801	DSB
"BCB321"							
SVXA32757	N	1463076.515200	E	2174443.737000	Z	926.988	DSB
"BCB321"							
SVXA32758	N	1463057.490300	E	2174482.790100	Z	927.434	DSB
"BCB321"							
SVXA32785	N	1462984.683300	E	2174471.553500	Z	928.468	DSB
"BCB321"							
SVXA32786	N	1462934.703300	E	2174455.075300	Z	926.615	DSB
"BCB321"							
SVXA32789	N	1462891.450500	E	2174443.729700	Z	927.778	DSB

channel points all.tpr

	"BCB321"					
	SVXA32790	N	1462869.789800	E	2174448.469800	Z 929.051 DSB
	"BCB321"					
	SVXA32793	N	1462822.307500	E	2174464.292900	Z 929.699 DSB
	"BCB321"					
	SVXA32902	N	1462786.237600	E	2174489.870700	Z 925.833 DSB
	"BCB321"					
	SVXA32903	N	1462745.356100	E	2174544.301500	Z 929.912 DSB
	"BCB321"					
	SVXA32906	N	1462724.892700	E	2174610.958400	Z 926.141 DSB
	"BCB321"					
	SVXA32908	N	1462700.823900	E	2174649.253100	Z 925.580 DSB
	"BCB321"					
	SVXA32912	N	1462681.834300	E	2174702.077700	Z 926.935 DSB
	"BCB321"					
	SVXA32639	N	1463209.416500	E	2173357.059100	Z 936.768 DSB
	"TCB316"					
	SVXA32638	N	1463208.419400	E	2173404.717100	Z 934.835 DSB
	"TCB316"					
	SVXA32629	N	1463188.308900	E	2173444.760100	Z 935.571 DSB
	"TCB316"					
	SVXA32628	N	1463160.738800	E	2173492.356900	Z 937.165 DSB
	"TCB316"					
	SVXA32607	N	1463216.739200	E	2173648.960300	Z 935.245 DSB
	"TCB316"					
	SVXA32606	N	1463246.301600	E	2173684.175700	Z 934.884 DSB
	"TCB316"					
	SVXA32597	N	1463271.880300	E	2173724.965600	Z 934.051 DSB
	"TCB316"					
	SVXA32596	N	1463294.066200	E	2173769.177500	Z 934.964 DSB
	"TCB316"					
X	SVXA32587	N	1463305.468700	E	2173823.837600	Z 936.845 DSB
	"TCB316"					
	SVXA32664	N	1463317.523100	E	2173859.440500	Z 935.127 DSB
	"TCB320"					
	SVXA32665	N	1463319.670500	E	2173909.713300	Z 936.031 DSB
	"TCB320"					
1	SVXA32666	N	1463304.364200	E	2173958.275200	Z 936.614 DSB
	"TCB320"					
2	SVXA32667	N	1463277.420700	E	2174003.265700	Z 936.327 DSB
	"TCB320"					
3	SVXA32668	N	1463245.569900	E	2174036.756600	Z 935.164 DSB
	"TCB320"					
4	SVXA32669	N	1463198.565000	E	2174051.310000	Z 935.629 DSB
	"TCB320"					
5	SVXA32699	N	1463155.169100	E	2174073.172200	Z 935.104 DSB
	"TCB320"					
6	SVXA32701	N	1463132.625500	E	2174092.312600	Z 935.297 DSB
	"TCB320"					
7	SVXA32704	N	1463132.924400	E	2174100.726400	Z 931.859 DSB
	"TCB320"					
8	SVXA32709	N	1463094.527600	E	2174155.431000	Z 930.851 DSB
	"TCB320"					
9	SVXA32715	N	1463069.675100	E	2174181.190900	Z 929.178 DSB
	"TCB320"					
10	SVXA32716	N	1463063.801900	E	2174181.296200	Z 929.366 DSB
	"TCB320"					
11	SVXA32717	N	1463060.580300	E	2174180.789600	Z 932.105 DSB
	"TCB320"					
12	SVXA32736	N	1463019.412000	E	2174275.254500	Z 932.960 DSB
	"TCB320"					
14	SVXA32740	N	1463033.949800	E	2174320.595300	Z 932.565 DSB
	"TCB320"					

channel points all.tpr

16 — SVXA32751 N 1463055.809900 E 2174409.352700 Z 933.521 DSB
 "TCB320"
 17 — SVXA32854 N 1463055.140300 E 2174428.639800 Z 933.374 DSB
 "TCB320"
 18 — SVXA32855 N 1463028.940900 E 2174456.518600 Z 934.076 DSB
 "TCB320"
 19 — SVXA32784 N 1462985.528300 E 2174465.382200 Z 934.268 DSB
 "TCB320"
 21 — SVXA32788 N 1462890.158600 E 2174440.550900 Z 936.283 DSB
 "TCB320"
 22 — SVXA32791 N 1462867.528600 E 2174445.779400 Z 936.837 DSB
 "TCB320"
 SVXA32901 N 1462782.264300 E 2174484.967800 Z 931.921 DSB
 "TCB320"
 SVXA32904 N 1462743.808700 E 2174542.149900 Z 933.120 DSB
 "TCB320"
 SVXA32905 N 1462716.297700 E 2174608.194500 Z 933.914 DSB
 "TCB320"
 SVXA32910 N 1462695.790600 E 2174648.638700 Z 933.577 DSB
 "TCB320"
 SVXA32911 N 1462678.483400 E 2174702.306700 Z 932.487 DSB
 "TCB320"
 SVXA32766 N 1463090.207700 E 2174485.536300 Z 932.026 DSB
 "TCB327"
 >>>> End of Describe Points <<<<

CALCULATION SHEET

PROJECT: I-75 / I-575 NORTHWEST CORRIDOR
JOB NUMBER NH000-0073-03(242)
CALC NO. BR#31

SUBJECT: Bridge Survey Shots
BY: JCR DATE: 11/30/2009

SHEET NO.
SHEET REV.

CALCULATION SHEET

PROJECT: I-75 / I-575 NORTHWEST CORRIDOR

JOB NUMBER NH000-0073-03(242)

CALC NO. BR#31

SUBJECT: Existing Bridge Plans


BY: JCR

DATE: 11/30/2009

SHEET NO.

SHEET REV.

22
11
11
8.5
11
17
22



FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
4	GA.	5-75-3 (60) 246	75	11	76

Contract 5

SBL BRIDGE CONSISTS OF

3 - COMPOSITE ROLLED BEAM SIMPLE SPANS	SPECIAL DESIGN
1 - CONCRETE ABUTMENT	SPECIAL DESIGN
1 - STEEL H PILE END BENT	SPECIAL DESIGN
2 - CONCRETE INTERMEDIATE BENTS	SPECIAL DESIGN
ALUMINUM HANDRAILING	GA. STD. NO. 3626(8-29-74)
BAR BENDING DETAILS	GA. STD. NO. 3901
TYPICAL FILL DETAIL AT END OF BRIDGE	GA. STD. NO. 9037(9-1-70)
END POST AND END POST GUARDRAIL ATTACHMENT DETAIL	GA. STD. NO. 9053

DRAINAGE DATA

DRAINAGE AREA = 10.6 SQ. MI.
Q₅₀ = 2300 CFS
AREA OF OPENINGS UNDER HIGH WATER = 975 SQ. FT.

GENERAL NOTES

SPECIFICATIONS - GEORGIA STANDARD DATED 1972.

END BENT EXCAVATION - EXCAVATION FOR END BENT NO. 1 LT. SHALL BE PAID FOR AS CU YD OR EXCAV. STREAM CROSS.

CHAMFER - ALL EXPOSED EDGES SHALL BE CHAMFERED 3/4 INCH UNLESS OTHERWISE NOTED.

PROTECTIVE SURFACE TREATMENT - PER SECTION 500.13C WILL BE REQUIRED AT THIS SITE.

REINFORCEMENT - ALL REINFORCEMENT SHALL BE PLACED AND TIED IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS. WELDING OF REINFORCEMENT WILL NOT BE PERMITTED, EXCEPT AS SHOWN ON THE PLANS.

DRIVING DATA PILES - ONE REQUIRED AT EACH OF BENT 4 LT. AND BENT 1 RT.

PLAN DRIVING OBJECTIVE - SEE SUBSTRUCTURE DETAILS.

UTILITIES

NONE

SUMMARY OF QUANTITIES	
47.510	CU YD BR EXCAV. STREAM CROSS
77	CU YD BR EXCAV.
LUMP	SUPERSTR CONC (CL 44) - BR NO 1 LT
271	CU YD CL A CONC
LUMP	STR STEEL - BR NO 1 LT
51,141	STR STEEL - BR NO 1 RT
LUMP	LB BAR REINF STEEL
41,152	SUPERSTR REINF STEEL - BR NO 1 LT
LUMP	SUPERSTR REINF STEEL - BR NO 1 RT
467	LIN FT ALUM HANDRAIL, STD 3626
245	LIN FT PILING IN PLACE, STEEL H, 12 BP 53
1	EACH LOAD TEST, STEEL H, 12 BP 53 (IF REQD)
359	SQ YD STN PLAIN R10 RAP

DESIGN DATA

SPECIFICATIONS - A.A.S.H.O., 1969, INT. 1970, 1971

TYPICAL HS20-44 AN./OR MILITARY LOADING - IMPACT ALLOWED

FUTURE PAVING ALLOWANCE = 15 LBS. PER SQ. FT.

BRIDGE NO. 1-LT

GEORGIA

DEPARTMENT OF TRANSPORTATION

HIGHWAY DIVISION-BRIDGE DESIGN

PLAN AND ELEVATION

SBL I-75 OVER NOONDAY CREEK

COBB CO.


SCALE: 1"=10'-0"

MAR. 1973

DESIGNED: HJL	TRACED: HJL	REVIEWED: CAP
DRAWN: HJL	CHECKED: CDE	APPROVED:

BRIDGE SHEET
1 OF 24

22
11
11
58
8.5
11
17
12



FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
4	GA.	275-3 (40128)	'75	12	76

Contract 5


BRIDGE NO. 1 LT.

GEORGIA
DEPARTMENT OF TRANSPORTATION
HIGHWAY DIVISION-BRIDGE DESIGN

PLAN AND ELEVATION
NBL I-75 OVER NOONDAY CREEK
COBB CO. I-1-314) 654 CT
SCALE: 1" = 10'-0" MAR. 1973

DESIGNED: HGL	TRACED: _____	REVIEWED: LRP
DRAWN: RHM	CHECKED: CDE	APPROVED: _____

BRIDGE SHEET 2 OF 24



PROFILE GRADE LINE

B.F.R.R. AT 4

END BRIDGE B.F.R.R. STA. 80490.0 SBL
END BRIDGE B.F.R.R. STA. 80495.0 NBL

NOTE: SBL SURVEY & AND NBL SURVEY &
ARE NOT THE SAME LINE AS SPAN.

B.F.R.R. AT 4

PROFILE GRADE LINE

NOTE: $\odot = 89^{\circ}24'00''$ MEASURED BETWEEN
± BEAM AND B.F.R.R. OR ± BENT,
AT ALL BEAMS, LT. AND RIGHT BRIDGE.

BRIDGE NO. 1 LT & RT.

GEORGIA
DEPARTMENT OF TRANSPORTATION
HIGHWAY DIVISION - BRIDGE DESIGN

BEAM CHORD LAYOUT
I-75 OVER NOONDAY CREEK


COBB CO. I-75-3(74)289 CT. 5
SCALE: 1"=10'-0" AUG. 1974

BRIDGE SHEET
3 OF 24

DESIGNED: JLL	TRACED: JPT	REVIEWED: LBP
DRAWN: JLL	CHECKED: JPT	APPROVED:



FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
4	GA.	5-75-3 44-284	'75	14	76

Contract 5



* * RADIAL DIMENSIONS TRUE ONLY AT B.F.P. OR
E BENT, VARY ELSEWHERE.


NOTE: ESTIMATE: JENSEN'S DEFLECT - 4, 1 - 10 SPANS, DUE TO WEIGHT OF SHIP - 114", PARAPET AND HANDRAIL = 2 1/2"




DATE		<u>BRIDGE NO. 1 LT</u> GEORGIA DEPARTMENT OF TRANSPORTATION HIGHWAY DIVISION - BRIDGE DESIGN	
REV. NO.		SUPERSTRUCTURE DETAILS SH. NO. 1 SBL I-75 OVER NOONDAY CREEK COBB CO I-75 - 3 (A01284) CT 5 SCALE: $\frac{1}{2}'' = 1'-0''$ (UNLESS NOTED) JULY 1973	
BY	DESIGNED: <u>HUL</u>	TRACED:	REVISED: <u>LAP</u>
	DRAWN: <u>MM</u>	CHECKED: <u>SGE</u>	APPROVED:

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
4	GA.	775-3	1975	15	76


Contract 5



SECTION AT ABUTMENT 1 LT. BRIDGE
LOOKING BACK




SECTION AT MIDSPAN LT. BRIDGE
LOOKING AHEAD



SECTION AT BENT 4 LT. BRIDGE
LOOKING AHEAD

"D" = 8 1/4" AND IS TRUE AT E BEARINGS ONLY. VARY COPING BETWEEN E BEARINGS TO COMPENSATE FOR DEAD LOAD DEFLECTION AND VERTICAL CURVE. MAINTAIN CONSTANT 7 1/8" SLAB BETWEEN COPINGS.



DETAIL AT PARAPET
SCALE 1" = 1'-0"


BRIDGE No. 1 LT.

GEORGIA
DEPARTMENT OF TRANSPORTATION
HIGHWAY DIVISION - BRIDGE DESIGN

SUPERSTRUCTURE DETAILS SHEET 2
SBL I-75 OVER NOONGY CREEK
COBB COUNTY I-75-3 (NO) 289 LT.5
SCALE: 3/8" = 1'-0" UN. SEPTEMBER 1974

DESIGNED: H.J.L. TRACED: C.D.E. REVIEWED: S.R.P.
DRAWN: C.D.E. CHECKED: J.P.T. APPROVED:

BRIDGE SHEET
5 OF 24



FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
4	GA.	I-75/3	1975	18	76





TABLE OF LETTERED DIM.

SPAN	DIM.	BEAM	A	B	C	D	E	F	G	H	I	J	K	L	M	N	P	Q	R	S
1	A		78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"
2	A		78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"
3	A		78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"	78'-5 1/2"





TABLE OF "C"

L.T. BR.	INT.	EXT.
1 1/2"	1 1/2"	1 1/2"
2 1/2"	2 1/2"	2 1/2"
1 1/2"	1 1/2"	1 1/2"



NOTE: CAMBER INCLUDES WEIGHT OF BEAM, SLAB, CURBING, PARAPET & HANDRAIL.

NOTE: FOR FURTHER DETAILS OF COVER PLATES AND SHEAR CONNECTORS SEE MISC. DETAILS.

COVER R. YIELD = $\frac{1}{8}$; TERNAL WELD = $\frac{1}{8}$; N = 3

STEEL NOTE

ALL ROLLED BEAMS AND COVER PLATES ARE MANY LOAD CARRYING MEMBER COMPONENTS SUBJECT TO TENSILE STRESS AND SHALL MEET THE CHARTER V-NOTCH TEST REQUIREMENTS AS SPECIFIED BY SPECIAL PROVISIONS MODIFYING SECTION 864 OF THE STANDARD SPECIFICATIONS. ALL ROLLED BEAMS AND COVER PLATES SHALL BE ASTM DESIGNATION A-572, GRADE 50.

ALL DIAPHRAGMS AND DIAPHRAGM CONNECTORS SHALL BE ASTM DESIGNATION A-36.

BRIDGE NO. 1LT. & RT.

GEORGIA

DEPARTMENT OF TRANSPORTATION

HIGHWAY DIVISION - BRIDGE DESIGN

STRUCTURAL STEEL DETAILS



I-75 OVER NOONDAY CREEK

COBB CO. I-75 - 1121 ST. S

NO SCALE JULY 1974

BRIDGE SHEET	8 OF 24	DESIGNED	MIL	TRACED		REVIEWED	LAP
		DRAWN	ARM	CHECKED	JPT	APPROVED	

22
11
11
58
8.5
11
11
22



NOTE: FOR FURTHER DETAILS OF PINTLES, SEE
MISC. DETAILS.

TABLE OF "T" DIMENSIONS

BENT	BEAM	A	B	C	D	E	F	G	H	I	J	K	L	M	N	P	Q	R
1		1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"
2 BH		2 1/2"	2 1/2"	2 1/2"	2 1/2"	2 1/2"	2 1/2"	2 1/2"	2 1/2"	2 1/2"	2 1/2"	2 1/2"	2 1/2"	2 1/2"	2 1/2"	2 1/2"	2 1/2"	2 1/2"
2 AH		1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"
3 BH		2 1/2"	2 1/2"	2 1/2"	2 1/2"	2 1/2"	2 1/2"	2 1/2"	2 1/2"	2 1/2"	2 1/2"	2 1/2"	2 1/2"	2 1/2"	2 1/2"	2 1/2"	2 1/2"	2 1/2"
3 AH		1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"
4		1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"

ANCHOR BOLT NOTE
ALL ANCHOR BOLTS SHALL BE 1" Ø S-WEDGED
WITH ASH HEX. NUT AND 4" X 3" PLATE WASHER.
STEEL NOTE
ALL STEEL COMPONENTS OF BEARING ASSEMBLIES
SHALL BE ASTM DESIGNATION A-36.
WELDING NOTE
* ALL WELDS, SOLE PLATE TO FLANGE, SHALL BE
A.R.S.D. MIN. FILLET WELDS.

BRIDGE NO. 1LT. & RT.

DATE		DESIGNED: NDL		TRACED:		REVIEWED: LJP	
BY		DRAWN: JMM		CHECKED: CDE		APPROVED:	
GEORGIA DEPARTMENT OF TRANSPORTATION HIGHWAY DIVISION - BRIDGE DESIGN							
BEARING DETAILS							
NRL & SBL 2-75 OVER NOONDY CREEK							
COBB CO. 2-75-46, 2-75-47							
SCALE: 1/2"=1'-0" (UNLESS NOTED) JULY 1979							

BRIDGE SHEET
9 OF 24




TABLE OF STATIONS	
POINT	STN.
1L	804+02.84
2L	804+53.07
3L	804+53.01
4L	804+42.46
5L	805+30.0
6L	805+30.0
7L	805+30.0
8L	806+10.0
9L	806+10.0
10L	806+10.0
11L	806+26.93
12L	806+75.88
13L	806+86.97
14L	806+75.78

NOTE: STATIONS AT INTERMEDIATE BENTS ARE GIVEN AT E COLUMN AT 2 BENT. STATIONS AT ABUTMENT 1 ARE GIVEN AT INSIDE FACE OF WING AT P.P. CAP AND AT END OF WING. STATIONS AT BENT 4 ARE GIVEN AT INTERSECTION OF P.P. CAP AND INSIDE FACE OF WING AND AT E WING PILE.

BRIDGE NO. 111


GEORGIA
DEPARTMENT OF TRANSPORTATION
HIGHWAY DIVISION - BRIDGE DESIGN

SUBSTITUTION: LHY. T SHEET 1
SBL I-75 OVER NOONDAY CREEK
COBB CO. I-75-3(4)1264 C.R.S.
SCALE: 1"=20'-0" FEB. 1975

BRIDGE SHEET
10 OF 24


DESIGNED: M.H.L.
DRAWN: H.M.T.
TRACED: J.P.T.
REVIEWED: L.A.P.
APPROVED:

22
11
11
58
8.5
11
17
22




FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
4	GA.	3-75-3 (40284)	1975	21	76


Contract 5
Rev 6-10-75




DETAIL "A"
SCALE: 1/4" = 1'-0"



SECTION AT BEAM SEAT
SCALE: 1/4" = 1'-0"



SECTION - S
SCALE: 1/4" = 1'-0"



SPREAD FOOTING PROPORTIONED FOR AN ALLOWABLE SOIL BEARING CAPACITY OF 3 TONS PER SQ. FT.

TABLE OF QUANTITIES	
CU. YDS. CLASS "A" CONCRETE	104.80
LBS. 3/8" REINFORCEMENT STEEL	14739

KEY EXCAVATION SHALL BE DONE AS NEAR PLANS AS PRACTICAL. KEY SHALL BE POURED AGAINST UNDISTURBED SOIL AND WITHOUT FORMS.

EXCAVATION FOR SPREAD FOOTING SHALL BE DONE WITH CARE TO PREVENT UNDERCUTTING. FOOTING SHALL BE POURED AGAINST UNDISTURBED SOIL.

ELEVATION
SCALE: 1/4" = 1'-0"
LOOKING EAST

BRIDGE NO. 1 LT.

GEORGIA
DEPARTMENT OF TRANSPORTATION
HIGHWAY DIVISION - BRIDGE DESIGN

ABUTMENT 1 LT. DETAILS SH. NO. 1
SBL I-75 OVER NOKUNDAY CREEK
COBB CO. I-75-3(40)291 C.C.S.
SCALE: AS SHOWN AUG. 1974

BRIDGE SHEET 11 OF 24	DESIGNED: HVL DRAWN: RMM	TRACED: CHECKED: CPE	REVIEWED: LRP APPROVED:
--------------------------	-----------------------------	-------------------------	----------------------------

22"	17"	11"	8.5"	11"	8.5"	17"	22"
-----	-----	-----	------	-----	------	-----	-----

PLAN OF FOOTING REINFORCEMENT STEEL
BOTTOM MAT


PLAN OF FOOTING REINFORCEMENT STEEL
TOP MAT

ELEVATION OF FOOTING

REVIEWED	<i>LRP</i>
APPROVED	

22
11
11
58
8.5
11
17
22

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
4	GA	7-75-3 (40) 289	75	23	76
Contract 5					



ELEVATION
LOOKING BACK

N.F. = NEAR FACE
F.F. = FAR FACE

BRIDGE NO. 1 LT.


GEORGIA
DEPARTMENT OF TRANSPORTATION
HIGHWAY DIVISION - BRIDGE DESIGN

ABUTMENT 1 LT. DETAILS SH. NO. 3
SBL I-75 OVER NOONDAY CREEK
COB'S CO. I-75-3 (40) 289 a.s.
SCALE: 3/4" = 1'-0" AUG. 1974

BRIDGE SHEET 13 OF 24	DESIGNED: HJL DRAWN: BMM	TRACED: CHECKED: CDE	REVIEWED: LAP APPROVED:
--------------------------	-----------------------------	-------------------------	----------------------------

22
11
11
58
8.5
11
17
22

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
4	GA.	5-75-3 (401000)	1975	24	76
Contract 5					



N.F. = NEAR FACE
F.F. = FAR FACE

BRIDGE NO. 1 LT.

DATE		REVISIONS	
GEORGIA DEPARTMENT OF TRANSPORTATION HIGHWAY DIVISION - BRIDGE DESIGN			
ABUTMENT 1 LT. DETAILS SH. NO. 4			
SBL I-75 OVER NOONDY CREEK			
COBB CO. I-75-3 (401000) CLS			
SCALE: 1/4"=1'-0" AUG. 1974			
BRIDGE SHEET 14 OF 24		DESIGNED: <u>N.M.</u> DRAWN: <u>B.H.M.</u>	TRACED: <u>CDE</u> CHECKED: <u>CDE</u> APPROVED: <u>LAP</u>

22

11

11


58

8.5

11

17

22







REV.	NO.	DATE	BY	CHKD.	APP'D.
1	GA	2-75-3			
2	GA	6-10-75			

Contract 5
Rev 6-10-75

22
11
11
8.5
8.5
11
17
22

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
4	GA	5-75-3 (40)284	75	26	76

CONTRACT 3
REV. 6-10-75



BRIDGE NO. 1 LT.

GEORGIA
DEPARTMENT OF TRANSPORTATION
HIGHWAY DIVISION-BRIDGE DESIGN

ABUTMENT 1 LT. DETAILS SH. NO. 6
SBL I-75 OVER NOONDAY CREEK
COBAG CO. I-75-3(40)284 CT. 5
SCALE: AS SHOWN AUG. 1979


BRIDGE SHEET 16 OF 24	DESIGNED: HNL DRAWN: HNL	TRACED: CDE CHECKED: CDE	REVIEWED: LAP APPROVED:
--------------------------	-----------------------------	-----------------------------	----------------------------

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
4	GA	2-75-3 401244	75	27	76

Contract 3

POINT	STATION
1A	800+17.23
2A	800+27.99
3A	800+37.79
4A	800+47.77
5A	801+25.00
6A	801+25.00
7A	801+25.00
8A	802+05.00
9A	802+05.00
10A	802+05.00
11A	802+82.01
12A	802+70.74
13A	802+82.06
14A	802+78.63

NOTE: STATIONS FOR INTERMEDIATE BENTS ARE GIVEN AT THE INTERSECTION OF E COL AND E BENT. STATIONS AT END BENTS ARE AT FRONT FACE OF CAP @ INSIDE FACE OF WING AND AT E WING PILE.



BRIDGE NO. 1 AT

GEORGIA
DEPARTMENT OF TRANSPORTATION
HIGHWAY DIVISION - BRIDGE DESIGN

SUBSTRUCTURE LAYOUT SHEET 2
NBL I-75 OVER NOONDAY CREEK
COBA CO. I-75-3(40)284 CT. 5
SCALE: 1"=20'-0" FEB. 1975

BRIDGE SHEET
17 OF 24

DESIGNED: HJL
DRAWN: HAM
TRACED:
CHECKED: JPT
REVIEWED: LRP
APPROVED:


NOTE: 552 BAR TO HAVE 1" MINIMUM
AND 2" MAXIMUM C.L. TOP & BOTTOM

* RADIAL DIMENSIONS


FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
4	GA.	2-75-3	75	28	76
Contract 5					

TABLE OF QUANTITIES

ITEM	BENT	1 RT
CU YDS OF CLASS "A" CONCRETE		21.37
LBLS BAR REINFORCEMENT STEEL		2440




DETAIL A
SCALE: 1/4" = 1'-0"



SECTION AT BEAM SEAT
SCALE: 1/4" = 1'-0"

NOTE: ALL PILES SHALL BE 12 BP 53.


NOTE: WING PILES ARE NOT SHOWN.
BOTTOM OF WINGS ARE LEVEL.
- E BEAM AT E CAP




SECTION D-D
SCALE: 1/4" = 1'-0"




SECTION C-C
SCALE: 1/4" = 1'-0"



SECTION B-B
SCALE: 1/4" = 1'-0"



SECTION A-A
SCALE: 1/4" = 1'-0"



WINGWALL DETAIL
SCALE: 1/4" = 1'-0"

FOR THE DESIGN OF THE
P.C. SHALL BE PRACTICAL REPAIRABLE
7' MAX. MIN. TIP ELEVATION OF 140.0' MIN. ELEV.

HOUSE: NC 1RT



GEORGIA
DEPARTMENT OF TRANSPORTATION
HIGHWAY DIVISION-BRIDGE DESIGN

END BENT 1 RT.
N.B.L. I-75 OVER NOONDAY CREEK
COBB CO. I-75-3(40)284 CT.5
SCALE: 3/8" = 1'-0" (UNLESS NOTED) MAR. 1973

BRIDGE SHEET	DESIGNED	TRACED	REVIEWED
18 OF 24	WLL	CHD	LRP
	BRN	CHD	APPROVED

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOT. SHEETS
4	CA.	575-3 (44)204	'75	29	70

Contract 5









DATE	DEPARTMENT OF TRANSPORTATION HIGHWAY DIVISION-BRIDGE DESIGN		
REVISIONS	INTERMEDIATE BENT 2LT & 2RT I-75 OVER NOONDAY CREEK COBB COUNTY I-75-3 (40) 289 C.T. 5 SCALE AS SHOWN AUG, 1973		
87	DESIGNED <i>Hell</i> DRAWN <i>WJM</i>	TRACED CHECKED <i>CDE</i>	REVIEWED <i>L.R.R.</i> APPROVED

TABLE OF ELEVATIONS																
BEAM	ELEV.	A	B	C	D	E	F	G	H	I	J	K	L	M	N	P
3 RT	754.70	754.02	754.34	754.70	755.09	755.48	755.72	756.08	756.48	756.92	757.21	757.47	757.70	757.98	758.21	758.50
3 LT	754.34	754.68	755.02	755.36	755.70	756.04	756.38	756.72	757.06	757.40	757.74	758.08	758.42	758.76	759.10	759.44

TABLE OF QUANTITIES		
ITEM	BENT	3 LT.
CUL. YDS. CLASS 'A' CONCRETE	76.81	81.67
LBS. BAR REINFORCEMENT STEEL	18,535	21,387

NO. ROAD DIST.	STATE	FEED NO.	TOTAL FEET	SHEET NO.	TOTAL SHEETS
4	GA	275-3	175	30	76

Contract 5



NOTE: SPALLS FOOTINGS ARE PROPORTIONED FOR AN ALLOWABLE BEARING PRESSURE OF 5 TONS PER SQUARE FOOT.

BR. NO. 1 LT. & RT.


GEORGIA
DEPARTMENT OF TRANSPORTATION
HIGHWAY DIVISION - BRIDGE DESIGN

INTERMEDIATE BENT 3 LT & RT.
I-75 OVER NCNDAY CREEK

COB3 COUNTY I-75-3 (40) 284 OF 285
SCALE AS SHOWN AUG. 1973

BRIDGE SHEET 20 OF 24	DESIGNED BY J.P.T.	TRACED BY C.D.E.	REVIEWED BY L.R.P.
--------------------------	-----------------------	---------------------	-----------------------

TABLE OF QUANTITIES			
ITEM	BEAM	4 RT	4 LT
CU YDS OF CLASS "A" CONCRETE		21.93	21.35
LBS BAR REINFORCEMENT STEEL		2445	2442



LOCATION														LOCATION														
NO. OF LOC.	MARK	LENGTH	NO. BARS	Y	AG	B	C	D	E	F	H	J	K	NO. OF LOC.	MARK	LENGTH	NO. BARS	Y	AG	B	C	D	E	F	H	J	K	N
SPAN ONE LEFT														SPAN TWO RIGHT														
1	401A	VARY	318	1										801	22-0	6	1											
	403	3-10	126	31	4	0-0	1-1 1/2	1-1 1/2																				
	501	34-0	128	1		12-11 1/2	2-0							1001	34-0	4	3											
	502A	36-4	149	1										1002	36-4	2	1											
	502B	27-10	185	1										1003	36-4	4	1											
	504A	30-0	16	1										SPAN TWO LEFT														
	504B	35-0	16	1										401A	VARY	318	1											
	505	40-0	145	14		0-10	2-5 1/2	2-0	1-0	0-0				403	3-10	126	31											
	506	34-0	4	1		32-0 R 1/2	2-0							501	34-0	128	1											
	507	37-2	4	1										502A	36-4	149	1											
	508	3-0	8	1										502B	27-10	185	1											
SPAN TWO LEFT														SPAN TWO LEFT														
1	401A	VARY	318	1										504A	30-0	16	1											
	403	3-10	126	31										504B	35-0	16	1											
	501	34-0	128	1										505	40-0	145	14											
	502A	36-4	149	1										506	34-0	4	1											
	502B	27-10	185	1										507	37-2	4	1											
	504A	30-0	16	1										508	3-0	8	1											
	504B	35-0	16	1										SPAN THREE LEFT														
	505	40-0	145	14										401A	VARY	318	1											
	506	34-0	4	1										403	3-10	126	31											
	507	37-2	4	1										501	34-0	128	1											
	508	3-0	8	1										502A	36-4	149	1											
SPAN THREE LEFT														SPAN THREE LEFT														
1	401A	VARY	318	1										403	3-10	126	31											
	403	3-10	126	31										501	34-0	128	1											
	501	34-0	128	1										502A	36-4	149	1											
	502A	36-4	149	1										502B	27-10	185	1											
	502B	27-10	185	1										504A	30-0	16	1											
	504A	30-0	16	1										504B	35-0	16	1											
	504B	35-0	16	1										505	40-0	145	14											
	505	40-0	145	14										506	34-0	4	1											
	506	34-0	4	1										507	37-2	4	1											
	507	37-2	4	1										508	3-0	8	1											
	508	3-0	8	1										SPAN FOUR LEFT														
SPAN FOUR LEFT														SPAN FOUR LEFT														
1	401A	VARY	318	1										401A	VARY	318	1											
	403	3-10	126	31										403	3-10	126	31											
	501	34-0	128	1										501	34-0	128	1											
	502A	36-4	149	1										502A	36-4	149	1											
	502B	27-10	185	1										502B	27-10	185	1											
	504A	30-0	16	1										504A	30-0	16	1											
	504B	35-0	16	1										504B	35-0	16	1											
	505	40-0	145	14										505	40-0	145	14											
	506	34-0	4	1										506	34-0	4	1											
	507	37-2	4	1										507	37-2	4	1											
	508	3-0	8	1										508	3-0	8	1											
SPAN FIVE LEFT														SPAN FIVE LEFT														
1	401A	VARY	318	1										401A	VARY	318	1											
	403	3-10	126	31										403	3-10	126	31											
	501	34-0	128	1										501	34-0	128	1											
	502A	36-4	149	1										502A	36-4	149	1											
	502B	27-10	185	1										502B	27-10	185	1											
	504A	30-0	16	1										504A	30-0	16	1											
	504B	35-0	16	1										504B	35-0	16	1											
	505	40-0	145	14										505	40-0	145	14											
	506	34-0	4	1										506	34-0	4	1											
	507	37-2	4	1										507	37-2	4	1											
	508	3-0	8	1										508	3-0	8	1											
SPAN FIVE LEFT														SPAN FIVE LEFT														
1	401A	VARY	318	1										401A	VARY	318	1											
	403	3-10	126	31										403	3-10	126	31											
	501	34-0	128	1										501	34-0	128	1											
	502A	36-4	149	1										502A	36-4	149	1											
	502B	27-10	185	1										502B	27-10	185	1											
	504A	30-0	16	1										504A	30-0	16	1											
	504B	35-0	16	1										504B	35-0	16	1											
	505	40-0	145	14										505	40-0	145	14											
	506	34-0	4	1										506	34-0	4	1											
	507	37-2	4	1										507	37-2	4	1											
	508	3-0	8	1										508	3-0	8	1											
SPAN FIVE LEFT														SPAN FIVE LEFT														
1	401A	VARY	318	1										401A	VARY	318	1											
	403	3-10	126	31										403	3-10	126	31											
	501	34-0	128	1										501	34-0	128	1											
	502A	36-4	149	1										502A	36-4	149	1											
	502B	27-10	185	1										502B	27-10	185	1											
	504A	30-0	16	1										504A	30-0	16	1											
	504B	35-0	16	1										504B	35-0	16	1											
	505	40-0	145	14										505	40-0	145	14											
	506	34-0	4	1										506	34-0	4	1											
	507	37-2	4	1										507	37-2	4	1											
	508	3-0	8	1										508	3-0	8	1											
SPAN FIVE LEFT														SPAN FIVE LEFT														
1	401A	VARY	318	1										401A	VARY	318	1											
	403	3-10	126	31										403	3-10	126	31											
	501	34-0	128	1										501	34-0	128	1											
	502A	36-4	149	1										502A	36-4	149	1											
	502B	27-10	185	1										502B	27-10	185	1											
	504A	30-0	16	1										504A	30-0	16	1											

FILE NO.	STATE	FILE NO.	STATE NO.	FILE NO.	FILE NO.	FILE NO.	FILE NO.
4	GA	2-75-3	175	32	76		
Contract 5							

BRIDGE NO. 1 LT E RT.	
STATE HIGHWAY DEPARTMENT OF GEORGIA	
BRIDGE DIVISION	
BAR REINFORCEMENT STEEL SH. NO. 1	
I-75 OVER NOONDAY CREEK	
COBB COUNTY I-75-3(40)284 CT. 5	
NO SCALE SEPT, 1974	
DESIGNED	TRACED
DRAWN	CHECKED
REVIEWED	APPROVED

BRIDGE SHEET
22 OF 24

LOCATION															LOCATION														
ABUTMENT	NO. OF LOC.	MARK	LENGTH	NO. BARS	AG	B	C	D	E	F	H	J	K	N	ABUTMENT	NO. OF LOC.	MARK	LENGTH	NO. BARS	AG	B	C	D	E	F	H	J	K	N
			FT. IN.	REGD.	FT. IN.	FT. IN.	FT. IN.	FT. IN.	FT. IN.	FT. IN.	FT. IN.	FT. IN.	FT. IN.	FT. IN.				FT. IN.	REGD.	FT. IN.	FT. IN.	FT. IN.	FT. IN.	FT. IN.	FT. IN.	FT. IN.	FT. IN.	FT. IN.	
1	455	26-4	1	34	6	20-1	3-0	2-0	3-0						654	14-5	3	1											
	457	27-1	1	34	6	20-10	3-0	2-0	3-0						655	4-3	3	1											
	459	3-6	1	8		2-6	0-6	0-6	0-6					83	83														
	460	5-0	21	4		2-0	2-6	0-0	0-6					83	7														
	461	VARY	2	6		2-6	VARIES	0-0	0-6					83	7														
	462	7-6	3	6		2-0	5-0	0-0	0-6					83	7														
	463	5-0	36	6		2-0	2-6	0-0	0-6					83	7														
	464	5-9	1	6		2-6	2-6	0-0	0-6					83	7														
	465	6-6	3	6		2-0	4-0	0-0	0-6					83	7														
	466	6-9	14	1										83	7														
	467	4-0	1	8		3-0	0-6	0-6						83	83														
	468	4-4	2	34	6	21-6	2-0	20-0	2-0						755	7-0	7	9	2	6-3									
	469	4-10	1	34	6	21-0	2-0	20-0	2-0						756	7-4	6	9	2	6-7									
	470	4-10	24	4		9-10	1-0							45	757	7-7	1	9	2	6-10									
	5628	34-7	12	3		32-6 1/2	2-0								758	9-8	7	9	2	8-11									
	5608	35-1	12	3		33-0 1/2	2-0								759	10-0	7	9	2	8-3									
	561	6-10	104	1											760	12-0	3	1											
	562	5-2	24	1											761	4-9	3	1											
	563	5-8	30	2		2-8	1-6	1-6							762	11-16	20	1											
	564	9-8	34	25	4	2-8	1-8								763	4-9	17	1											
	5654	30-9	2	3		28-9	2-0								764	6-0	4	1											
	5658	31-3	4	3		29-3	2-0								765	VARY	3	1											
	566	VARY	20	3		VARIES	2-0								766	13-5	5	3		11-5	2-0								
	567	VARY	3	3		VARIES	2-0								851	VARY	12	1											
	568	VARY	24	1											852	8-4	11	5		6-6	1-10								
	569	10-8	2	3		8-8	2-0								853	5-1	12	5		3-3	1-10								
	570	34-7	2	48		0-0	1-9	28-9 1/2	0-0	0-0	2-0	2-0			956	9-0	21	1											
	571	5-2	24	1											957	11-6	6	1											
	572	8-0	3	34	6	4-0	0-0	2-0	2-0						1056	7-4	7	9	2	6-3									
	573	38-10	2	3		38-10	2-0								1057	7-11	2	9	2	6-10									
	574	41-6	3	3		39-6	2-0								1058	8-2	2	9	2	7-1									
	575	11-0	18	14		2-6	2-0	2-3	2-0	2-3					1059	9-1	1	9	2	8-0									
	576	9-7	8	48		3-3 1/2	2-3	0-0	2-0	2-0	0-0	0-0			1060	8-10	1	9	2	7-9									
	577	19-4	2	3		17-6	2-0								1061	9-4	2	9	2	8-3									
	578	38-4	6	3		38-4	2-0								1062	10-2	1	9	2	9-1									
	579	19-10	1	3		17-9 1/2	2-0								1063	11-1	2	9	2	10-0									
	580	VARY	22	1											1064	7-9	7	9	2	6-3									
	81	VARY	17	1											1065	11-1	1	9	2	10-0									
	582	4-6	8	1											1066	11-6	42	1											
	583	42-6	13	34	6	19-0	0-0	21-6	2-0						1067	12-0	6	1											
	584	41-4	13	34	6	18-0	2-0	10-6	2-0						456	10-5	72	25	4	4	2-5	2-5							
	585	37-4	13	34	6	25-7	0-0	2-3	2-0						553	VARY	14	25	4	4	VARIES	2-8							
	586	24-4	13	34	6	21-1	3-0	4-0	3-0						555	13-4	92	25	4	4	3-11	2-3							
	587	13-0	54	1											556	14-2	16	25	4	4	3-11	2-8							
	588	5-7	2	1											557	31-5	6	1											
	589	5-3	12	3		1-6	2-4								751	6-6	31	10	2	2	7-0								
	590	VARY	17	1											951	4-3	2	1											
	591	VARY	22	1											952	5-6	1	1											
	592	1-11	4	35	3	3-2	1-6 1/2	1-6 1/2							953	10-6	16	10	2	2	8-6								
	593	2-4	2	4		4-5 3/4	1-6	0-0	1-6						1052	11-2	8	10	2	2	4-0								
	594	5-7	1	50	4	3-0	1-4	2-4	0-5	0-4	0-9			45	45														
	595	5-11	4	25	4	2-9	3-6								11-1A	22-9	2	9	2	21-7									
	596	VARY	3	50	3	VARIES	1-6 1/2	1-6 1/2							11518	45-6	2	9	2	44-4									
	597	12-5	2	1											1152	10-8	4	9	2	17-5 1/2									
	598	5-7	64	21	2	1-1 3/8	2-0								1153	14-8	4	1											
	599	6-5	9	30	3	1-8	1-6 1/2	1-6 1/2						90	1154	11-6	4	1											
	602	9-0	14	1											1155	9-0	4	1											
	603	4-3	8	1											1156	22-0	2	1											
	604	4-3	8	1											1157	17-6	2	1											

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	STATE AID PROJ. NO.	FEDAL ROAD NO.	SHEET NO.	TOTAL SHEETS
4	GA	175-3	175-3	175	33	76

Contract 5

BRIDGE NO. 1 LT & RT.

STATE HIGHWAY DEPARTMENT OF GEORGIA
BRIDGE DIVISION

BAR REINFORCEMENT STEEL SH. NO. 2
I-75 OVER NOONDAY CREEK
COBB CO. I-75-3(4)269 CT. 5
NO SCALE SEPT. 1974

BRIDGE SHEET
23 OF 24

DESIGNED _____ TRACED _____ REVIEWED _____
DRAWN _____ CHECKED _____ APPROVED _____

22
11
11
58
8.5
11
17
22

LOCATION																	LOCATION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																								
NO. OF LOC.	MARK	LENGTH		NO. BARS	T	AG	B		C	D		E	F	H	J	K	N	Θ	NO. OF LOC.	MARK	LENGTH		NO. BARS	T	AG	B		C	D	E	F	H	J	K	N	Θ																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																					
		FT.	IN.				FT.	IN.		FT.	IN.										FT.	IN.				FT.	IN.										FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.

FILE NO.	STATE	FILE NO.	STATE	FILE NO.	STATE	FILE NO.	STATE
4	GA.	2753	GA.	75	34	76	

Contract 5

LOCATION		OF LOC	MARK	LENGTH		BARS	V	A G		B	
				FT	IN			REGG	E		
	1155			11-8	9	10	2	2		9-6	
	1151A			22-9	2	9					
	1151B			49-8	2	9					
	1161B			21-3	18	1					
	1162A			33-0	2	24					
	1162B			33-0	2	24					
	1165			7-8	48	9					
	1170			19-2	4	9					
	1171			16-5	4	9					
	1172			12-3	4	1					
	1173			9-6	4	1					
	1174			22-0	2	1					
	1175			20-0	2	1					
	1176			19-0	3	1					
	1177			12-6	2	1					
	1178			10-6	2	1					
	1179			19-3	4	1					
	1180			14-3	4	1					
	1181B			22-1	16	1					
	1182			19-9	48	1					
	1183B			22-11	16						
BENT & RIGHT		1									
	451			6-9	33	32					
	452			9-5	58	25					
	453			9-5	0	23					
	454			1-6	0	1					
	455			9-6	32	1					
	452			6-0	44	1					
	451			6-0	6	1					
	1051			36-0	6	3					

CALCULATION SHEET

PROJECT: I-75 / I-575 NORTHWEST CORRIDOR

JOB NUMBER NH000-0073-03(242)

CALC NO. BR#31

SUBJECT: Bridge Maintenance Reports

BY: JCR

DATE: 11/30/2009

SHEET NO.

SHEET REV.

BRIDGE INVENTORY DATA LISTING GEOGRAPHIC A DEPARTMENT OF TRANSPORTATION

86.30

SUFF. RATING

Cobb

Structure ID: 067-0083-0

Location & Geography

* Structure I.D.No:	067-0083-0	* 104 Highway System:	1	Signs & Attachments	
* 200 Bridge Information	06	* 26 Functional Classification:	11	225 Expansion Joint Type:	15
* 6A Feature Int:	NOONDAY CREEK	* 204 Federal Route Type:	1	242 Deck Drains:	1
* 6B Critical Bridge:	0	* 105 Federal Lands Highway:	0	243 Parapet Location:	3
* 7A Route Number Carried:	SR00401	* 110 Truck Route:	1	Height:	2.10
* 7B Facility Carried:	1-75 (NBL)	* 206 School Bus Route:	0	Width:	1.30
* 9 Location:	2.5 MI E OF KENNESAW	* 217 Benchmark Elevation:	0000.00		0.00
* 2 DOT District:	7	* 218 Datum:	0	238 Curb:	0
* 207 Year Photo:	2009	* 19 Bypass Length:	01	239 Handrail:	7
* 91 Inspection Frequency:	24 Date: 04/08/2009	* 20 Toll:	3	* 240 Median Barrier Rail:	0
* 92A Fract Crit Insp Freq:	00 Date: 02/01/1901	* 21 Maintenance:	01	241 Bridge Median Height:	0.00
* 92B Underwater Insp Freq:	00 Date: 02/01/1901	* 22 Owner:	01	Width:	0.00
* 92C Other Spec. Insp Freq:	00 Date: 02/01/1901	* 31 Design Load:	6		
* 4 Place Code:	00000	* 37 Historical Significance:	5	* 230 Guardrail Loc Dir Rear:	3
* 5 Inventory Route (O/U):	1	* 205 Congressional District:	11	Fwd:	2
Type:	1	* 27 Year Constructed:	1975	Oppo Dir Rear:	0
Designation:	1	* 106 Year Reconstructed:	0000	Fwd:	0
Number:	00075	* 33 Bridge Median:	1	244 Approach Slab:	3
Direction:	0	* 34 Skew:	15	224 Retaining Wall:	0
* 16 Latitude:	34-01.2600	* 35 Structure Flared:	0	233 Posted Speed Limit:	65
* 17 Longitude:	84-34.2010	* 38 Navigation Control:	0	236 Warning Sign:	0
* 98 Border Bridge:	000	* 213 Special Steel Design:	0	234 Delineator:	0
* 99 ID Number:	0000000000000000	* 267 Type of Paint:	5	235 Hazard Boards:	0
* 100 STRAHNET:	1	* 42 Type of Service on:	1	237 Utilities Gas:	00
12 Base Highway Network:	1		5	W	00
13A LRS Inventory Route:	671040100	214 Movable Bridge:	0	Ele	22
13B Sub Inventory Route:	0	203 Type Bridge:	O-O-M-O	Telephone:	00
* 101 Parallel Structure:	R	259 Pile Encasement:	3	St	00
* 102 Direction of Traffic:	1	* 43 Structure Type Main:	3	247 Lighting Street:	0
* 264 Road Inventory Mile Post:	012.62	45 No. Spans Main:	003	Naviagation:	0
* 208 Inspection Area:	09	44 Structure Type Appr:	0	Aerial:	0
Engineer's Initial:	sgm	46 No. Spans Appr:	0000		
		226 Bridge Curve Horiz:	1	* 248 County Continuity No.:	00
		111 Pier Protection:	0		
		107 Deck Structure Type:	1		
		108 Wearing Surface Type:	1		
			M		
			F		
			0		
* Location I.D. No.:	067-00401D-270.25N				

BRIDGE INVENTORY DATA LISTING GEOGRAPHIC A DEPARTMENT OF TRANSPORTATION

Structure ID: 067-0083-0

Cobb

SUFF. RATING

86.30

Programming Data

201 Project No.: 1-75-3 (40) 284 CT.5
 202 Plans Available: 4
 249 Prop. Proj. No. 000000000000000000
 250 Approval Status: 0000
 251 P.I. No.: 00000000
 252 Contract Date: 02/01/1901
 260 Seismic No.: 00000
 75 Type Work: 00 0
 94 Bridge Imp. Cost: \$ 0
 95 Roadway Imp. Cost: \$ 0
 96 Total Imp Cost: \$ 0
 76 Imp. Length: 000000
 97 Imp. Year: 0000
 114 Future ADT: 216240 Year: 2027

Measurements

* 29 ADT: 144160 Year: 2007
 109 % Trucks: 0
 * 28 Lanes On: 03 Under: 00
 210 No. Tracks On: 00 Under: 00
 * 48 Max. Span Length: 0082
 * 49 Structure Length: 245
 51 Br. Rwdy. Width: 58.90
 52 Deck Width: 61.30
 * 47 Tot. Horz. Cl: 58.90
 50 Curb/Sdewlk Width: 0.00/0.00
 32 Approach Rdwy Width: 060
 * 229 Shoulder Width:

Rear Lt: 14.00 Type: 1 Rt: 10.00
 Fwd Lt: 14.00 Type: 1 Rt: 10.00
 Pavement Width:

Rear: 36.00 Type: 1
 Fwd: 36.00 Type: 1

Intersection Rear: 0 Fwd: 0
 36 Safety Features Br. Rail:

Transition: 1

App. G. Rail: 1
 App. Rail End: 1
 53 Minimum CLOver: 99 ' 99 "

Under: N
 * 228 Min. Vertical Cl: 00 ' 00 "

Act. Odm Dir: 99 ' 99 "
 Oppo. Dir: 99 ' 99 "
 Posted Odm. Dir: 00 ' 00 "
 Oppo. Dir: 00 ' 00 "

55 Lateral Undercl. Rt: N 0.00
 56 Lateral Undercl. Lt: 0.00

* 10 Max Min Vert Cl: 99 ' 99 " Dir: 0
 39 Nav Vert Cl: 000 Horz: 0000

116 Nav Vert Cl Closed: 000
 245 Deck Thickness Main: 7.00
 Deck Thick Approach: 0.00

246 Overlay Thickness: 0.00
 212 Year Last Painted: Sup: 1994 Sub: 0000

* Location I.D. No.: 067-00401D-270.25N

Ratings

65 Inventory Rating Method: 1
 63 Inventory Rating Method: 1
 66 Inventory Type: 2 Rating: 34
 64 Operating Type: 2 Rating: 58
 231 Calculated Loads
 H-Modified: 21 0
 HS-Modified: 30 0
 Type 3: 33 0
 Type 3s2: 40 0
 Timber: 37 0
 Piggyback: 40 0

261 H Inventory Rating: 37

262 H Operating Rating: 63

67 Structural Evaluation: 7

58 Deck Condition: 7

59 Superstructure Condition: 8

* 227 Collision Damage: 0

60A Substructure Condition: 7

60B Scour Condition: 8

60C Underwater Condition: N

71 Waterway Adequacy: 9

61 Channel Protection Cond: 8

68 Deck Geometry: 7

69 UnderClr. Horz/Vert: N

72 Appr. Alignment: 8

62 Culvert: N

Posting Data

70 Bridge Posting Required: 5

41 Struct Open, Posted, Cl: A

* 103 Temporary Structure: 0

232 Posted Loads H-Modified: 00

HS-Modified: 00

Type 3: 00

Type 3s2: 00

Timber: 00

Piggyback: 00

253 Notification Date 02/01/1901

253 Fed Notify Date: 02/01/1901

0

Hydraulic Data

215 Waterway Data
 Highway Elev.: 0000.0 Year: 1900
 Avg. Streambed Elev.: 0000.0 Freq.: 00
 Drainage Area: 00011
 Area Of Opening: 000975
 113 Scour Critical: 5
 216 Water Depth: 02.2 Br. Height: 30.8
 222 Slope Protection: 1
 221 Spur Dikes Rear: 0 Fwd: 0
 219 Fender System: 0
 220 Dolphin: 0
 223 Culvert Cover: 000
 Type: 0
 No. Barrels: 0
 Width: 0.00 Height: 0.00
 Length: 0 Apron: 0 Diver: ZZZ
 * 265 U/W Insp. Area: 0

GEORGIA DEPARTMENT OF TRANSPORTATION

Bridge Inspection Report

District: 7
 Bridge Inspector: Jerry Cooper
 Location ID: 067-00401D-270.25N
 Structure ID: 067-0083-0

Inspection Date: 4/8/2009
 Over: NOONDAY CREEK
 County: Cobb
 Road Name: I-75 (NBL)

Inspection Area: 09
 Bridge Status: 06

EVALUATION & DEFICIENCIES

SubStructure:

Year Painted: 0000

Concrete Caps At Both Abutments, Founded On Steel H-Piles.
 Minor cracking in both abutment caps.
 Minor settlement at both abutments.
 1 pile exposed at abutment 1 less than 1'.
 Bent 2 And 3 Have Concrete Caps On 3 Concrete Columns, Founded On Spread Footings.
 Very minor spalls on column 3 at bent 2.
 Minor cracking bent 3, right side.
 Bent #3 = H-37 Calculated 2004 by Central Office (Load Factor)

SuperStructure:

Year Painted: 1994

3 Span Steel Beam, (8 W36 X 194 Beams Per Span).
 Square End Cover Plates, (Welded).
 Minor section loss on various bearings, but all have been cleaned and painted.
 Span #2 = H-44 Calculated 2004 by Central Office (Load Factor).

Deck:

7.0" Concrete Slab.
 Minor transverse cracking on the top with some very minor cracking on the bottom.
 The joint in the parapet at bents 2 and 3 are jammed.
 Appears that the joint in the handrail was constructed smaller then the deck joint.
 (This condition caused the spall noted below).
 Minor spall in the left outside handrail parapet at bent 3.
 Inside at bent 2 crack spall.
 Minor settlement of both approach slabs, overlaid with asphalt.
 Deck: H-32 Calculated 2004 by Central Office (Load Factor).

General:

Built in 1975 Project # I-75-3 (40) 284CT. 5
 This structure is in Good Condition with some minor cracking and spalls.
 Hand tools and ladder used.
 Calculations for this structure were determined by the Central Office. - February, 2004.

Condition Rating

Temp Shored: No

Component	Material	Rating	Truck Type	Gross/H-Mod	HSMOD	Tand	3-S-2	Log	Piggy
Substructure	Concrete	7	Calculated Posting	21	30	33	40	37	40
Superstructure	Steel	8	Posting Required	No	No	No	No	No	No
Deck	Concrete	7	Existing Posting	00	00	00	00	00	00

Not a School Bus Route.

Structure Does Not Require Posting

GEORGIA DEPARTMENT OF TRANSPORTATION

Deficiency Report

District: 7 Inspection Date: 4/8/2009 Inspection Area: 09
Bridge Inspector: Jerry Cooper Over: NOONDAY CREEK
Location ID: 067-00401D-270.25N County: Cobb
Structure ID: 067-0083-0 Asst. District Engineer: Shun Pringle

EVALUATION & DEFICIENCIES

I-75 (NBL) Over NOONDAY CREEK-----2.5 MI E OF KENNESAW

Item	Units	Work	P	Date Reported	Location	Date Completed	Complete
800	LIN. FT.	240	B	5/29/2001		12/14/2001	199.00
845	HOURS	20	B	3/15/2005			***
845	HOURS	56	B	3/21/2007		7/10/2007	111.00

Comments:

GEORGIA DEPARTMENT OF TRANSPORTATION

Waterway Report

District: 7
Bridge Inspector: Jerry Cooper
Location ID: 067-00401D-270.25N
Structure ID: 067-0083-0

Inspection Date: 4/8/2009
Over: NOONDAY CREEK
County: Cobb
Road Name: I-75 (NBL)

Inspection Area: 09
Skew: 15

Span #:	1	2	3
Length:	81.5	82.0	81.5

Upstream -					
Upstream +					
08/18/1997	BDH DEM		23.80	26.00	6.10
04/20/1999	DEM		23.80	26.00	6.10
08/05/2003	JMC-WBR		24.00	26.00	6.00
03/15/2005	JMC-WBR		24.10	25.90	6.00
03/21/2007	JMC-WBR		24.40	26.20	6.00
04/08/2009	JMC-WBR		24.20	26.10	6.00

Downstream -					
Downstream +					
08/18/1997	BDH DEM		25.40	26.70	6.40
04/20/1999	DEM		25.40	26.70	6.40
08/05/2003	JMC-WBR		25.50	26.80	6.50
03/15/2005	JMC-WBR		25.70	26.60	6.60
03/21/2007	JMC-WBR		26.20	26.50	6.60
04/08/2009	JMC-WBR		26.40	26.20	6.60


GEORGIA DEPARTMENT OF TRANSPORTATION

Waterway Report


District: 7
 Bridge Inspector: Jerry Cooper
 Location ID: 067-00401D-270.25N
 Structure ID: 067-0083-0

Inspection Date: 4/8/2009
 Over: NOONDAY CREEK
 County: Cobb
 Road Name: I-75 (NBL)

Inspection Area: 09
 Skew: 15



A: 24
 B: 16
 C: 32
 D: 30.8
 E: 02.2
 F: 23
 G: 25
 H: 21
 I: 27
 J: 2
 K: 3



Side view at the Channel.

B, C, H, & I are measured to center of bent or B.F.P.R.

Location of Bridge Height + 28' from bent #2

Scour Condition: 8 Waterway Adequacy: 9 Channel Protection: 8

Comments:

Bridge is super elevated downstream side is the high side.

15 = SubStructure
 0 = Channel Skew
 15 = Stream Angle

GEORGIA DEPARTMENT OF TRANSPORTATION
Bridge Component Report

District: 7

Bridge Inspector: Jerry Cooper

Location ID: 067-00401D-270.25N

Structure ID: 067-0083-0

Inspection Date: 4/8/2009

Over: NOONDAY CREEK

County: Cobb

Road Name: I-75 (NBL)

Inspection Area: 09

SubStructure Data

Bent#	Type	Foundation	Col	#Cols	Piling	#Piles	Sway	CAP	Remarks
1	A	DP		0		0		C	CAP ON STEEL PILE
2	B	SF	C	3		0		C	
3	B	SF	C	3		0		C	
4	A	DP		0		0		C	CAP ON STEEL PILE

SuperStructure Data

Span#	Beam Type	Spacing	Length	#Beams	Remarks
1	Steel Beams	8.50	81.50	8	W36 X 194
2	Steel Beams	8.50	82.00	8	W36 X 194
3	Steel Beams	8.50	81.50	8	W36 X 194

Bearing Data

Span#	Rear Type Bearing	FWD Type Bearing	Remarks
1	02 - Fixed Plate	01 - Sliding Plate	GOOD
2	02 - Fixed Plate	01 - Sliding Plate	GOOD
3	01 - Sliding Plate	02 - Fixed Plate	GOOD

CALCULATION SHEET

PROJECT: I-75 / I-575 NORTHWEST CORRIDOR

JOB NUMBER NH000-0073-03(242)

CALC NO. BR#31

SUBJECT: Bridge Hydraulic Information

BY: JCR

DATE: 11/30/2009

SHEET NO.

SHEET REV.

HYDRAULIC TABLE (50-YEAR STORM)

	<i>UNCONSTRICTED SECTION</i>	<i>EXISTING CONDITIONS</i>	<i>PROPOSED CONDITIONS</i>
FLOODSTAGE ELEVATION BRIDGE SECTION (ft)	941.30	941.59	941.59
FLOODSTAGE ELEVATION APPROACH SECTION (ft)*	946.57	947.06	947.06
AREA OF OPENING UNDER FLOODSTAGE (ft ²)	*****	1382	1382
DISCHARGE THROUGH BRIDGE (cfs)	*****	6003	6003
DISCHARGE OVER ROADWAY (cfs)	*****	0	0
CHANNEL VELOCITY (ft/s)	5.19	7.37	7.37
MEAN VELOCITY (ft/s)	*****	4.34	4.34
2-YEAR FLOODSTAGE ELEVATION BRIDGE SECTION (ft)	937.06	937.19	937.19
BACKWATER HEIGHT (ft)	*****	0.49	0.49

* Approach Section is located upstream of the southbound bridge (Section 1250).

HYDRAULIC TABLE (100-YEAR STORM)

	<i>UNCONSTRICTED SECTION</i>	<i>EXISTING CONDITIONS</i>	<i>PROPOSED CONDITIONS</i>
FLOODSTAGE ELEVATION BRIDGE SECTION (ft)	942.19	942.49	942.49
FLOODSTAGE ELEVATION APPROACH SECTION (ft)*	947.49	947.86	947.86
AREA OF OPENING UNDER FLOODSTAGE (ft ²)	*****	1544	1544
DISCHARGE THROUGH BRIDGE (cfs)	*****	6889	6889
DISCHARGE OVER ROADWAY (cfs)	*****	0	0
CHANNEL VELOCITY (ft/s)	5.27	7.76	7.76
MEAN VELOCITY (ft/s)	*****	4.46	4.46
2-YEAR FLOODSTAGE ELEVATION BRIDGE SECTION (ft)	937.06	937.19	937.19
BACKWATER HEIGHT (ft)	*****	0.37	0.37

* Approach Section is located upstream of the southbound bridge (Section 1250).

HYDRAULIC TABLE (500-YEAR STORM)

	<i>UNCONSTRICTED SECTION</i>	<i>EXISTING CONDITIONS</i>	<i>PROPOSED CONDITIONS</i>
FLOODSTAGE ELEVATION BRIDGE SECTION (ft)	944.02	944.33	944.33
FLOODSTAGE ELEVATION APPROACH SECTION (ft)*	948.96	949.10	949.04
AREA OF OPENING UNDER FLOODSTAGE (ft ²)	*****	1881	1881
DISCHARGE THROUGH BRIDGE (cfs)	*****	8519	8519
DISCHARGE OVER ROADWAY (cfs)	*****	0	0
CHANNEL VELOCITY (ft/s)	5.18	8.18	8.18
MEAN VELOCITY (ft/s)	*****	4.53	4.53
2-YEAR FLOODSTAGE ELEVATION BRIDGE SECTION (ft)	937.06	937.19	937.19
BACKWATER HEIGHT (ft)	*****	0.14	0.08

* Approach Section is located upstream of the southbound bridge (Section 1250).

NH000-0073-03(242) Cobb County
I-75 over Noonday Creek

Proposed widened bridges

MIN PROFILE GRADE ELEVATION	949.85
DEPTH OF CROSS SLOPE	0.84
DEPTH OF SLAB AND BEAM	5.06

BOTTOM OF BEAM ELEVATION	943.95
--------------------------	--------

MINIMUM BOTTOM OF BEAM ELEVATION	943.95
50 YEAR FLOODSTAGE ELEVATION*	941.59

CLEARANCE	2.36
-----------	------

MINIMUM BOTTOM OF BEAM ELEVATION	943.95
100 YEAR FLOODSTAGE ELEVATION*	942.49

CLEARANCE	1.46
-----------	------

*Floodstage taken from proposed conditions model.